

# CC1100

# Low-Power Sub- 1 GHz RF Transceiver

# **Applications**

- Ultra low-power wireless applications operating in the 315/433/868/915 MHz ISM/SRD bands
- Wireless alarm and security systems
- Industrial monitoring and control

- Wireless sensor networks
- AMR Automatic Meter Reading
- Home and building automation


# **Product Description**

The *CC1100* is a low-cost sub- 1 GHz transceiver designed for very low-power wireless applications. The circuit is mainly intended for the ISM (Industrial, Scientific and Medical) and SRD (Short Range Device) frequency bands at 315, 433, 868, and 915 MHz, but can easily be programmed for operation at other frequencies in the 300-348 MHz, 400-464 MHz and 800-928 MHz bands.

The RF transceiver is integrated with a highly configurable baseband modem. The modem supports various modulation formats and has a configurable data up to 500 kBaud.

*CC1100* provides extensive hardware support for packet handling, data buffering, burst transmissions, clear channel assessment, link quality indication, and wake-on-radio.

The main operating parameters and the 64-byte transmit/receive FIFOs of *CC1100* can be controlled via an SPI interface. In a typical system, the *CC1100* will be used together with a microcontroller and a few additional passive components.



This product shall not be used in any of the following products or systems without prior express written permission from Texas Instruments:

- (i) implantable cardiac rhythm management systems, including without limitation pacemakers, defibrillators and cardiac resynchronization devices,
- (ii) external cardiac rhythm management systems that communicate directly with one or more implantable medical devices; or
- (iii) other devices used to monitor or treat cardiac function, including without limitation pressure sensors, biochemical sensors and neurostimulators.

Please contact lpw-medical-approval @list.ti.com if your application might fall within the category described above.



SWRS038D Page 1 of 92



# **Key Features**

#### **RF Performance**

- High sensitivity (-111 dBm at 1.2 kBaud, 868 MHz, 1% packet error rate)
- Low current consumption (14.4 mA in RX, 1.2 kBaud, 868 MHz)
- Programmable output power up to +10 dBm for all supported frequencies
- Excellent receiver selectivity and blocking performance
- Programmable data rate from 1.2 to 500 kBaud
- Frequency bands: 300-348 MHz, 400-464 MHz and 800-928 MHz

# **Analog Features**

- 2-FSK, GFSK, and MSK supported as well as OOK and flexible ASK shaping
- Suitable for frequency hopping systems due to a fast settling frequency synthesizer: 90us settling time
- Automatic Frequency Compensation (AFC) can be used to align the frequency synthesizer to the received centre frequency
- Integrated analog temperature sensor

# **Digital Features**

- Flexible support for packet oriented systems: On-chip support for sync word detection, address check, flexible packet length, and automatic CRC handling
- Efficient SPI interface: All registers can be programmed with one "burst" transfer
- Digital RSSI output
- Programmable channel filter bandwidth
- Programmable Carrier Sense (CS) indicator

- Programmable Preamble Quality Indicator (PQI) for improved protection against false sync word detection in random noise
- Support for automatic Clear Channel Assessment (CCA) before transmitting (for listen-before-talk systems)
- Support for per-package Link Quality Indication (LQI)
- Optional automatic whitening and dewhitening of data

### **Low-Power Features**

- 400nA SLEEP mode current consumption
- Fast startup time: 240us from sleep to RX or TX mode (measured on EM reference design [5] and [6])
- Wake-on-radio functionality for automatic low-power RX polling
- Separate 64-byte RX and TX data FIFOs (enables burst mode data transmission)

### General

- Few external components: Completely onchip frequency synthesizer, no external filters or RF switch needed
- Green package: RoHS compliant and no antimony or bromine
- Small size (QLP 4x4 mm package, 20 pins)
- Suited for systems targeting compliance with EN 300 220 (Europe) and FCC CFR Part 15 (US).
- Support for asynchronous and synchronous serial receive/transmit mode for backwards compatibility with existing radio communication protocols



SWRS038D Page 2 of 92



# **Abbreviations**

Abbreviations used in this data sheet are described below.

ACP	Adjacent Channel Power	MSK	Minimum Shift Keying
ADC	Analog to Digital Converter	N/A	Not Applicable
AFC	Automatic Frequency Compensation	NRZ	Non Return to Zero (Coding)
AGC	Automatic Gain Control	OOK	On-Off Keying
AMR	Automatic Meter Reading	PA	Power Amplifier
ASK	Amplitude Shift Keying	PCB	Printed Circuit Board
BER	Bit Error Rate	PD	Power Down
BT	Bandwidth-Time product	PER	Packet Error Rate
CCA	Clear Channel Assessment	PLL	Phase Locked Loop
CFR	Code of Federal Regulations	POR	Power-On Reset
CRC	Cyclic Redundancy Check	PQI	Preamble Quality Indicator
CS	Carrier Sense	PQT	Preamble Quality Threshold
CW	Continuous Wave (Unmodulated Carrier)	PTAT	Proportional To Absolute Temperature
DC	Direct Current	QLP	Quad Leadless Package
DVGA	Digital Variable Gain Amplifier	QPSK	Quadrature Phase Shift Keying
ESR	Equivalent Series Resistance	RC	Resistor-Capacitor
FCC	Federal Communications Commission	RF	Radio Frequency
FEC	Forward Error Correction	RSSI	Received Signal Strength Indicator
FIFO	First-In-First-Out	RX	Receive, Receive Mode
FHSS	Frequency Hopping Spread Spectrum	SAW	Surface Aqustic Wave
2-FSK	Binary Frequency Shift Keying	SMD	Surface Mount Device
GFSK	Gaussian shaped Frequency Shift Keying	SNR	Signal to Noise Ratio
IF	Intermediate Frequency	SPI	Serial Peripheral Interface
I/Q	In-Phase/Quadrature	SRD	Short Range Devices
ISM	Industrial, Scientific, Medical	TBD	To Be Defined
LC	Inductor-Capacitor	T/R	Transmit/Receive
LNA	Low Noise Amplifier	TX	Transmit, Transmit Mode
LO	Local Oscillator	UHF	Ultra High frequency
LSB	Least Significant Bit	VCO	Voltage Controlled Oscillator
LQI	Link Quality Indicator	WOR	Wake on Radio, Low power polling
MCU	Microcontroller Unit	XOSC	Crystal Oscillator
MSB	Most Significant Bit	XTAL	Crystal



SWRS038D Page 3 of 92




# **Table Of Contents**

APPL	JCATIONS	1
PROI	DUCT DESCRIPTION	1
KEY	FEATURES	2
RF PI	ERFORMANCE	2
ANAI	LOG FEATURES	2
DIGI	TAL FEATURES	2
	-POWER FEATURES	
	ERAL	
	REVIATIONS	
	LE OF CONTENTS	
1	ABSOLUTE MAXIMUM RATINGS	
2	OPERATING CONDITIONS	
	GENERAL CHARACTERISTICS	
3	ELECTRICAL SPECIFICATIONS	
<b>4</b> 4.1	CURRENT CONSUMPTION	
4.2	RF RECEIVE SECTION	
4.3	RF Transmit Section	13
4.4	CRYSTAL OSCILLATOR	
4.5	Low Power RC Oscillator	
4.6 4.7	FREQUENCY SYNTHESIZER CHARACTERISTICS	
4.8	DC CHARACTERISTICS	
4.9	POWER-ON RESET	
5	PIN CONFIGURATION	17
6	CIRCUIT DESCRIPTION	18
7	APPLICATION CIRCUIT	19
8	CONFIGURATION OVERVIEW	22
9	CONFIGURATION SOFTWARE	24
10	4-WIRE SERIAL CONFIGURATION AND DATA INTERFACE	24
10.1	CHIP STATUS BYTE	26
10.2	REGISTER ACCESS	
10.3 10.4	SPI READ COMMAND STROBES	
10.4	FIFO Access	
10.6	PATABLE Access	
11	MICROCONTROLLER INTERFACE AND PIN CONFIGURATION	28
11.1	CONFIGURATION INTERFACE	28
11.2	GENERAL CONTROL AND STATUS PINS	
11.3	OPTIONAL RADIO CONTROL FEATURE	
12	DATA RATE PROGRAMMING	
13	RECEIVER CHANNEL FILTER BANDWIDTH	
14	DEMODULATOR, SYMBOL SYNCHRONIZER, AND DATA DECISION	30
14.1 14.2	Frequency Offset Compensation	
14.3	BYTE SYNCHRONIZATION	
15	PACKET HANDLING HARDWARE SUPPORT	
15.1	Data Whitening	31
15.2	D. Gyrpp Constant	22
	PACKET FORMAT	
15.3	PACKET FILTERING IN RECEIVE MODE	34
15.3 15.4 15.5		34 34



15.6	PACKET HANDLING IN FIRMWARE	35
16	MODULATION FORMATS	36
16.1	Frequency Shift Keying	
16.2	MINIMUM SHIFT KEYING	
16.3	AMPLITUDE MODULATION	
17	RECEIVED SIGNAL QUALIFIERS AND LINK QUALITY INFORMATION	
17.1	SYNC WORD QUALIFIER.	37
17.2	PREAMBLE QUALITY THRESHOLD (PQT)	
17.3	RSSI	
17.4 17.5	CLEAR CHANNEL ASSESSMENT (CCA)	
17.6	LINK QUALITY INDICATOR (LQI)	
18	FORWARD ERROR CORRECTION WITH INTERLEAVING	
18.1	FORWARD ERROR CORRECTION (FEC)	
18.2	Interleaving	
19	RADIO CONTROL	
19.1	POWER-ON START-UP SEQUENCE	
19.2	CRYSTAL CONTROL	
19.3	VOLTAGE REGULATOR CONTROL	
19.4	ACTIVE MODES	
19.5	WAKE ON RADIO (WOR)	
19.6	TIMING	
19.7	RX TERMINATION TIMER	
20	DATA FIFO	
21	FREQUENCY PROGRAMMING	
22	VCO	
22.1	VCO AND PLL SELF-CALIBRATION	
23	VOLTAGE REGULATORS	49
24	OUTPUT POWER PROGRAMMING	49
25	SHAPING AND PA RAMPING	50
26	SELECTIVITY	52
27	CRYSTAL OSCILLATOR	
27.1	REFERENCE SIGNAL	
28	EXTERNAL RF MATCH	54
29	PCB LAYOUT RECOMMENDATIONS	
30	GENERAL PURPOSE / TEST OUTPUT CONTROL PINS	
<b>31</b> 31.1	ASYNCHRONOUS AND SYNCHRONOUS SERIAL OPERATION	
31.1	SYNCHRONOUS SERIAL OPERATION	
32	SYSTEM CONSIDERATIONS AND GUIDELINES	
32.1	SRD REGULATIONS	
32.2	FREQUENCY HOPPING AND MULTI-CHANNEL SYSTEMS	
32.3	WIDEBAND MODULATION NOT USING SPREAD SPECTRUM	58
32.4	Data Burst Transmissions	58
32.5	CONTINUOUS TRANSMISSIONS	
32.6	CRYSTAL DRIFT COMPENSATION	
32.7 32.8	SPECTRUM EFFICIENT MODULATION	
32.8	BATTERY OPERATED SYSTEMS	
32.10	INCREASING OUTPUT POWER	
33	CONFIGURATION REGISTERS	
33.1	CONFIGURATION REGISTERS  CONFIGURATION REGISTER DETAILS – REGISTERS WITH PRESERVED VALUES IN SLEEP STATE	
33.2	CONFIGURATION REGISTER DETAILS - REGISTERS THAT LOSE PROGRAMMING IN SLEEP STATE	
33.3	STATUS REGISTER DETAILS	





34	PACKAGE DESCRIPTION (OLP 20)	88
34.1	RECOMMENDED PCB LAYOUT FOR PACKAGE (QLP 20)	88
	SOLDERING INFORMATION	
35	ORDERING INFORMATION	89
36	REFERENCES	90
37	GENERAL INFORMATION	91
	DOCUMENT HISTORY	





# 1 Absolute Maximum Ratings

Under no circumstances must the absolute maximum ratings given in Table 1 be violated. Stress exceeding one or more of the limiting values may cause permanent damage to the device.



**Caution!** ESD sensitive device. Precaution should be used when handling the device in order to prevent permanent damage.

Parameter	Min	Max	Units	Condition
Supply voltage	-0.3	3.9	V	All supply pins must have the same voltage
Voltage on any digital pin	-0.3	VDD+0.3	V	
		max 3.9		
Voltage on the pins RF_P, RF_N, and DCOUPL	-0.3	2.0	V	
Voltage ramp-up rate		120	kV/µs	
Input RF level		+10	dBm	
Storage temperature range	-50	150	°C	
Solder reflow temperature		260	°C	According to IPC/JEDEC J-STD-020C
ESD		<500	V	According to JEDEC STD 22, method A114, Human Body Model

**Table 1: Absolute Maximum Ratings** 

# 2 Operating Conditions

The operating conditions for *CC1100* are listed Table 2 in below.

Parameter	Min	Max	Unit	Condition
Operating temperature	-40	85	°C	
Operating supply voltage	1.8	3.6	V	All supply pins must have the same voltage

**Table 2: Operating Conditions** 

# 3 General Characteristics

Parameter	Min	Тур	Max	Unit	Condition/Note
Frequency range	300		348	MHz	
	400		464	MHz	
	800		928	MHz	
Data rate	1.2		500	kBaud	2-FSK
	1.2		250	kBaud	GFSK, OOK, and ASK
	26		500	kBaud	(Shaped) MSK (also known as differential offset QPSK)
					Optional Manchester encoding (the data rate in kbps will be half the baud rate)

**Table 3: General Characteristics** 



SWRS038D Page 7 of 92



# 4 Electrical Specifications

# 4.1 Current Consumption


 $Tc = 25^{\circ}C$ , VDD = 3.0V if nothing else stated. All measurement results are obtained using the CC1100EM reference designs ([5] and [6]).

Reduced current settings (MDMCFG2.DEM\_DCFILT\_OFF=1) gives a slightly lower current consumption at the cost of a reduction in sensitivity. See Table 5 for additional details on current consumption and sensitivity.

Parameter	Min	Тур	Max	Unit	Condition
Current consumption in power down modes		400		nA	Voltage regulator to digital part off, register values retained (SLEEP state). All GDO pins programmed to 0x2F (HW to 0)
		900		nA	Voltage regulator to digital part off, register values retained, low-power RC oscillator running (SLEEP state with WOR enabled
		95		μА	Voltage regulator to digital part off, register values retained, XOSC running (SLEEP state with MCSM0.OSC_FORCE_ON set)
		160		μА	Voltage regulator to digital part on, all other modules in power down (XOFF state)
Current consumption		9.8		μΑ	Automatic RX polling once each second, using low-power RC oscillator, with 460 kHz filter bandwidth and 250 kBaud data rate, PLL calibration every 4 <sup>th</sup> wakeup. Average current with signal in channel <i>below</i> carrier sense level (MCSM2.RX_TIME_RSSI=1).
		34.2		μΑ	Same as above, but with signal in channel <i>above</i> carrier sense level, 1.95 ms RX timeout, and no preamble/sync word found.
		1.5		μА	Automatic RX polling every 15 <sup>th</sup> second, using low-power RC oscillator, with 460kHz filter bandwidth and 250 kBaud data rate, PLL calibration every 4 <sup>th</sup> wakeup. Average current with signal in channel below carrier sense level (MCSM2.RX_TIME_RSSI=1).
		39.3		μА	Same as above, but with signal in channel <i>above</i> carrier sense level, 29.3 ms RX timeout, and no preamble/sync word found.
		1.6		mA	Only voltage regulator to digital part and crystal oscillator running (IDLE state)
		8.2		mA	Only the frequency synthesizer is running (FSTXON state). This currents consumption is also representative for the other intermediate states when going from IDLE to RX or TX, including the calibration state.
Current consumption, 315MHz		15.1		mA	Receive mode, 1.2 kBaud, reduced current, input at sensitivity limit
		13.9		mA	Receive mode, 1.2 kBaud, reduced current, input well above sensitivity limit
		14.9		mA	Receive mode, 38.4 kBaud, reduced current, input at sensitivity limit
		14.1		mA	Receive mode,38.4 kBaud, reduced current, input well above sensitivity limit
		15.9		mA	Receive mode, 250 kBaud, reduced current, input at sensitivity limit
		14.5		mA	Receive mode, 250 kBaud, reduced current, input well above sensitivity limit
		27.0		mA	Transmit mode, +10 dBm output power
		14.8		mA	Transmit mode, 0 dBm output power
		12.3		mA	Transmit mode, –6 dBm output power



SWRS038D Page 8 of 92



Parameter	Min	Тур	Max	Unit	Condition
Current consumption, 433MHz		15.5		mA	Receive mode, 1.2 kBaud , reduced current, input at sensitivity limit
		14.5		mA	Receive mode, 1.2 kBaud , reduced current, input well above sensitivity limit
		15.4		mA	Receive mode, 38.4 kBaud , reduced current, input at sensitivity limit
		14.4		mA	Receive mode, 38.4 kBaud , reduced current, input well above sensitivity limit
		16.5		mA	Receive mode, 250 kBaud , reduced current, input at sensitivity limit
		15.2		mA	Receive mode, 250 kBaud , reduced current, input well above sensitivity limit
		28.9		mA	Transmit mode, +10 dBm output power
		15.5		mA	Transmit mode, 0 dBm output power
		13.1		mA	Transmit mode, –6 dBm output power
Current consumption, 868/915MHz		15.4		mA	Receive mode, 1.2 kBaud , reduced current, input at sensitivity limit
		14.4		mA	Receive mode, 1.2 kBaud , reduced current, input well above sensitivity limit
		15.2		mA	Receive mode, 38.4 kBaud , reduced current, input at sensitivity limit
		14.4		mA	Receive mode,38.4 kBaud , reduced current, input well above sensitivity limit
		16.4		mA	Receive mode, 250 kBaud , reduced current, input at sensitivity limit
		15.1		mA	Receive mode, 250 kBaud , reduced current, input well above sensitivity limit
		31.1		mA	Transmit mode, +10 dBm output power
		16.9		mA	Transmit mode, 0 dBm output power
		13.5		mA	Transmit mode, –6 dBm output power

**Table 4: Electrical Specifications** 

# 4.2 RF Receive Section

 $Tc = 25^{\circ}C$ , VDD = 3.0V if nothing else stated. All measurement results are obtained using the CC1100EM reference designs ([5] and [6]).

Parameter	Min	Тур	Max	Unit	Condition/Note		
Digital channel filter bandwidth	58		812	kHz	User programmable. The bandwidth limits are proportional to crystal frequency (given values assume a 26.0 MHz crystal).		
315 MHz, 1.2 kBaud data rate, sensitivity optimized, MDMCFG2.DEM_DCFILT_OFF=0 (2-FSK, 1% packet error rate, 20 bytes packet length, 5.2 kHz deviation, 58 kHz digital channel filter bandwidth)							
Receiver sensitivity		-111		dBm	Sensitivity can be traded for current consumption by setting MDMCFG2 .DEM_DCFILT_OFF=1. The typical current consumption is then reduced from 17.1 mA to 15.1 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm		
315 MHz, 500 kBaud data rate, sensitivity optimized, MDMCFG2.DEM_DCFILT_OFF=0 (MDMCFG2.DEM_DCFILT_OFF=1 cannot be used for data rates > 250 kBaud) (MSK, 1% packet error rate, 20 bytes packet length, 812 kHz digital channel filter bandwidth)							
		-88		dBm			



SWRS038D Page 9 of 92



Parameter	Min	Тур	Max	Unit	Condition/Note
,	,		, .	•	MCFG2.DEM_DCFILT_OFF=0
· · ·	or rate, 20	–110	acket lenç I		Hz deviation, 58 kHz digital channel filter bandwidth
Receiver sensitivity		-110		dBm	Sensitivity can be traded for current consumption by setting MDMCFG2.DEM_DCFILT_OFF=1. The typical current consumption is then reduced from 17.4 mA to 15.5 mA at sensitivity limit. The sensitivity is typically reduced to -108 dBm
*		•		•	DMCFG2.DEM_DCFILT_OFF=0 Hz deviation, 100 kHz digital channel filter bandwidth)
Receiver sensitivity		-103		dBm	
					MCFG2.DEM_DCFILT_OFF=0 Hz digital channel filter bandwidth)
Receiver sensitivity		-94		dBm	
cannot be used for data	a rates > :	250 kΒaι	ıd)		MCFG2.DEM_DCFILT_OFF=0 (MDMCFG2.DEM_DCFILT_OFF=1  Hz digital channel filter bandwidth)
Receiver sensitivity		-88		dBm	
			I		
					MCFG2.DEM_DCFILT_OFF=0 Hz deviation, 58 kHz digital channel filter bandwidth)
Receiver sensitivity		<b>–111</b>		dBm	Sensitivity can be traded for current consumption by setting MDMCFG2.DEM_DCFILT_OFF=1. The typical current consumption is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm
Saturation		-15		dBm	
Adjacent channel rejection		33		dB	Desired channel 3 dB above the sensitivity limit. 100 kHz channel spacing
Alternate channel rejection		33		dB	Desired channel 3 dB above the sensitivity limit. 100 kHz channel spacing
					See Figure 25 for plot of selectivity versus frequency offset
Image channel		30		dB	IF frequency 152 kHz
rejection, 868MHz					Desired channel 3 dB above the sensitivity limit.
868 MHz, 38.4 kBaud (2-FSK, 1% packet erro			acket lenç	gth, 20 kl	Hz deviation, 100 kHz digital channel filter bandwidth)
Receiver sensitivity		-103		dBm	
Saturation		-16		dBm	
Adjacent channel rejection		20		dB	Desired channel 3 dB above the sensitivity limit. 200 kHz channel spacing
Alternate channel rejection		28		dB	Desired channel 3 dB above the sensitivity limit. 200 kHz channel spacing
					See Figure 26 for plot of selectivity versus frequency offset
Image channel		23		dB	IF frequency 152 kHz
rejection, 868MHz					Desired channel 3 dB above the sensitivity limit.





	Min	Тур	Max	Unit	Condition/Note
					MDMCFG2.DEM_DCFILT_OFF=0 kHz digital channel filter bandwidth)
Receiver sensitivity	Torrace, 2	-93	Packet lei	dBm	Sensitivity can be traded for current consumption by setting MDMCFG2.DEM_DCFILT_OFF=1. The typical current consumption is then reduced from 18.8 mA to 16.4 mA at sensitivity limit. The sensitivity is typically reduced to -91 dBm
Saturation		-16		dBm	
Adjacent channel rejection		24		dB	Desired channel 3 dB above the sensitivity limit. 750 kHz channel spacing
Alternate channel rejection		37		dB	Desired channel 3 dB above the sensitivity limit. 750 kHz channel spacing
•					See Figure 27 for plot of selectivity versus frequency offset
Image channel		14		dB	IF frequency 254 kHz
rejection, 868MHz					Desired channel 3 dB above the sensitivity limit.
cannot be used for	data rates	s > 250 k	Baud)		<pre>MDMCFG2.DEM_DCFILT_OFF=0 (MDMCFG2.DEM_DCFILT_OFF=1</pre> <pre>2 kHz digital channel filter bandwidth)</pre>
Receiver sensitivity		-88		dBm	
					MDMCFG2.DEM_DCFILT_OFF=0 kHz digital channel filter bandwidth)
Receiver sensitivity		-86		dBm	
					MDMCFG2.DEM_DCFILT_OFF=0 s packet length, 58 kHz digital channel filter bandwidth)
Receiver sensitivity		<b>–111</b>		dBm	Sensitivity can be traded for current consumption by setting MDMCFG2.DEM DCFILT OFF=1. The typical current consumption
					is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm
					is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The
					is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm  MDMCFG2.DEM_DCFILT_OFF=0
(2-FSK, 1% packet Receiver sensitivity 915 MHz, 250 kBa	error rate	, 20 bytes -104 rate, sens	s packet le	dBm otimized,	is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm  MDMCFG2.DEM_DCFILT_OFF=0
(2-FSK, 1% packet Receiver sensitivity 915 MHz, 250 kBa	error rate	, 20 bytes -104 rate, sens	s packet le	dBm otimized,	is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm  I, MDMCFG2.DEM_DCFILT_OFF=0  I kHz deviation, 100 kHz digital channel filter bandwidth)  MDMCFG2.DEM_DCFILT_OFF=0
(2-FSK, 1% packet Receiver sensitivity  915 MHz, 250 kBa (MSK, 1% packet el Receiver sensitivity  915 MHz, 500 kBa cannot be used for	ud data r rror rate, 2  ud data r data rates	20 bytes  -104  ate, sens 20 bytes  -93  ate, sens 5 > 250 k	sitivity oppositivity oppositiv	dBm  otimized, ngth, 540  dBm	is then reduced from 17.7 mA to 15.4 mA at sensitivity limit. The sensitivity is typically reduced to -109 dBm  1, MDMCFG2.DEM_DCFILT_OFF=0  2 kHz deviation, 100 kHz digital channel filter bandwidth)  MDMCFG2.DEM_DCFILT_OFF=0 kHz digital channel filter bandwidth)  Sensitivity can be traded for current consumption by setting MDMCFG2.DEM_DCFILT_OFF=1. The typical current consumption is then reduced from 18.8 mA to 16.4 mA at sensitivity limit. The




SWRS038D Page 11 of 92



Parameter	Min	Тур	Max	Unit	Condition/Note
Blocking					
Blocking at ±2 MHz offset,		-53		dBm	Desired channel 3dB above the sensitivity limit. Compliant
1.2 kBaud, 868 MHz					with ETSI EN 300 220 class 2 receiver requirement.
Blocking at ±2 MHz offset,		-51		dBm	Desired channel 3dB above the sensitivity limit. Compliant
500 kBaud, 868 MHz					with ETSI EN 300 220 class 2 receiver requirement.
Blocking at ±10 MHz offset, 1.2 kBaud, 868 MHz		-43		dBm	Desired channel 3dB above the sensitivity limit. Compliant
					with ETSI EN 300 220 class 2 receiver requirement.
Blocking at ±10 MHz offset,		-43		dBm	Desired channel 3dB above the sensitivity limit. Compliant
500 kBaud, 868 MHz					with ETSI EN 300 220 class 2 receiver requirement.
General					
Spurious emissions		-68	<b>–</b> 57	dBm	25 MHz – 1 GHz (Maximum figure is the ETSI EN 300 220 limit)
		-66	<b>–47</b>	dBm	Above 1 GHz (Maximum figure is the ETSI EN 300 220 limit)
RX latency		9		bit	Serial operation. Time from start of reception until data is available on the receiver data output pin is equal to 9 bit.

**Table 5: RF Receive Section** 






# 4.3 RF Transmit Section

Tc = 25°C, VDD = 3.0V, +10dBm if nothing else stated. All measurement results are obtained using the CC1100EM reference designs ([5] and [6]).

Parameter	Min	Тур	Max	Unit	Condition/Note
Differential load impedance					Differential impedance as seen from the RF-port (RF_P and RF_N) towards the antenna. Follow the CC1100EM reference design ([5] and [6]) available from theTI website.
315 MHz		122 + j31		Ω	acoign ([o] and [o]) available normalien mesone.
433 MHz		116 + j41			
868/915 MHz		86.5 + j43			
Output power, highest setting		+10		dBm	Output power is programmable, and full range is available in all frequency bands (Output power may be restricted by regulatory limits. See also Application Note AN039 [3].
					Delivered to a $50\Omega$ single-ended load via CC1100EM reference design ([5] and [6]) RF matching network.
Output power, lowest setting		-30		dBm	Output power is programmable, and full range is available in all frequency bands.
					Delivered to a $50\Omega$ single-ended load via CC1100EM reference design([5] and [6]) RF matching network.
Harmonics, radiated					Measured on CC1100EM reference designs([5] and [6]) with CW, 10 dBm output power
2 <sup>nd</sup> Harm, 433 MHz 3 <sup>rd</sup> Harm, 433 MHz		-50 -40		dBm	The antennas used during the radiated measurements (SMAFF-433 from R.W.Badland and Nearson S331 868/915) plays a part
2 <sup>nd</sup> Harm, 868 MHz 3 <sup>rd</sup> Harm, 868 MHz		-34 -45			in attenuating the harmonics
Harmonics, conducted					Measured with 10 dBm CW, TX frequency at 315.00 MHz, 433.00 MHz, 868.00 MHz, or 915.00 MHz
315 MHz		< -33 < -38		dBm	Frequencies below 960 MHz Frequencies above 960 MHz
433 MHz		< -51 < -34			Frequencies below 1 GHz Frequencies above 1 GHz
868 MHz		< -32			
915 MHz		< -30			





Spurious emissions, conducted Harmonics not included			Measured with 10 dBm CW, TX frequency at 315.00 MHz, 433.00 MHz, 868.00 MHz or 915.00 MHz
315 MHz	< -58 < -53	dBm	Frequencies below 960 MHz Frequencies above 960 MHz
433 MHz	< -50 < -54 < -56		Frequencies below 1 GHz Frequencies above 1 GHz Frequencies within 47-74, 87.5-118, 174-230, 470-862 MHz
868 MHz	< -50 < -51 < -53		Frequencies below 1 GHz Frequencies above 1 GHz Frequencies within 47-74, 87.5-118, 174-230, 470-862 MHz.  The peak conducted spurious emission is -53dBm @ 699 MHz, which is in an EN300220 restricted band limited to -54dBm. All radiated spurious emissions are within the limits of ETSI.
915 MHz	< -51 < -51		Frequencies below 960 MHz Frequencies above 960 MHz
General	·		
TX latency	8	bit	Serial operation. Time from sampling the data on the transmitter data input DIO pin until it is observed on the RF output ports.

**Table 6: RF Transmit Section** 

# 4.4 Crystal Oscillator

Tc =  $25^{\circ}$ C @ VDD = 3.0 V if nothing else is stated.

Parameter	Min	Тур	Max	Unit	Condition/Note
Crystal frequency	26	26	27	MHz	
Tolerance		±40		ppm	This is the total tolerance including a) initial tolerance, b) crystal loading, c) aging, and d) temperature dependence.  The acceptable crystal tolerance depends on RF frequency and channel spacing / bandwidth.
ESR			100	Ω	
Start-up time		150		μs	Measured on the CC1100EM reference designs ([5] and [6]) using crystal AT-41CD2 from NDK.  This parameter is to a large degree crystal dependent.

**Table 7: Crystal Oscillator Parameters** 





# 4.5 Low Power RC Oscillator

 $Tc = 25^{\circ}C$ , VDD = 3.0 V if nothing else is stated. All measurement results obtained using the CC1100EM reference designs ([5] and [6]).

Parameter	Min	Тур	Max	Unit	Condition/Note
Calibrated frequency	34.7	34.7	36	kHz	Calibrated RC Oscillator frequency is XTAL frequency divided by 750
Frequency accuracy after calibration			±1	%	
Temperature coefficient		+0.5		% / °C	Frequency drift when temperature changes after calibration
Supply voltage coefficient		+3		% / V	Frequency drift when supply voltage changes after calibration
Initial calibration time		2		ms	When the RC Oscillator is enabled, calibration is continuously done in the background as long as the crystal oscillator is running.

**Table 8: RC Oscillator Parameters** 

# 4.6 Frequency Synthesizer Characteristics

 $Tc = 25^{\circ}C$  @ VDD = 3.0 V if nothing else is stated. All measurement results are obtained using the CC1100EM reference designs ([5] and [6]). Min figures are given using a 27 MHz crystal. Typ and max are given using a 26 MHz crystal.

Parameter	Min	Тур	Max	Unit	Condition/Note
Programmed frequency	397	F <sub>XOSC</sub> /	412	Hz	26-27 MHz crystal.
resolution		2.0			The resolution (in Hz) is equal for all frequency bands.
Synthesizer frequency tolerance		±40		ppm	Given by crystal used. Required accuracy (including temperature and aging) depends on frequency band and channel bandwidth / spacing.
RF carrier phase noise		-89		dBc/Hz	@ 50 kHz offset from carrier
RF carrier phase noise		-89		dBc/Hz	@ 100 kHz offset from carrier
RF carrier phase noise		-90		dBc/Hz	@ 200 kHz offset from carrier
RF carrier phase noise		-98		dBc/Hz	@ 500 kHz offset from carrier
RF carrier phase noise		-107		dBc/Hz	@ 1 MHz offset from carrier
RF carrier phase noise		-113		dBc/Hz	@ 2 MHz offset from carrier
RF carrier phase noise		-119		dBc/Hz	@ 5 MHz offset from carrier
RF carrier phase noise		-129		dBc/Hz	@ 10 MHz offset from carrier
PLL turn-on / hop time	85.1	88.4	88.4	μs	Time from leaving the IDLE state until arriving in the RX, FSTXON or TX state, when not performing calibration. Crystal oscillator running.
PLL RX/TX settling time	9.3	9.6	9.6	μs	Settling time for the 1·IF frequency step from RX to TX
PLL TX/RX settling time	20.7	21.5	21.5	μs	Settling time for the 1·IF frequency step from TX to RX
PLL calibration time	694	721	721	μs	Calibration can be initiated manually or automatically before entering or after leaving RX/TX.

**Table 9: Frequency Synthesizer Parameters** 





# 4.7 Analog Temperature Sensor

The characteristics of the analog temperature sensor at 3.0 V supply voltage are listed in Table 10 below. Note that it is necessary to write 0xBF to the PTEST register to use the analog temperature sensor in the IDLE state.

Parameter	Min	Тур	Max	Unit	Condition/Note
Output voltage at –40°C		0.651		V	
Output voltage at 0°C		0.747		V	
Output voltage at +40°C		0.847		٧	
Output voltage at +80°C		0.945		V	
Temperature coefficient		2.45		mV/°C	Fitted from –20 °C to +80 °C
Error in calculated temperature, calibrated	-2 <sup>*</sup>	0	2 *	°C	From –20 °C to +80 °C when using 2.45 mV / °C, after 1-point calibration at room temperature  The indicated minimum and maximum error with 1-point calibration is based on simulated values for typical process parameters
Current consumption increase when enabled		0.3		mA	

**Table 10: Analog Temperature Sensor Parameters** 

#### 4.8 DC Characteristics

Tc = 25°C if nothing else stated.

Digital Inputs/Outputs	Min	Max	Unit	Condition
Logic "0" input voltage	0	0.7	V	
Logic "1" input voltage	VDD-0.7	VDD	٧	
Logic "0" output voltage	0	0.5	V	For up to 4 mA output current
Logic "1" output voltage	VDD-0.3	VDD	V	For up to 4 mA output current
Logic "0" input current	N/A	-50	nA	Input equals 0V
Logic "1" input current	N/A	50	nA	Input equals VDD

**Table 11: DC Characteristics** 

### 4.9 Power-On Reset


When the power supply complies with the requirements in Table 12 below, proper Power-On-Reset functionality is guaranteed. Otherwise, the chip should be assumed to have unknown state until transmitting an SRES strobe over the SPI interface. See Section 19.1 on page 42 for further details.

Parameter	Min	Тур	Max	Unit	Unit Condition/Note	
Power-up ramp-up time.			5	ms	From 0V until reaching 1.8V	
Power off time	1			ms	Minimum time between power-on and power-off	

**Table 12: Power-On Reset Requirements** 



# 5 Pin Configuration



**Figure 1: Pinout Top View** 

Note: The exposed die attach pad **must** be connected to a solid ground plane as this is the main ground connection for the chip.

Pin#	Pin Name	Pin type	Description
1	SCLK	Digital Input	Serial configuration interface, clock input
2	SO (GDO1)	Digital Output	Serial configuration interface, data output.
			Optional general output pin when CSn is high
3	GDO2	Digital Output	Digital output pin for general use:
			Test signals
			FIFO status signals
			Clear Channel Indicator
			Clock output, down-divided from XOSC
			Serial output RX data
4	DVDD	Power (Digital)	1.8 - 3.6 V digital power supply for digital I/O's and for the digital core voltage regulator
5	DCOUPL	Power (Digital)	1.6 - 2.0 V digital power supply output for decoupling.
			NOTE: This pin is intended for use with the <i>CC1100</i> only. It can not be used to provide supply voltage to other devices.
6	GDO0	Digital I/O	Digital output pin for general use:
	(ATEST)		Test signals
			FIFO status signals
			Clear Channel Indicator
			Clock output, down-divided from XOSC
			Serial output RX data
			Serial input TX data
			Also used as analog test I/O for prototype/production testing
7	CSn	Digital Input	Serial configuration interface, chip select
8	XOSC_Q1	Analog I/O	Crystal oscillator pin 1, or external clock input
9	AVDD	Power (Analog)	1.8 - 3.6 V analog power supply connection
10	XOSC_Q2	Analog I/O	Crystal oscillator pin 2



Pin#	Pin Name	Pin type	Description
11	AVDD	Power (Analog)	1.8 -3.6 V analog power supply connection
12	RF_P	RF I/O	Positive RF input signal to LNA in receive mode
			Positive RF output signal from PA in transmit mode
13	RF_N	RF I/O	Negative RF input signal to LNA in receive mode
			Negative RF output signal from PA in transmit mode
14	AVDD	Power (Analog)	1.8 - 3.6 V analog power supply connection
15	AVDD	Power (Analog)	1.8 - 3.6 V analog power supply connection
16	GND	Ground (Analog)	Analog ground connection
17	RBIAS	Analog I/O	External bias resistor for reference current
18	DGUARD	Power (Digital)	Power supply connection for digital noise isolation
19	GND	Ground (Digital)	Ground connection for digital noise isolation
20	SI	Digital Input	Serial configuration interface, data input

**Table 13: Pinout Overview** 

# 6 Circuit Description




Figure 2: CC1100 Simplified Block Diagram

A simplified block diagram of *CC1100* is shown in Figure 2.

CC1100 features a low-IF receiver. The received RF signal is amplified by the low-noise amplifier (LNA) and down-converted in quadrature (I and Q) to the intermediate frequency (IF). At IF, the I/Q signals are digitised by the ADCs. Automatic gain control (AGC), fine channel filtering and demodulation bit/packet synchronization are performed digitally.

The transmitter part of *CC1100* is based on direct synthesis of the RF frequency. The

frequency synthesizer includes a completely on-chip LC VCO and a 90 degree phase shifter for generating the I and Q LO signals to the down-conversion mixers in receive mode.

A crystal is to be connected to XOSC\_Q1 and XOSC\_Q2. The crystal oscillator generates the reference frequency for the synthesizer, as well as clocks for the ADC and the digital part.

A 4-wire SPI serial interface is used for configuration and data buffer access.

The digital baseband includes support for channel configuration, packet handling, and data buffering.



SWRS038D Page 18 of 92



# 7 Application Circuit

Only a few external components are required for using the *CC1100*. The recommended application circuits are shown in Figure 3 and Figure 4. The external components are described in Table 14, and typical values are given in Table 15.

#### **Bias Resistor**

The bias resistor R171 is used to set an accurate bias current.

### **Balun and RF Matching**

The components between the RF\_N/RF\_P pins and the point where the two signals are joined together (C131, C121, L121 and L131 for the 315/433 MHz reference design [5]. L121, L131, C121, L122, C131, C122 and L132 for the 868/915 MHz reference design [6]) form a balun that converts the differential RF signal on CC1100 to a single-ended RF signal. C124 is needed for DC blocking. Together with an appropriate LC network, the balun components also transform the impedance to match a 50  $\Omega$  antenna (or cable). Suggested values for 315 MHz, 433 MHz, and 868/915 MHz are listed in Table 15.

The balun and LC filter component values and their placement are important to keep the performance optimized. It is highly recommended to follow the CC1100EM reference design [5] and [6].

#### Crystal

The crystal oscillator uses an external crystal with two loading capacitors (C81 and C101). See Section 27 on page 53 for details.

#### **Additional Filtering**

Additional external components (e.g. an RF SAW filter) may be used in order to improve the performance in specific applications.

### **Power Supply Decoupling**

The power supply must be properly decoupled close to the supply pins. Note that decoupling capacitors are not shown in the application circuit. The placement and the size of the decoupling capacitors are very important to achieve the optimum performance. The CC1100EM reference design ([5] and [6]) should be followed closely.

Component	Description
C51	Decoupling capacitor for on-chip voltage regulator to digital part
C81/C101	Crystal loading capacitors, see Section 27 on page 53 for details
C121/C131	RF balun/matching capacitors
C122	RF LC filter/matching filter capacitor (315 and 433 MHz). RF balun/matching capacitor (868/915 MHz).
C123	RF LC filter/matching capacitor
C124	RF balun DC blocking capacitor
C125	RF LC filter DC blocking capacitor (only needed if there is a DC path in the antenna)
L121/L131	RF balun/matching inductors (inexpensive multi-layer type)
L122	RF LC filter/matching filter inductor (315 and 433 MHz). RF balun/matching inductor (868/915 MHz). (inexpensive multi-layer type)
L123	RF LC filter/matching filter inductor (inexpensive multi-layer type)
L124	RF LC filter/matching filter inductor (inexpensive multi-layer type)
L132	RF balun/matching inductor. (inexpensive multi-layer type)
R171	Resistor for internal bias current reference.
XTAL	26MHz - 27MHz crystal, see Section 27 on page 53 for details.

Table 14: Overview of External Components (excluding supply decoupling capacitors)



SWRS038D Page 19 of 92




Figure 3: Typical Application and Evaluation Circuit 315/433 MHz (excluding supply decoupling capacitors)




Figure 4: Typical Application and Evaluation Circuit 868/915 MHz (excluding supply decoupling capacitors)



Component	Value at 315MHz	Value at 433MHz	Value at 868/915MHz	Manufacturer
C51	100 nF ± 10%, 0402 X5R			Murata GRM1555C series
C81	2	7 pF ± 5%, 0402 NP0		Murata GRM1555C series
C101	2	7 pF ± 5%, 0402 NP0		Murata GRM1555C series
C121	6.8 pF ± 0.5 pF, 0402 NP0	3.9 pF ± 0.25 pF, 0402 NP0	1.0 pF ± 0.25 pF, 0402 NP0	Murata GRM1555C series
C122	12 pF ± 5%, 0402 NP0	8.2 pF ± 0.5 pF, 0402 NP0	1.5 pF ± 0.25 pF, 0402 NP0	Murata GRM1555C series
C123	6.8 pF ± 0.5 pF, 0402 NP0	5.6 pF ± 0.5 pF, 0402 NP0	3.3 pF ± 0.25 pF, 0402 NP0	Murata GRM1555C series
C124	220 pF ± 5%, 0402 NP0	220 pF ± 5%, 0402 NP0	100 pF ± 5%, 0402 NP0	Murata GRM1555C series
C125	220 pF ± 5%, 0402 NP0	220 pF ± 5%, 0402 NP0	100 pF ± 5%, 0402 NP0	Murata GRM1555C series
C131	6.8 pF ± 0.5 pF, 0402 NP0	3.9 pF ± 0.25 pF, 0402 NP0	1.5 pF ± 0.25 pF, 0402 NP0	Murata GRM1555C series
L121	33 nH ± 5%, 0402 monolithic	27 nH ± 5%, 0402 monolithic	12 nH ± 5%, 0402 monolithic	Murata LQG15HS series
L122	18 nH ± 5%, 0402 monolithic	22 nH ± 5%, 0402 monolithic	18 nH ± 5%, 0402 monolithic	Murata LQG15HS series
L123	33 nH ± 5%, 0402 monolithic	27 nH ± 5%, 0402 monolithic	12 nH ± 5%, 0402 monolithic	Murata LQG15HS series
L124			12 nH ± 5%, 0402 monolithic	Murata LQG15HS series
L131	33 nH ± 5%, 0402 monolithic	27 nH ± 5%, 0402 monolithic	12 nH ± 5%, 0402 monolithic	Murata LQG15HS series
L132			18 nH ± 5%, 0402 monolithic	Murata LQG15HS series
R171	56 kΩ ± 1%, 0402			Koa RK73 series
XTAL	26.0 MHz surface mount crystal			NDK, AT-41CD2

**Table 15: Bill Of Materials for the Application Circuit** 

The Gerber files for the CC1100EM reference designs ([5] and [6]) are available from the TI website.





# 8 Configuration Overview

*CC1100* can be configured to achieve optimum performance for many different applications. Configuration is done using the SPI interface. The following key parameters can be programmed:

- Power-down / power up mode
- Crystal oscillator power-up / power-down
- Receive / transmit mode
- RF channel selection
- Data rate
- Modulation format
- RX channel filter bandwidth
- RF output power
- Data buffering with separate 64-byte receive and transmit FIFOs
- Packet radio hardware support

- Forward Error Correction (FEC) with interleaving
- Data Whitening
- Wake-On-Radio (WOR)

Details of each configuration register can be found in Section 33, starting on page 60.

Figure 5 shows a simplified state diagram that explains the main *CC1100* states, together with typical usage and current consumption. For detailed information on controlling the *CC1100* state machine, and a complete state diagram, see Section 19, starting on page 42.



SWRS038D Page 22 of 92




Figure 5: Simplified State Diagram, with Typical Current Consumption at 1.2 kBaud Data Rate and MDMCFG2.DEM DCFILT OFF=1 (current optimized). Freq. Band = 868 MHz





# 9 Configuration Software

CC1100 can be configured using the SmartRF® Studio software [7]. The SmartRF® Studio software is highly recommended for obtaining optimum register settings, and for evaluating performance and functionality. A screenshot of the SmartRF® Studio user interface for CC1100 is shown in Figure 6.

After chip reset, all the registers have default values as shown in the tables in Section 33. The optimum register setting might differ from the default value. After a reset all registers that shall be different from the default value therefore needs to be programmed through the SPI interface.




Figure 6: SmartRF® Studio [7] User Interface

# 10 4-wire Serial Configuration and Data Interface

*CC1100* is configured via a simple 4-wire SPI-compatible interface (SI, SO, SCLK and CSn) where *CC1100* is the slave. This interface is also used to read and write buffered data. All transfers on the SPI interface are done most significant bit first.

All transactions on the SPI interface start with a header byte containing a R/W; bit, a burst access bit (B), and a 6-bit address ( $A_5 - A_0$ ).

The CSn pin must be kept low during transfers on the SPI bus. If CSn goes high during the transfer of a header byte or during read/write from/to a register, the transfer will be cancelled. The timing for the address and data transfer on the SPI interface is shown in Figure 7 with reference to Table 16.

When CSn is pulled low, the MCU must wait until *CC1100* SO pin goes low before starting to transfer the header byte. This indicates that the crystal is running. Unless the chip was in



SWRS038D Page 24 of 92

the SLEEP or XOFF states, the SO pin will low. always go low immediately after taking CSn




Figure 7: Configuration Registers Write and Read Operations

Parameter	Description	Min	Max	Units	
f <sub>SCLK</sub>	SCLK frequency 100 ns delay inserted between address byte and data byte (single access), or between address and data, and between each data byte (burst access).		-	10	MHz
	SCLK frequency, single access No delay between address and data byte		-	9	
	SCLK frequency, burst access No delay between address and data byte, or between data bytes		-	6.5	
t <sub>sp,pd</sub>	CSn low to positive edge on SCLK, in power-down mode		150	-	μs
t <sub>sp</sub>	CSn low to positive edge on SCLK, in active mode		20	-	ns
t <sub>ch</sub>	Clock high		50	-	ns
t <sub>cl</sub>	Clock low		50	-	ns
t <sub>rise</sub>	Clock rise time		-	5	ns
t <sub>fall</sub>	Clock fall time		-	5	ns
$t_{sd}$	Setup data (negative SCLK edge) to	Single access	55	-	ns
	positive edge on SCLK (t <sub>sd</sub> applies between address and data bytes, and between data bytes)	Burst access	76	-	
t <sub>hd</sub>	Hold data after positive edge on SCLK		20	-	ns
t <sub>ns</sub>	Negative edge on SCLK to CSn high.		20	-	ns

**Table 16: SPI Interface Timing Requirements** 

**Note:** The minimum  $t_{sp,pd}$  figure in Table 16 can be used in cases where the user does not read the CHIP\_RDYn signal. CSn low to positive edge on SCLK when the chip is woken from power-down depends on the start-up time of the crystal being used. The 150 us in Table 16 is the crystal oscillator start-up time measured on CC1100EM reference designs ([5] and [6]) using crystal AT-41CD2 from NDK.



SWRS038D Page 25 of 92



#### 10.1 Chip Status Byte

When the header byte, data byte, or command strobe is sent on the SPI interface, the chip status byte is sent by the *CC1100* on the SO pin. The status byte contains key status signals, useful for the MCU. The first bit, s7, is the CHIP\_RDYn signal; this signal must go low before the first positive edge of SCLK. The CHIP\_RDYn signal indicates that the crystal is running.

Bits 6, 5, and 4 comprise the STATE value. This value reflects the state of the chip. The XOSC and power to the digital core is on in the IDLE state, but all other modules are in power down. The frequency and channel configuration should only be updated when the chip is in this state. The RX state will be active

when the chip is in receive mode. Likewise, TX is active when the chip is transmitting.

The last four bits (3:0) in the status byte contains FIFO BYTES AVAILABLE. For read operations (the R/W; bit in the header byte is set to 1), the FIFO BYTES AVAILABLE field contains the number of bytes available for reading from the RX FIFO. For write operations (the R/W; bit in the header byte is set to 0), the FIFO BYTES AVAILABLE field contains the number of bytes that can be written to the TΧ FIFO. When FIFO BYTES AVAILABLE=15, 15 or more bytes are available/free.

Table 17 gives a status byte summary.

Bits	Name	Descrip	Description		
7	CHIP_RDYn	Stays high until power and crystal have stabilized. Should always be low when using the SPI interface.			
6:4	STATE[2:0]	Indicates the current main state machine mode			
		Value	State	Description	
		000	IDLE	IDLE state (Also reported for some transitional states instead of SETTLING or CALIBRATE)	
		001	RX	Receive mode	
		010	TX	Transmit mode	
		011	FSTXON	Fast TX ready	
		100	CALIBRATE	Frequency synthesizer calibration is running	
		101	SETTLING	PLL is settling	
		110	RXFIFO_OVERFLOW	RX FIFO has overflowed. Read out any useful data, then flush the FIFO with SFRX	
		111	TXFIFO_UNDERFLOW	TX FIFO has underflowed. Acknowledge with SFTX	
3:0	FIFO_BYTES_AVAILABLE[3:0]	The number of bytes available in the RX FIFO or free bytes in the TX FIFO			

**Table 17: Status Byte Summary** 

### 10.2 Register Access

The configuration registers on the *CC1100* are located on SPI addresses from 0x00 to 0x2E. Table 36 on page 61 lists all configuration registers. It is highly recommended to use SmartRF® Studio [7] to generate optimum register settings. The detailed description of each register is found in Section 33.1 and 33.2, starting on page 64. All configuration registers can be both written to and read. The R/W; bit controls if the register should be written to or read. When writing to registers,

the status byte is sent on the SO pin each time a header byte or data byte is transmitted on the SI pin. When reading from registers, the status byte is sent on the SO pin each time a header byte is transmitted on the SI pin.

Registers with consecutive addresses can be accessed in an efficient way by setting the burst bit (B) in the header byte. The address bits  $(A_5 - A_0)$  set the start address in an internal address counter. This counter is incremented by one each new byte (every 8 clock pulses). The burst access is either a



SWRS038D Page 26 of 92



read or a write access and must be terminated by setting CSn high.

For register addresses in the range 0x30-0x3D, the burst bit is used to select between status registers, burst bit is one, and command strobes, burst bit is zero (see 10.4 below). Because of this, burst access is not available for status registers and they must be accesses one at a time. The status registers can only be read.

#### 10.3 SPI Read

When reading register fields over the SPI interface while the register fields are updated by the radio hardware (e.g. MARCSTATE or TXBYTES), there is a small, but finite, probability that a single read from the register is being corrupt. As an example, the probability of any single read from TXBYTES being corrupt, assuming the maximum data rate is used, is approximately 80 ppm. Refer to the *CC1100* Errata Notes [1] for more details.


#### 10.4 Command Strobes

Command Strobes may be viewed as single byte instructions to *CC1100*. By addressing a command strobe register, internal sequences will be started. These commands are used to disable the crystal oscillator, enable receive mode, enable wake-on-radio etc. The 13 command strobes are listed in Table 35 on page 60.

The command strobe registers are accessed by transferring a single header byte (no data is being transferred). That is, only the R/W; bit, the burst access bit (set to 0), and the six address bits (in the range 0x30 through 0x3D) are written. The R/W; bit can be either one or zero and will determine how the FIFO\_BYTES\_AVAILABLE field in the status byte should be interpreted.

When writing command strobes, the status byte is sent on the SO pin.

A command strobe may be followed by any other SPI access without pulling CSn high. However, if an SRES strobe is being issued, one will have to waith for SO to go low again before the next header byte can be issued as shown in Figure 8. The command strobes are executed immediately, with the exception of the SPWD and the SXOFF strobes that are executed when CSn goes high.



#### 10.5 FIFO Access

The 64-byte TX FIFO and the 64-byte RX FIFO are accessed through the 0x3F address. When the R/W; bit is zero, the TX FIFO is accessed, and the RX FIFO is accessed when the R/W; bit is one.

The TX FIFO is write-only, while the RX FIFO is read-only.

The burst bit is used to determine if the FIFO access is a single byte access or a burst access. The single byte access method expects a header byte with the burst bit set to zero and one data byte. After the data byte a new header byte is expected; hence, CSn can remain low. The burst access method expects one header byte and then consecutive data bytes until terminating the access by setting CSn high.

The following header bytes access the FIFOs:

- 0x3F: Single byte access to TX FIFO
- 0x7F: Burst access to TX FIFO
- 0xBF: Single byte access to RX FIFO
- 0xFF: Burst access to RX FIFO

When writing to the TX FIFO, the status byte (see Section 10.1) is output for each new data byte on SO, as shown in Figure 7. This status byte can be used to detect TX FIFO underflow while writing data to the TX FIFO. Note that the status byte contains the number of bytes free *before* writing the byte in progress to the TX FIFO. When the last byte that fits in the TX FIFO is transmitted on SI, the status byte received concurrently on SO will indicate that one byte is free in the TX FIFO.

The TX FIFO may be flushed by issuing a SFTX command strobe. Similarly, a SFRX command strobe will flush the RX FIFO. A SFTX or SFRX command strobe can only be issued in the IDLE, TXFIFO\_UNDERLOW, or RXFIFO\_OVERFLOW states. Both FIFOs are flushed when going to the SLEEP state.

Figure 9 gives a brief overview of different register access types possible.



SWRS038D Page 27 of 92



#### 10.6 PATABLE Access

The 0x3E address is used to access the PATABLE, which is used for selecting PA power control settings. The SPI expects up to eight data bytes after receiving the address. By programming the PATABLE, controlled PA power ramp-up and ramp-down can be achieved, as well as ASK modulation shaping for reduced bandwidth. Note that both the ASK modulation shaping and the PA ramping is limited to output powers up to -1 dBm, and the PATABLE settings allowed are 0x00 and 0x30 to 0x3F. See SmartRF® Studio [7] for recommended shaping / PA ramping sequences.

See Section 24 on page 49 for details on output power programming.

The PATABLE is an 8-byte table that defines the PA control settings to use for each of the eight PA power values (selected by the 3-bit value FRENDO.PA POWER). The table is

written and read from the lowest setting (0) to the highest (7), one byte at a time. An index counter is used to control the access to the table. This counter is incremented each time a byte is read or written to the table, and set to the lowest index when CSn is high. When the highest value is reached the counter restarts at zero.

The access to the PATABLE is either single byte or burst access depending on the burst bit. When using burst access the index counter will count up; when reaching 7 the counter will restart at 0. The R/W; bit controls whether the access is a read or a write access.

If one byte is written to the PATABLE and this value is to be read out then CSn must be set high before the read access in order to set the index counter back to zero.

Note that the content of the PATABLE is lost when entering the SLEEP state, except for the first byte (index 0).




Figure 9: Register Access Types

# 11 Microcontroller Interface and Pin Configuration

In a typical system, *CC1100* will interface to a microcontroller. This microcontroller must be able to:

- Program CC1100 into different modes
- · Read and write buffered data
- Read back status information via the 4-wire SPI-bus configuration interface (SI, SO, SCLK and CSn).

# 11.1 Configuration Interface

The microcontroller uses four I/O pins for the SPI configuration interface (SI, SO, SCLK and CSn). The SPI is described in Section 10 on page 24.

#### 11.2 General Control and Status Pins

The CC1100 has two dedicated configurable pins (GDO0 and GDO2) and one shared pin

(GDO1) that can output internal status information useful for control software. These pins can be used to generate interrupts on the MCU. See Section 30 page 55 for more details on the signals that can be programmed. GDO1 is shared with the SO pin in the SPI interface. The default setting for GDO1/SO is 3-state output. By selecting any other of the programming options, the GDO1/SO pin will become a generic pin. When CSn is low, the pin will always function as a normal SO pin.

In the synchronous and asynchronous serial modes, the GDO0 pin is used as a serial TX data input pin while in transmit mode.

The GDO0 pin can also be used for an on-chip analog temperature sensor. By measuring the voltage on the GDO0 pin with an external ADC, the temperature can be calculated. Specifications for the temperature sensor are found in Section 4.7 on page 16.



SWRS038D Page 28 of 92

With default PTEST register setting (0x7F) the temperature sensor output is only available when the frequency synthesizer is enabled (e.g. the MANCAL, FSTXON, RX, and TX states). It is necessary to write 0xBF to the PTEST register to use the analog temperature sensor in the IDLE state. Before leaving the IDLE state, the PTEST register should be restored to its default value (0x7F).

### 11.3 Optional Radio Control Feature

The *CC1100* has an optional way of controlling the radio, by reusing SI, SCLK, and CSn from the SPI interface. This feature allows for a simple three-pin control of the major states of the radio: SLEEP, IDLE, RX, and TX.

This optional functionality is enabled with the MCSMO.PIN CTRL EN configuration bit.

State changes are commanded as follows: When CSn is high the SI and SCLK is set to the desired state according to Table 18. When CSn goes low the state of SI and SCLK is

# 12 Data Rate Programming

The data rate used when transmitting, or the data rate expected in receive is programmed by the MDMCFG3.DRATE\_M and the MDMCFG4.DRATE\_E configuration registers. The data rate is given by the formula below. As the formula shows, the programmed data rate depends on the crystal frequency.

$$R_{DATA} = \frac{\left(256 + DRATE\_M\right) \cdot 2^{DRATE\_E}}{2^{28}} \cdot f_{XOSC}$$

The following approach can be used to find suitable values for a given data rate:

$$DRATE\_E = \left[ \log_2 \left( \frac{R_{DATA} \cdot 2^{20}}{f_{XOSC}} \right) \right]$$

$$DRATE\_M = \frac{R_{DATA} \cdot 2^{28}}{f_{XOSC} \cdot 2^{DRATE\_E}} - 256$$

latched and a command strobe is generated internally according to the pin configuration. It is only possible to change state with this functionality. That means that for instance RX will not be restarted if SI and SCLK are set to RX and CSn toggles. When CSn is low the SI and SCLK has normal SPI functionality.

All pin control command strobes are executed immediately, except the SPWD strobe, which is delayed until CSn goes high.

CSn	SCLK	SI	Function
1	Χ	X	Chip unaffected by SCLK/SI
$\downarrow$	0	0	Generates SPWD strobe
$\downarrow$	0	1	Generates STX strobe
$\downarrow$	1	0	Generates SIDLE strobe
$\downarrow$	1	1	Generates SRX strobe
0	SPI mode	SPI mode	SPI mode (wakes up into IDLE if in SLEEP/XOFF)

**Table 18: Optional Pin Control Coding** 

If DRATE\_M is rounded to the nearest integer and becomes 256, increment DRATE\_E and use DRATE M = 0.

The data rate can be set from 1.2 kBaud to 500 kBaud with the minimum step size of:

Min Data Rate [kBaud]	Typical Data Rate [kBaud]	Max Data Rate [kBaud]	Data rate Step Size [kBaud]
0.8	1.2 / 2.4	3.17	0.0062
3.17	4.8	6.35	0.0124
6.35	9.6	12.7	0.0248
12.7	19.6	25.4	0.0496
25.4	38.4	50.8	0.0992
50.8	76.8	101.6	0.1984
101.6	153.6	203.1	0.3967
203.1	250	406.3	0.7935
406.3	500	500	1.5869

**Table 19: Data Rate Step Size** 



### 13 Receiver Channel Filter Bandwidth

In order to meet different channel width requirements, the receiver channel filter is programmable. The MDMCFG4.CHANBW\_E and MDMCFG4.CHANBW\_M configuration registers control the receiver channel filter bandwidth, which scales with the crystal oscillator frequency. The following formula gives the relation between the register settings and the channel filter bandwidth:

$$BW_{channel} = \frac{f_{XOSC}}{8 \cdot (4 + CHANBW_M) \cdot 2^{CHANBW_E}}$$

The *CC1100* supports the following channel filter bandwidths:

MDMCFG4.	MI	MDMCFG4.CHANBW_E			
CHANBW_M	00	01	10	11	
00	812	406	203	102	
01	650	325	162	81	
10	541	270	135	68	
11	464	232	116	58	

Table 20: Channel Filter Bandwidths [kHz] (Assuming a 26MHz crystal)

For best performance, the channel filter bandwidth should be selected so that the signal bandwidth occupies at most 80% of the channel filter bandwidth. The channel centre tolerance due to crystal accuracy should also be subtracted from the signal bandwidth. The following example illustrates this:

With the channel filter bandwidth set to 500 kHz, the signal should stay within 80% of 500 kHz, which is 400 kHz. Assuming 915 MHz frequency and ±20 ppm frequency uncertainty for both the transmitting device and the receiving device, the total frequency uncertainty is ±40 ppm of 915MHz, which is ±37 kHz. If the whole transmitted signal bandwidth is to be received within 400kHz, the transmitted signal bandwidth should be maximum 400kHz – 2·37 kHz, which is 326 kHz

# 14 Demodulator, Symbol Synchronizer, and Data Decision

*CC1100* contains an advanced and highly configurable demodulator. Channel filtering and frequency offset compensation is performed digitally. To generate the RSSI level (see Section 17.3 for more information) the signal level in the channel is estimated. Data filtering is also included for enhanced performance.

#### 14.1 Frequency Offset Compensation

When using 2-FSK, GFSK, or MSK modulation, the demodulator will compensate for the offset between the transmitter and receiver frequency, within certain limits, by estimating the centre of the received data. This value is available in the FREQEST status register. Writing the value from FREQEST into FSCTRLO.FREQOFF the frequency synthesizer is automatically adjusted according to the estimated frequency offset.

The tracking range of the algorithm is selectable as fractions of the channel bandwidth with the FOCCFG.FOC\_LIMIT configuration register.

If the FOCCFG.FOC\_BS\_CS\_GATE bit is set, the offset compensator will freeze until carrier sense asserts. This may be useful when the radio is in RX for long periods with no traffic, since the algorithm may drift to the boundaries when trying to track noise.

The tracking loop has two gain factors, which affects the settling time and noise sensitivity of the algorithm. FOCCFG.FOC\_PRE\_K sets the gain before the sync word is detected, and FOCCFG.FOC\_POST\_K selects the gain after the sync word has been found.

Note that frequency offset compensation is not supported for ASK or OOK modulation.

### 14.2 Bit Synchronization

The bit synchronization algorithm extracts the clock from the incoming symbols. The algorithm requires that the expected data rate is programmed as described in Section 12 on page 29. Re-synchronization is performed continuously to adjust for error in the incoming symbol rate.



SWRS038D Page 30 of 92

### 14.3 Byte Synchronization

Byte synchronization is achieved by a continuous sync word search. The sync word is a 16 bit configurable field (can be repeated to get a 32 bit) that is automatically inserted at the start of the packet by the modulator in transmit mode. The demodulator uses this field to find the byte boundaries in the stream of bits. The sync word will also function as a system identifier, since only packets with the correct predefined sync word will be received if the sync word detection in RX is enabled in register MDMCFG2 (see Section 17.1). The sync word detector correlates against the user-configured 16 or 32 bit sync word. The

correlation threshold can be set to 15/16, 16/16, or 30/32 bits match. The sync word can be further qualified using the preamble quality indicator mechanism described below and/or a carrier sense condition. The sync word is configured through the SYNC1 and SYNC0 registers.

In order to make false detections of sync words less likely, a mechanism called preamble quality indication (PQI) can be used to qualify the sync word. A threshold value for the preamble quality must be exceeded in order for a detected sync word to be accepted. See Section 17.2 on page 37 for more details.

# 15 Packet Handling Hardware Support

The *CC1100* has built-in hardware support for packet oriented radio protocols.

In transmit mode, the packet handler can be configured to add the following elements to the packet stored in the TX FIFO:

- A programmable number of preamble bytes
- A two byte synchronization (sync) word.
   Can be duplicated to give a 4-byte sync word (recommended). It is not possible to only insert preamble or only insert a sync word.
- A CRC checksum computed over the data field.
- The recommended setting is 4-byte preamble and 4-byte sync word, except for 500 kBaud data rate where the recommended preamble length is 8 bytes.
- In addition, the following can be implemented on the data field and the optional 2-byte CRC checksum:
- Whitening of the data with a PN9 sequence.
- Forward error correction by the use of interleaving and coding of the data (convolutional coding).

In receive mode, the packet handling support will de-construct the data packet by implementing the following (if enabled):

- Preamble detection.
- Sync word detection.
- CRC computation and CRC check.
- One byte address check.

- Packet length check (length byte checked against a programmable maximum length).
- De-whitening
- De-interleaving and decoding
- Optionally, two status bytes (see Table 21 and Table 22) with RSSI value, Link Quality Indication, and CRC status can be appended in the RX FIFO.

Bit	Field Name	Description
7:0	RSSI	RSSI value

Table 21: Received Packet Status Byte 1 (first byte appended after the data)

Bit	Field Name	Description
7	CRC_OK	1: CRC for received data OK (or CRC disabled)
		0: CRC error in received data
6:0	LQI	Indicating the link quality

Table 22: Received Packet Status Byte 2 (second byte appended after the data)

 Note that register fields that control the packet handling features should only be altered when CC1100 is in the IDLE state.

#### 15.1 Data Whitening

From a radio perspective, the ideal over the air data are random and DC free. This results in the smoothest power distribution over the occupied bandwidth. This also gives the regulation loops in the receiver uniform operation conditions (no data dependencies).



SWRS038D Page 31 of 92

Real world data often contain long sequences of zeros and ones. Performance can then be improved by whitening the data before transmitting, and de-whitening the data in the receiver. With *CC1100*, this can be done automatically by setting PKTCTRL0.WHITE\_DATA=1. All data, except the preamble and the sync word, are then

XOR-ed with a 9-bit pseudo-random (PN9) sequence before being transmitted, as shown in Figure 10. At the receiver end, the data are XOR-ed with the same pseudo-random sequence. This way, the whitening is reversed, and the original data appear in the receiver. The PN9 sequence is initialized to all 1's.




Figure 10: Data Whitening in TX Mode

#### 15.2 Packet Format

The format of the data packet can be configured and consists of the following items (see Figure 11):

- Preamble
- Synchronization word

- Optional length byte
- Optional address byte
- Payload
- Optional 2 byte CRC
- \_




Figure 11: Packet Format

The preamble pattern is an alternating sequence of ones and zeros (10101010...). The minimum length of the preamble is programmable. When enabling TX, the modulator will start transmitting the preamble.

When the programmed number of preamble bytes has been transmitted, the modulator will send the sync word and then data from the TX FIFO if data is available. If the TX FIFO is empty, the modulator will continue to send



SWRS038D Page 32 of 92



preamble bytes until the first byte is written to the TX FIFO. The modulator will then send the sync word and then the data bytes. The number of preamble bytes is programmed with the MDMCFG1.NUM PREAMBLE value.

The synchronization word is a two-byte value set in the SYNC1 and SYNC0 registers. The sync word provides byte synchronization of the incoming packet. A one-byte synch word can be emulated by setting the SYNC1 value to the preamble pattern. It is also possible to emulate a 32 bit sync word by using MDMCFG2.SYNC\_MODE set to 3 or 7. The sync word will then be repeated twice.

*CC1100* supports both constant packet length protocols and variable length protocols. Variable or fixed packet length mode can be used for packets up to 255 bytes. For longer packets, infinite packet length mode must be used.

Fixed packet length mode is selected by setting PKTCTRL0.LENGTH\_CONFIG=0. The desired packet length is set by the PKTLEN register.

In variable packet length mode, PKTCTRLO.LENGTH\_CONFIG=1, the packet length is configured by the first byte after the sync word. The packet length is defined as the payload data, excluding the length byte and the optional CRC. The PKTLEN register is used to set the maximum packet length allowed in RX. Any packet received with a length byte with a value greater than PKTLEN will be discarded.

With PKTCTRLO.LENGTH\_CONFIG=2, the packet length is set to infinite and transmission and reception will continue until turned off manually. As described in the next section, this can be used to support packet formats with different length configuration than natively supported by *CC1100*. One should make sure that TX mode is not turned off during the transmission of the first half of any byte. Refer to the *CC1100* Errata Notes [1] for more details.

Note that the minimum packet length supported (excluding the optional length byte and CRC) is one byte of payload data.

### 15.2.1 Arbitrary Length Field Configuration

The packet length register, PKTLEN, can be reprogrammed during receive and transmit. In combination with fixed packet length mode

(PKTCTRLO.LENGTH\_CONFIG=0) this opens the possibility to have a different length field configuration than supported for variable length packets (in variable packet length mode the length byte is the first byte after the sync word). At the start of reception, the packet length is set to a large value. The MCU reads out enough bytes to interpret the length field in the packet. Then the PKTLEN value is set according to this value. The end of packet will occur when the byte counter in the packet handler is equal to the PKTLEN register. Thus, the MCU must be able to program the correct length, before the internal counter reaches the packet length.

#### 15.2.2 Packet Length > 255

Also the packet automation control register, PKTCTRL0, can be reprogrammed during TX and RX. This opens the possibility to transmit and receive packets that are longer than 256 bytes and still be able to use the packet handling hardware support. At the start of the packet, the infinite packet length mode (PKTCTRL0.LENGTH CONFIG=2) must active. On the TX side, the PKTLEN register is set to mod(length, 256). On the RX side the MCU reads out enough bytes to interpret the length field in the packet and sets the PKTLEN register to mod(length, 256). When less than 256 bytes remains of the packet the MCU disables infinite packet length mode and activates fixed packet length mode. When the internal byte counter reaches the PKTLEN value, the transmission or reception ends (the radio enters the state determined TXOFF MODE or RXOFF MODE). Automatic CRC appending/checking can also be used (by setting PKTCTRL0.CRC EN=1).

When for example a 600-byte packet is to be transmitted, the MCU should do the following (see also Figure 12)

- Set PKTCTRL0.LENGTH\_CONFIG=2.
- Pre-program the PKTLEN register to mod(600, 256) = 88.
- Transmit at least 345 bytes (600 255), for example by filling the 64-byte TX FIFO six times (384 bytes transmitted).
- Set PKTCTRL0.LENGTH CONFIG=0.
- The transmission ends when the packet counter reaches 88. A total of 600 bytes are transmitted.



SWRS038D Page 33 of 92

Internal byte counter in packet handler counts from 0 to 255 and then starts at 0 again




Figure 12: Packet Length > 255

#### 15.3 Packet Filtering in Receive Mode

*CC1100* supports three different types of packet-filtering; address filtering, maximum length filtering, and CRC filtering.

#### 15.3.1 Address Filtering

Setting PKTCTRL1.ADR CHK to any other value than zero enables the packet address filter. The packet handler engine will compare the destination address byte in the packet with the programmed node address in the ADDR register and the 0x00 broadcast address when PKTCTRL1.ADR CHK=10 or both 0x00 and 0xFF broadcast addresses PKTCTRL1.ADR CHK=11. If the received address matches a valid address, the packet is received and written into the RX FIFO. If the address match fails, the packet is discarded and receive mode restarted (regardless of the MCSM1.RXOFF MODE setting).

If the received address matches a valid address when using infinite packet length mode *and* address filtering is enabled, 0xFF will be written into the RX FIFO followed by the address byte and then the payload data.

### 15.3.2 Maximum Length Filtering

In variable packet length mode, PKTCTRLO.LENGTH\_CONFIG=1, the PKTLEN.PACKET\_LENGTH register value is used to set the maximum allowed packet length. If the received length byte has a larger value than this, the packet is discarded and receive mode restarted (regardless of the MCSM1.RXOFF\_MODE setting).

### 15.3.3 CRC Filtering

The filtering of a packet when CRC check fails is enabled by setting PKTCTRL1.CRC\_AUTOFLUSH=1. The CRC auto flush function will flush the *entire* RX

FIFO if the CRC check fails. After auto flushing the RX FIFO, the next state depends on the MCSM1.RXOFF MODE setting.

When using the auto flush function, the maximum packet length is 63 bytes in variable packet length mode and 64 bytes in fixed packet length mode. Note that the maximum allowed packet length is reduced by two bytes when PKTCTRL1.APPEND\_STATUS is enabled, to make room in the RX FIFO for the two status bytes appended at the end of the packet. Since the entire RX FIFO is flushed when the CRC check fails, the previously received packet must be read out of the FIFO before receiving the current packet. The MCU must not read from the current packet until the CRC has been checked as OK.

### 15.4 Packet Handling in Transmit Mode

The payload that is to be transmitted must be written into the TX FIFO. The first byte written must be the length byte when variable packet length is enabled. The length byte has a value equal to the payload of the packet (including the optional address byte). If address recognition is enabled on the receiver, the second byte written to the TX FIFO must be the address byte. If fixed packet length is enabled, then the first byte written to the TX FIFO should be the address (if the receiver uses address recognition).

The modulator will first send the programmed number of preamble bytes. If data is available in the TX FIFO, the modulator will send the two-byte (optionally 4-byte) sync word and then the payload in the TX FIFO. If CRC is enabled, the checksum is calculated over all the data pulled from the TX FIFO and the result is sent as two extra bytes following the payload data. If the TX FIFO runs empty before the complete packet has been



SWRS038D Page 34 of 92



transmitted, the radio will enter TXFIFO\_UNDERFLOW state. The only way to exit this state is by issuing an SFTX strobe. Writing to the TX FIFO after it has underflowed will not restart TX mode.

If whitening is enabled, everything following the sync words will be whitened. This is done before the optional FEC/Interleaver stage. Whitening is enabled by setting PKTCTRL0.WHITE DATA=1.

If FEC/Interleaving is enabled, everything following the sync words will be scrambled by the interleaver and FEC encoded before being modulated. FEC is enabled by setting MDMCFG1.FEC EN=1.

### 15.5 Packet Handling in Receive Mode

In receive mode, the demodulator and packet handler will search for a valid preamble and the sync word. When found, the demodulator has obtained both bit and byte synchronism and will receive the first payload byte.

If FEC/Interleaving is enabled, the FEC decoder will start to decode the first payload byte. The interleaver will de-scramble the bits before any other processing is done to the data.

If whitening is enabled, the data will be dewhitened at this stage.

When variable packet length mode is enabled, the first byte is the length byte. The packet handler stores this value as the packet length and receives the number of bytes indicated by the length byte. If fixed packet length mode is used, the packet handler will accept the programmed number of bytes.

Next, the packet handler optionally checks the address and only continues the reception if the address matches. If automatic CRC check is enabled, the packet handler computes CRC and matches it with the appended CRC checksum.

At the end of the payload, the packet handler will optionally write two extra packet status bytes (see Table 21 and Table 22) that contain CRC status, link quality indication, and RSSI value.

### 15.6 Packet Handling in Firmware

When implementing a packet oriented radio protocol in firmware, the MCU needs to know

when a packet has been received/transmitted. Additionally, for packets longer than 64 bytes the RX FIFO needs to be read while in RX and the TX FIFO needs to be refilled while in TX. This means that the MCU needs to know the number of bytes that can be read from or written to the RX FIFO and TX FIFO respectively. There are two possible solutions to get the necessary status information:

#### a) Interrupt Driven Solution

In both RX and TX one can use one of the GDO pins to give an interrupt when a sync word has been received/transmitted and/or when a complete packet has been received/transmitted

(IOCFGx.GDOx CFG=0x06). In addition, there 2 configurations for the IOCFGx.GDOx CFG reaister that are the RX **FIFO** associated with (IOCFGx.GDOx CFG=0x00 and IOCFGx.GDOx CFG=0x01) and two that are associated with the TX FIFO (IOCFGx.GDOx CFG=0x02 and IOCFGx.GDOx CFG=0x03) that can be used as interrupt sources to provide information on how many bytes are in the RX FIFO and TX FIFO respectively. See Table 34.

#### b) SPI Polling

The PKTSTATUS register can be polled at a given rate to get information about the current GDO2 and GDO0 values respectively. The RXBYTES and TXBYTES registers can be polled at a given rate to get information about the number of bytes in the RX FIFO and TX FIFO respectively. Alternatively, the number of bytes in the RX FIFO and TX FIFO can be read from the chip status byte returned on the MISO line each time a header byte, data byte, or command strobe is sent on the SPI bus.

It is recommended to employ an interrupt driven solution as high rate SPI polling will reduce the RX sensitivity. Furthermore, as explained in Section 10.3 and the *CC1100* Errata Notes [1], when using SPI polling there is a small, but finite, probability that a single read from registers PKTSTATUS, RXBYTES and TXBYTES is being corrupt. The same is the case when reading the chip status byte.

Refer to the TI website for SW examples ([8] and [9]).



SWRS038D Page 35 of 92



#### 16 Modulation Formats

 ${\it CC1100}$  supports amplitude, frequency, and phase shift modulation formats. The desired modulation format is set in the MDMCFG2.MOD FORMAT register.

Optionally, the data stream can be Manchester coded by the modulator and decoded by the demodulator. This option is enabled by setting MDMCFG2.MANCHESTER\_EN=1. Manchester encoding is not supported at the same time as using the FEC/Interleaver option.

### 16.1 Frequency Shift Keying

2-FSK can optionally be shaped by a Gaussian filter with BT = 1, producing a GFSK modulated signal.

The frequency deviation is programmed with the DEVIATION\_M and DEVIATION\_E values in the DEVIATN register. The value has an exponent/mantissa form, and the resultant deviation is given by:

$$f_{dev} = \frac{f_{xosc}}{2^{17}} \cdot (8 + DEVIATION \_M) \cdot 2^{DEVIATION \_E}$$

The symbol encoding is shown in Table 23.

Format	Symbol	Coding
2-FSK/GFSK	'0'	<ul><li>Deviation</li></ul>
	<b>'1'</b>	+ Deviation

Table 23: Symbol Encoding for 2-FSK/GFSK Modulation

### 16.2 Minimum Shift Keying

When using MSK<sup>1</sup>, the complete transmission (preamble, sync word, and payload) will be MSK modulated.

Phase shifts are performed with a constant transition time.

The fraction of a symbol period used to change the phase can be modified with the DEVIATN.DEVIATION\_M setting. This is equivalent to changing the shaping of the symbol.

The MSK modulation format implemented in *CC1100* inverts the sync word and data compared to e.g. signal generators.

# 16.3 Amplitude Modulation

*CC1100* supports two different forms of amplitude modulation: On-Off Keying (OOK) and Amplitude Shift Keying (ASK).

OOK modulation simply turns on or off the PA to modulate 1 and 0 respectively.

The ASK variant supported by the *CC1100* allows programming of the modulation depth (the difference between 1 and 0), and shaping of the pulse amplitude. Pulse shaping will produce a more bandwidth constrained output spectrum. Note that the pulse shaping feature on the *CC1100* does only support output power up to about -1dBm. The PATABLE settings that can be used for pulse shaping are 0x00 and 0x30 to 0x3F.



SWRS038D Page 36 of 92

<sup>&</sup>lt;sup>1</sup> Identical to offset QPSK with half-sine shaping (data coding may differ)

# 17 Received Signal Qualifiers and Link Quality Information

*CC1100* has several qualifiers that can be used to increase the likelihood that a valid sync word is detected.

#### 17.1 Sync Word Qualifier

If sync word detection in RX is enabled in register MDMCFG2 the *CC1100* will not start filling the RX FIFO and perform the packet filtering described in Section 15.3 before a valid sync word has been detected. The sync word qualifier mode is set by MDMCFG2.SYNC\_MODE and is summarized in Table 24. Carrier sense is described in Section 17.4.

MDMCFG2.	CFG2. Sync Word Qualifier Mode	
SYNC_MODE		
000	No preamble/sync	
001	15/16 sync word bits detected	
010	16/16 sync word bits detected	
011	30/32 sync word bits detected	
100	No preamble/sync, carrier sense above threshold	
101	15/16 + carrier sense above threshold	
110	16/16 + carrier sense above threshold	
111	30/32 + carrier sense above threshold	

**Table 24: Sync Word Qualifier Mode** 

#### 17.2 Preamble Quality Threshold (PQT)

The Preamble Quality Threshold (PQT) syncword qualifier adds the requirement that the received sync word must be preceded with a preamble with a quality above the programmed threshold.

Another use of the preamble quality threshold is as a qualifier for the optional RX termination timer. See Section 19.7 on page 46 for details.

The preamble quality estimator increases an internal counter by one each time a bit is received that is different from the previous bit, and decreases the counter by 8 each time a bit is received that is the same as the last bit. The threshold is configured with the register field PKTCTRL1.PQT. A threshold of 4·PQT for this counter is used to gate sync word detection. By setting the value to zero, the preamble quality qualifier of the synch word is disabled.

A "Preamble Quality Reached" signal can be observed on one of the GDO pins by setting IOCFGx.GDOx\_CFG=8. It is also possible to determine if preamble quality is reached by checking the PQT\_REACHED bit in the PKTSTATUS register. This signal / bit asserts when the received signal exceeds the PQT.

#### 17.3 RSSI

The RSSI value is an estimate of the signal power level in the chosen channel. This value is based on the current gain setting in the RX chain and the measured signal level in the channel.

In RX mode, the RSSI value can be read continuously from the RSSI status register until the demodulator detects a sync word (when sync word detection is enabled). At that point the RSSI readout value is frozen until the next time the chip enters the RX state. The RSSI value is in dBm with ½dB resolution. The RSSI update rate,  $f_{RSSI}$ , depends on the receiver filter bandwidth (BW\_channel defined in Section 13) and AGCCTRLO.FILTER\_LENGTH.

$$f_{RSSI} = \frac{2 \cdot BW_{channel}}{8 \cdot 2^{FILTER\_LENGTH}}$$

If PKTCTRL1.APPEND\_STATUS is enabled the last RSSI value of the packet is automatically added to the first byte appended after the payload.

The RSSI value read from the RSSI status register is a 2's complement number. The following procedure can be used to convert the RSSI reading to an absolute power level (RSSI dBm).


- 1) Read the RSSI status register
- 2) Convert the reading from a hexadecimal number to a decimal number (RSSI\_dec)
- 3) If RSSI\_dec ≥ 128 then RSSI\_dBm = (RSSI dec 256)/2 RSSI offset
- 4) Else if RSSI\_dec < 128 then RSSI\_dBm = (RSSI\_dec)/2 - RSSI\_offset

Table 25 gives typical values for the RSSI offset.

Figure 13 and Figure 14 shows typical plots of RSSI reading as a function of input power level for different data rates.



SWRS038D Page 37 of 92



Data rate [kBaud]	RSSI_offset [dB], 433 MHz	RSSI_offset [dB], 868 MHz
1.2	75	74
38.4	75	74
250	79	78
500	79	77

Table 25: Typical RSSI\_offset Values




Figure 13: Typical RSSI Value vs. Input Power Level for Different Data Rates at 433 MHz




Figure 14: Typical RSSI Value vs. Input Power Level for Different Data Rates at 868 MHz



SWRS038D Page 38 of 92

#### 17.4 Carrier Sense (CS)

Carrier Sense (CS) is used as a sync word qualifier and for CCA and can be asserted based on two conditions, which can be individually adjusted:

- CS is asserted when the RSSI is above a programmable absolute threshold, and deasserted when RSSI is below the same threshold (with hysteresis).
- CS is asserted when the RSSI has increased with a programmable number of dB from one RSSI sample to the next, and de-asserted when RSSI has decreased with the same number of dB. This setting is not dependent on the absolute signal level and is thus useful to detect signals in environments with time varying noise floor.

Carrier Sense can be used as a sync word qualifier that requires the signal level to be higher than the threshold for a sync word search to be performed. The signal can also be observed on one of the GDO pins by setting IOCFGx.GDOx\_CFG=14 and in the status register bit PKTSTATUS.CS.

Other uses of Carrier Sense include the TX-if-CCA function (see Section 17.5 on page 40) and the optional fast RX termination (see Section 19.7 on page 46).

CS can be used to avoid interference from other RF sources in the ISM bands.

#### 17.4.1 CS Absolute Threshold

The absolute threshold related to the RSSI value depends on the following register fields:

- AGCCTRL2.MAX\_LNA\_GAIN
- AGCCTRL2.MAX DVGA GAIN
- AGCCTRL1.CARRIER SENSE ABS THR
- AGCCTRL2.MAGN TARGET
- For a given AGCCTRL2.MAX\_LNA\_GAIN and AGCCTRL2.MAX\_DVGA\_GAIN setting the absolute threshold can be adjusted ±7 dB in steps of 1 dB using CARRIER SENSE ABS THR.

The MAGN\_TARGET setting is a compromise between blocker tolerance/selectivity and sensitivity. The value sets the desired signal level in the channel into the demodulator. Increasing this value reduces the headroom for blockers, and therefore close-in selectivity. It is strongly recommended to use SmartRF®

Studio to generate the correct MAGN\_TARGET setting.

Table 26 and Table 27 show the typical RSSI readout values at the CS threshold at 2.4 kBaud and 250 kBaud data rate respectively. The default CARRIER\_SENSE\_ABS\_THR=0 (0 dB) and MAGN\_TARGET=3 (33 dB) have been used.

For other data rates the user must generate similar tables to find the CS absolute threshold.

		MAX_DVGA_GAIN[1:0]				
		00	01	10	11	
	000	-97.5	-91.5	-85.5	-79.5	
0]	001	-94	-88	-82.5	-76	
MAX_LNA_GAIN[2:0]	010	-90.5	-84.5	-78.5	-72.5	
_GAI	011	-88	-82.5	-76.5	-70.5	
AN.	100	-85.5	-80	-73.5	-68	
AX	101	-84	-78	-72	-66	
Σ	110	-82	-76	-70	-64	
	111	-79	-73.5	-67	-61	

Table 26: Typical RSSI Value in dBm at CS Threshold with Default MAGN\_TARGET at 2.4 kBaud, 868 MHz

		MAX_DVGA_GAIN[1:0]					
		00	01	10	11		
	000	-90.5	-84.5	-78.5	-72.5		
0]	001	-88	-82	-76	-70		
MAX_LNA_GAIN[2:0]	010	-84.5	-78.5	-72	-66		
	011	-82.5	-76.5	-70	-64		
	100	-80.5	-74.5	-68	-62		
Ϋ́	101	-78	-72	-66	-60		
Σ	110	-76.5	-70	-64	-58		
	111	-74.5	-68	-62	-56		

Table 27: Typical RSSI Value in dBm at CS Threshold with Default MAGN\_TARGET at 250 kBaud, 868 MHz

If the threshold is set high, i.e. only strong signals are wanted, the threshold should be adjusted upwards by first reducing the MAX\_LNA\_GAIN value and then the MAX\_DVGA\_GAIN value. This will reduce power consumption in the receiver front end, since the highest gain settings are avoided.



SWRS038D Page 39 of 92



#### 17.4.2 CS Relative Threshold

The relative threshold detects sudden changes in the measured signal level. This setting is not dependent on the absolute signal level and is thus useful to detect signals in environments with a time varying noise floor. The register field AGCCTRL1.CARRIER\_SENSE\_REL\_THR is used to enable/disable relative CS, and to select threshold of 6 dB, 10 dB, or 14 dB RSSI change.

#### 17.5 Clear Channel Assessment (CCA)

The Clear Channel Assessment (CCA) is used to indicate if the current channel is free or busy. The current CCA state is viewable on any of the GDO pins by setting IOCFGx.GDOx CFG=0x09.

 ${\tt MCSM1.CCA\_MODE}$  selects the mode to use when determining CCA.

When the STX or SFSTXON command strobe is given while *CC1100* is in the RX state, the TX or FSTXON state is only entered if the clear channel requirements are fulfilled. The chip will otherwise remain in RX (if the channel becomes available, the radio will not enter TX or FSTXON state before a new strobe command is sent on the SPI interface). This

feature is called TX-if-CCA. Four CCA requirements can be programmed:

- Always (CCA disabled, always goes to TX)
- If RSSI is below threshold
- Unless currently receiving a packet
- Both the above (RSSI below threshold and not currently receiving a packet)

### 17.6 Link Quality Indicator (LQI)

The Link Quality Indicator is a metric of the current quality of the received signal. If PKTCTRL1.APPEND STATUS is enabled, the value is automatically added to the last byte appended after the payload. The value can also be read from the  ${\tt LQI}$  status register. The LQI gives an estimate of how easily a received signal can be demodulated by accumulating the magnitude of the error between ideal constellations and the received signal over the 64 symbols immediately following the sync word. LQI is best used as a relative measurement of the link quality (a high value indicates a better link than what a low value does), since the value is dependent on the modulation format.

# 18 Forward Error Correction with Interleaving

#### 18.1 Forward Error Correction (FEC)

CC1100 has built in support for Forward Error Correction (FEC). To enable this option, set MDMCFG1.FEC EN to 1. FEC is only supported packet fixed length mode (PKTCTRL0.LENGTH CONFIG=0). employed on the data field and CRC word in order to reduce the gross bit error rate when operating near the sensitivity Redundancy is added to the transmitted data in such a way that the receiver can restore the original data in the presence of some bit errors.

The use of FEC allows correct reception at a lower SNR, thus extending communication range if the receiver bandwidth remains constant. Alternatively, for a given SNR, using FEC decreases the bit error rate (BER). As the packet error rate (PER) is related to BER by:

$$PER = 1 - (1 - BER)^{packet\_length}$$

a lower BER can be used to allow longer packets, or a higher percentage of packets of

a given length, to be transmitted successfully. Finally, in realistic ISM radio environments, transient and time-varying phenomena will produce occasional errors even in otherwise good reception conditions. FEC will mask such errors and, combined with interleaving of the coded data, even correct relatively long periods of faulty reception (burst errors).

The FEC scheme adopted for CC1100 is convolutional coding, in which n bits are generated based on k input bits and the m most recent input bits, forming a code stream able to withstand a certain number of bit errors between each coding state (the m-bit window).

The convolutional coder is a rate 1/2 code with a constraint length of m=4. The coder codes one input bit and produces two output bits; hence, the effective data rate is halved. I.e. to transmit at the same effective datarate when using FEC, it is necessary to use twice as high over-the-air datarate. This will require a higher receiver bandwidth, and thus reduce sensitivity. In other words the improved



SWRS038D Page 40 of 92



reception by using FEC and the degraded sensitivity from a higher receiver bandwidth will be counteracting factors.

#### 18.2 Interleaving

Data received through radio channels will often experience burst errors due to interference and time-varying signal strengths. In order to increase the robustness to errors spanning multiple bits, interleaving is used when FEC is enabled. After de-interleaving, a continuous span of errors in the received stream will become single errors spread apart.

CC1100 employs matrix interleaving, which is illustrated in Figure 15. The on-chip interleaving and de-interleaving buffers are  $4 \times 4$  matrices. In the transmitter, the data bits from the rate  $\frac{1}{2}$  convolutional coder are written into the rows of the matrix, whereas the bit sequence to be transmitted is read from the columns of the matrix. Conversely, in the

receiver, the received symbols are written into the columns of the matrix, whereas the data passed onto the convolutional decoder is read from the rows of the matrix.

When FEC and interleaving is used at least one extra byte is required for trellis termination. In addition, the amount of data transmitted over the air must be a multiple of the size of the interleaver buffer (two bytes). The packet control hardware therefore automatically inserts one or two extra bytes at the end of the packet, so that the total length of the data to be interleaved is an even number. Note that these extra bytes are invisible to the user, as they are removed before the received packet enters the RX FIFO.

When FEC and interleaving is used the minimum data payload is 2 bytes.




Figure 15: General Principle of Matrix Interleaving



SWRS038D Page 41 of 92

#### 19 Radio Control




Figure 16: Complete Radio Control State Diagram

*CC1100* has a built-in state machine that is used to switch between different operational states (modes). The change of state is done either by using command strobes or by internal events such as TX FIFO underflow.

A simplified state diagram, together with typical usage and current consumption, is shown in Figure 5 on page 23. The complete radio control state diagram is shown in Figure 16. The numbers refer to the state number readable in the MARCSTATE status register. This register is primarily for test purposes.

#### 19.1 Power-On Start-Up Sequence

When the power supply is turned on, the system must be reset. This is achieved by one of the two sequences described below, i.e. automatic power-on reset (POR) or manual reset.

After the automatic power-on reset or manual reset it is also recommended to change the signal that is output on the GDO0 pin. The default setting is to output a clock signal with a frequency of CLK\_XOSC/192, but to optimize



SWRS038D Page 42 of 92

performance in TX and RX an alternative GDO setting should be selected from the settings found in Table 34 on page 56.

#### 19.1.1 Automatic POR

A power-on reset circuit is included in the *CC1100*. The minimum requirements stated in Table 12 must be followed for the power-on reset to function properly. The internal power-up sequence is completed when CHIP\_RDYn goes low. CHIP\_RDYn is observed on the SO pin after CSn is pulled low. See Section 10.1 for more details on CHIP\_RDYn.

When the *CC1100* reset is completed the chip will be in the IDLE state and the crystal oscillator will be running. If the chip has had sufficient time for the crystal oscillator to stabilize after the power-on-reset the SO pin will go low immediately after taking CSn low. If CSn is taken low before reset is completed the SO pin will first go high, indicating that the crystal oscillator is not stabilized, before going low as shown in Figure 17.




Figure 17: Power-On Reset

### 19.1.2 Manual Reset

The other global reset possibility on *CC1100* uses the SRES command strobe. By issuing this strobe, all internal registers and states are set to the default, IDLE state. The manual power-up sequence is as follows (see Figure 18):

- Set SCLK = 1 and SI = 0, to avoid potential problems with pin control mode (see Section 11.3 on page 29).
- Strobe CSn low / high.
- Hold CSn high for at least 40µs relative to pulling CSn low
- Pull CSn low and wait for SO to go low (CHIP RDYn).
- Issue the SRES strobe on the SI line.
- When SO goes low again, reset is complete and the chip is in the IDLE state.




Figure 18: Power-On Reset with SRES

Note that the above reset procedure is only required just after the power supply is first turned on. If the user wants to reset the *CC1100* after this, it is only necessary to issue an SRES command strobe.

### 19.2 Crystal Control

The crystal oscillator (XOSC) is either automatically controlled or always on, if MCSMO.XOSC FORCE ON is set.

In the automatic mode, the XOSC will be turned off if the SXOFF or SPWD command strobes are issued; the state machine then goes to XOFF or SLEEP respectively. This can only be done from the IDLE state. The XOSC will be turned off when CSn is released (goes high). The XOSC will be automatically turned on again when CSn goes low. The state machine will then go to the IDLE state. The SO pin on the SPI interface must be pulled low before the SPI interface is ready to be used; as described in Section 10.1 on page

If the XOSC is forced on, the crystal will always stay on even in the SLEEP state.

Crystal oscillator start-up time depends on crystal ESR and load capacitances. The electrical specification for the crystal oscillator can be found in Section 4.4 on page 14.

#### 19.3 Voltage Regulator Control

The voltage regulator to the digital core is controlled by the radio controller. When the chip enters the SLEEP state, which is the state with the lowest current consumption, the voltage regulator is disabled. This occurs after CSn is released when a SPWD command strobe has been sent on the SPI interface. The chip is now in the SLEEP state. Setting CSn



SWRS038D Page 43 of 92



low again will turn on the regulator and crystal oscillator and make the chip enter the IDLE state.

When wake on radio is enabled, the WOR module will control the voltage regulator as described in Section 19.5.

#### 19.4 Active Modes

 ${\it CC1100}$  has two active modes: receive and transmit. These modes are activated directly by the MCU by using the SRX and STX command strobes, or automatically by Wake on Radio.

The frequency synthesizer must be calibrated regularly. *CC1100* has one manual calibration option (using the SCAL strobe), and three automatic calibration options, controlled by the MCSM0.FS\_AUTOCAL setting:

- Calibrate when going from IDLE to either RX or TX (or FSTXON)
- Calibrate when going from either RX or TX to IDLE automatically
- Calibrate every fourth time when going from either RX or TX to IDLE automatically

If the radio goes from TX or RX to IDLE by issuing an SIDLE strobe, calibration will not be performed. The calibration takes a constant number of XOSC cycles (see Table 28 for timing details).

When RX is activated, the chip will remain in receive mode until a packet is successfully received or the RX termination timer expires (see Section 19.7). Note: the probability that a false sync word is detected can be reduced by using PQT, CS, maximum sync word length, and sync word qualifier mode as described in Section 17. After a packet is successfully received the radio controller will then go to the state indicated by the MCSM1.RXOFF\_MODE setting. The possible destinations are:

- IDLE
- FSTXON: Frequency synthesizer on and ready at the TX frequency. Activate TX with STX.
- TX: Start sending preamble
- RX: Start search for a new packet

Similarly, when TX is active the chip will remain in the TX state until the current packet has been successfully transmitted. Then the

state will change as indicated by the MCSM1.TXOFF\_MODE setting. The possible destinations are the same as for RX.

The MCU can manually change the state from RX to TX and vice versa by using the command strobes. If the radio controller is currently in transmit and the SRX strobe is used, the current transmission will be ended and the transition to RX will be done.

If the radio controller is in RX when the STX or SFSTXON command strobes are used, the TX-if-CCA function will be used. If the channel is not clear, the chip will remain in RX. The  $\texttt{MCSM1.CCA\_MODE}$  setting controls the conditions for clear channel assessment. See Section 17.5 on page 40 for details.

The SIDLE command strobe can always be used to force the radio controller to go to the IDLE state.

#### 19.5 Wake On Radio (WOR)

The optional Wake on Radio (WOR) functionality enables *CC1100* to periodically wake up from SLEEP and listen for incoming packets without MCU interaction.

When the WOR strobe command is sent on the SPI interface, the *CC1100* will go to the SLEEP state when CSn is released. The RC oscillator must be enabled before the WOR strobe can be used, as it is the clock source for the WOR timer. The on-chip timer will set *CC1100* into IDLE state and then RX state. After a programmable time in RX, the chip will go back to the SLEEP state, unless a packet is received. See Figure 19 and Section 19.7 for details on how the timeout works.

Set the *CC1100* into the IDLE state to exit WOR mode.

CC1100 can be set up to signal the MCU that a packet has been received by using the GDO pins. If a packet is received, the MCSM1.RXOFF\_MODE will determine the behaviour at the end of the received packet. When the MCU has read the packet, it can put the chip back into SLEEP with the SWOR strobe from the IDLE state. The FIFO will loose its contents in the SLEEP state.

The WOR timer has two events, Event 0 and Event 1. In the SLEEP state with WOR activated, reaching Event 0 will turn on the digital regulator and start the crystal oscillator. Event 1 follows Event 0 after a programmed timeout.



SWRS038D Page 44 of 92

The time between two consecutive Event 0 is programmed with a mantissa value given by WOREVT1.EVENTO and WOREVTO.EVENTO, and an exponent value set by WORCTRL.WOR RES. The equation is:

$$t_{Event0} = \frac{750}{f_{XOSC}} \cdot EVENT0 \cdot 2^{5 \cdot WOR\_RES}$$

The Event 1 timeout is programmed with WORCTRL.EVENT1. Figure 19 shows the timing relationship between Event 0 timeout and Event 1 timeout.




Figure 19: Event 0 and Event 1 Relationship

The time from the  $\mathcal{CC1100}$  enters SLEEP state until the next Event0 is programmed to appear ( $t_{SLEEP}$  in Figure 19) should be larger than 11.08 ms when using a 26 MHz crystal and 10.67 ms when a 27 MHz crystal is used. If  $t_{SLEEP}$  is less than 11.08 (10.67) ms there is a chance that the consecutive Event 0 will occur

$$\frac{750}{f_{\it xosc}}._{128} \ {\rm seconds}$$

too early. Application Note AN047 [4] explains in detail the theory of operation and the different registers involved when using WOR, as well as highlighting important aspects when using WOR mode.

#### 19.5.1 RC Oscillator and Timing

The frequency of the low-power RC oscillator used for the WOR functionality varies with temperature and supply voltage. In order to keep the frequency as accurate as possible, the RC oscillator will be calibrated whenever possible, which is when the XOSC is running and the chip is not in the SLEEP state. When the power and XOSC is enabled, the clock used by the WOR timer is a divided XOSC clock. When the chip goes to the sleep state, the RC oscillator will use the last valid calibration result. The frequency of the RC

oscillator is locked to the main crystal frequency divided by 750.

In applications where the radio wakes up very often, typically several times every second, it is possible to do the RC oscillator calibration once and then turn off calibration (WORCTRL.RC CAL=0) to reduce the current consumption. This requires that RC oscillator calibration values are read from registers RCCTRLO STATUS and RCCTRL1 STATUS and written back to RCCTRLO and RCCTRL1 respectively. If the RC oscillator calibration is turned off it will have to be manually turned on again if temperature and supply voltage changes.

Refer to Application Note AN047 [4] for further details.

#### 19.6 Timing

The radio controller controls most of the timing in *CC1100*, such as synthesizer calibration, PLL lock time, and RX/TX turnaround times. Timing from IDLE to RX and IDLE to TX is constant, dependent on the auto calibration setting. RX/TX and TX/RX turnaround times are constant. The calibration time is constant 18739 clock periods. Table 28 shows timing in crystal clock cycles for key state transitions.

Power on time and XOSC start-up times are variable, but within the limits stated in Table 7.

Note that in a frequency hopping spread spectrum or a multi-channel protocol the calibration time can be reduced from 721  $\mu$ s to approximately 150  $\mu$ s. This is explained in Section 32.2.

Description	XOSC Periods	26 MHz Crystal
IDLE to RX, no calibration	2298	88.4µs
IDLE to RX, with calibration	~21037	809µs
IDLE to TX/FSTXON, no calibration	2298	88.4µs
IDLE to TX/FSTXON, with calibration	~21037	809µs
TX to RX switch	560	21.5µs
RX to TX switch	250	9.6µs
RX or TX to IDLE, no calibration	2	0.1µs
RX or TX to IDLE, with calibration	~18739	721µs
Manual calibration	~18739	721µs

**Table 28: State Transition Timing** 





#### 19.7 RX Termination Timer

CC1100 has optional functions for automatic termination of RX after a programmable time. The main use for this functionality is wake-on-radio (WOR), but it may be useful for other applications. The termination timer starts when in RX state. The timeout is programmable with the MCSM2.RX\_TIME setting. When the timer expires, the radio controller will check the condition for staying in RX; if the condition is not met, RX will terminate.

The programmable conditions are:

- MCSM2.RX\_TIME\_QUAL=0: Continue receive if sync word has been found
- MCSM2.RX\_TIME\_QUAL=1: Continue receive if sync word has been found or preamble quality is above threshold (PQT)

If the system can expect the transmission to have started when enabling the receiver, the MCSM2.RX\_TIME\_RSSI function can be used. The radio controller will then terminate RX if the first valid carrier sense sample indicates no carrier (RSSI below threshold). See Section 17.4 on page 39 for details on Carrier Sense.

For ASK/OOK modulation, lack of carrier sense is only considered valid after eight symbol periods. Thus, the MCSM2.RX\_TIME\_RSSI function can be used in ASK/OOK mode when the distance between "1" symbols is 8 or less.

If RX terminates due to no carrier sense when the MCSM2.RX TIME RSSI function is used. or if no sync word was found when using the MCSM2.RX TIME timeout function, the chip will always go back to IDLE if WOR is disabled and back to SLEEP if WOR is enabled. Otherwise, the MCSM1.RXOFF MODE setting determines the state to go to when RX ends. This means that the chip will not automatically go back to SLEEP once a sync word has been received. It is therefore recommended to always wake up the microcontroller on sync word detection when using WOR mode. This can be done by selecting output signal 6 (see Table 34 on page 56) on one of the programmable GDO output pins. programming the microcontroller to wake up on an edge-triggered interrupt from this GDO pin.

#### 20 Data FIFO

The *CC1100* contains two 64 byte FIFOs, one for received data and one for data to be transmitted. The SPI interface is used to read from the RX FIFO and write to the TX FIFO. Section 10.5 contains details on the SPI FIFO access. The FIFO controller will detect overflow in the RX FIFO and underflow in the TX FIFO.

When writing to the TX FIFO it is the responsibility of the MCU to avoid TX FIFO overflow. A TX FIFO overflow will result in an error in the TX FIFO content.

Likewise, when reading the RX FIFO the MCU must avoid reading the RX FIFO past its empty value, since an RX FIFO underflow will result in an error in the data read out of the RX FIFO.

The chip status byte that is available on the SO pin while transferring the SPI header contains the fill grade of the RX FIFO if the access is a read operation and the fill grade of the TX FIFO if the access is a write operation. Section 10.1 on page 26 contains more details on this.

The number of bytes in the RX FIFO and TX FIFO can be read from the status registers RXBYTES.NUM RXBYTES and

TXBYTES.NUM\_TXBYTES respectively. If a received data byte is written to the RX FIFO at the exact same time as the last byte in the RX FIFO is read over the SPI interface, the RX FIFO pointer is not properly updated and the last read byte is duplicated. To avoid this problem one should never empty the RX FIFO before the last byte of the packet is received.

For packet lengths less than 64 bytes it is recommended to wait until the complete packet has been received before reading it out of the RX FIFO.

If the packet length is larger than 64 bytes the MCU must determine how many bytes can be read from the RX FIFO (RXBYTES.NUM\_RXBYTES-1) and the following software routine can be used:

- 1. Read RXBYTES.NUM\_RXBYTES repeatedly at a rate guaranteed to be at least twice that of which RF bytes are received until the same value is returned twice: store value in n.
- 2. If *n* < # of bytes remaining in packet, read *n*-1 bytes from the RX FIFO.





- 3. Repeat steps 1 and 2 until *n* = # of bytes remaining in packet.
- 4. Read the remaining bytes from the RX FIFO.

The 4-bit FIFOTHR.FIFO\_THR setting is used to program threshold points in the FIFOs. Table 29 lists the 16 FIFO\_THR settings and the corresponding thresholds for the RX and TX FIFOs. The threshold value is coded in opposite directions for the RX FIFO and TX FIFO. This gives equal margin to the overflow and underflow conditions when the threshold is reached.

A signal will assert when the number of bytes in the FIFO is equal to or higher than the programmed threshold. This signal can be viewed on the GDO pins (see Table 34 on page 56).

Figure 21 shows the number of bytes in both the RX FIFO and TX FIFO when the threshold signal toggles, in the case of FIFO\_THR=13. Figure 20 shows the signal as the respective FIFO is filled above the threshold, and then drained below.




Figure 20: FIFO\_THR=13 vs. Number of Bytes in FIFO (GDOx\_CFG=0x00 in RX and GDOx\_CFG=0x02 in TX)

FIFO_THR	Bytes in TX FIFO	Bytes in RX FIFO
0 (0000)	61	4
1 (0001)	57	8
2 (0010)	53	12
3 (0011)	49	16
4 (0100)	45	20
5 (0101)	41	24
6 (0110)	37	28
7 (0111)	33	32
8 (1000)	29	36
9 (1001)	25	40
10 (1010)	21	44
11 (1011)	17	48
12 (1100)	13	52
13 (1101)	9	56
14 (1110)	5	60
15 (1111)	1	64

Table 29: FIFO\_THR Settings and the Corresponding FIFO Thresholds




Figure 21: Example of FIFOs at Threshold



SWRS038D Page 47 of 92

# 21 Frequency Programming

The frequency programming in *CC1100* is designed to minimize the programming needed in a channel-oriented system.

To set up a system with channel numbers, the desired channel spacing is programmed with the <code>MDMCFG0.CHANSPC\_M</code> and <code>MDMCFG1.CHANSPC\_E</code> registers. The channel spacing registers are mantissa and exponent respectively.

The base or start frequency is set by the 24 bit frequency word located in the FREQ2, FREQ1, and FREQ0 registers. This word will typically be set to the centre of the lowest channel frequency that is to be used.

The desired channel number is programmed with the 8-bit channel number register, CHANNR.CHAN, which is multiplied by the channel offset. The resultant carrier frequency is given by:

$$f_{carrier} = \frac{f_{XOSC}}{2^{16}} \cdot \left( FREQ + CHAN \cdot \left( (256 + CHANSPC \_M) \cdot 2^{CHANSPC \_E-2} \right) \right)$$

With a 26 MHz crystal the maximum channel spacing is 405 kHz. To get e.g. 1 MHz channel spacing one solution is to use 333 kHz channel spacing and select each third channel in CHANNR. CHAN.

The preferred IF frequency is programmed with the FSCTRL1.FREQ\_IF register. The IF frequency is given by:

$$f_{IF} = \frac{f_{XOSC}}{2^{10}} \cdot FREQ\_IF$$

### **22 VCO**

The VCO is completely integrated on-chip.

#### 22.1 VCO and PLL Self-Calibration

The VCO characteristics will vary with temperature and supply voltage changes, as well as the desired operating frequency. In order to ensure reliable operation, *CC1100* includes frequency synthesizer self-calibration circuitry. This calibration should be done regularly, and must be performed after turning on power and before using a new frequency (or channel). The number of XOSC cycles for completing the PLL calibration is given in Table 28 on page 45.

The calibration can be initiated automatically or manually. The synthesizer can be automatically calibrated each time the synthesizer is turned on, or each time the synthesizer is turned off automatically. This is configured with the MCSMO.FS\_AUTOCAL register setting. In manual mode, the calibration is initiated when the SCAL

Note that the SmartRF<sup>®</sup> Studio software [7] automatically calculates the optimum FSCTRL1.FREQ\_IF register setting based on channel spacing and channel filter bandwidth.

If any frequency programming register is altered when the frequency synthesizer is running, the synthesizer may give an undesired response. Hence, the frequency programming should only be updated when the radio is in the IDLE state.

command strobe is activated in the IDLE mode.

Note that the calibration values are maintained in SLEEP mode, so the calibration is still valid after waking up from SLEEP mode (unless supply voltage or temperature has changed significantly).

To check that the PLL is in lock the user can program register  ${\tt IOCFGx.GDOx\_CFG}$  to  ${\tt OxOA}$  and use the lock detector output available on the GDOx pin as an interrupt for the MCU (x = 0,1, or 2). A positive transition on the GDOx pin means that the PLL is in lock. As an alternative the user can read register FSCAL1. The PLL is in lock if the register content is different from  ${\tt Ox3F.Refer}$  also to the  ${\tt CC1100}$  Errata Notes [1]. For more robust operation the source code could include a check so that the PLL is re-calibrated until PLL lock is achieved if the PLL does not lock the first time.





# 23 Voltage Regulators

*CC1100* contains several on-chip linear voltage regulators, which generate the supply voltage needed by low-voltage modules. These voltage regulators are invisible to the user, and can be viewed as integral parts of the various modules. The user must however make sure that the absolute maximum ratings and required pin voltages in Table 1 and Table 13 are not exceeded. The voltage regulator for the digital core requires one external decoupling capacitor.

Setting the CSn pin low turns on the voltage regulator to the digital core and starts the crystal oscillator. The SO pin on the SPI interface must go low before the first positive edge of SCLK. (setup time is given in Table 16).

If the chip is programmed to enter power-down mode, (SPWD strobe issued), the power will be turned off after CSn goes high. The power and crystal oscillator will be turned on again when CSn goes low.

The voltage regulator output should only be used for driving the *CC1100*.

### 24 Output Power Programming

The RF output power level from the device has two levels of programmability, as illustrated in Figure 22. Firstly, the special PATABLE register can hold up to eight user selected output power settings. Secondly, the 3-bit FRENDO.PA\_POWER value selects the PATABLE entry to use. This two-level functionality provides flexible PA power ramp up and ramp down at the start and end of transmission, as well as ASK modulation shaping. All the PA power settings in the PATABLE from index 0 up to the FRENDO.PA POWER value are used.

The power ramping at the start and at the end of a packet can be turned off by setting FRENDO.PA\_POWER to zero and then program the desired output power to index 0 in the PATABLE.

If OOK modulation is used, the logic 0 and logic 1 power levels shall be programmed to index 0 and 1 respectively.

Table 30 contains recommended PATABLE settings for various output levels and frequency bands. Using PA settings from 0x61 to 0x6F is not recommended. See Section 10.6 on page 28 for PATABLE programming details.

Table 31 contains output power and current consumption for default PATABLE setting (0xC6). PATABLE must be programmed in burst mode if you want to write to other entries than PATABLE [0].

Note that all content of the PATABLE, except for the first byte (index 0) is lost when entering the SLEEP state.

	315 MHz		4	433 MHz		868 MHz		915 MHz	
Output Power [dBm]	Setting	Current Consumption, Typ. [mA]							
-30	0x04	10.6	0x04	11.5	0x03	11.9	0x11	11.8	
-20	0x17	11.1	0x17	12.1	0x0D	12.4	0x0D	12.3	
-15	0x1D	11.8	0x1C	12.7	0x1C	13.0	0x1C	13.0	
-10	0x26	13.0	0x26	14.0	0x34	14.5	0x26	14.3	
-5	0x57	12.9	0x57	13.7	0x57	14.1	0x57	13.9	
0	0x60	14.8	0x60	15.6	0x8E	16.9	0x8E	16.7	
5	0x85	18.1	0x85	19.1	0x85	20.0	0x83	19.9	
7	0xCB	22.1	0xC8	24.2	0xCC	25.8	0xC9	25.8	
10	0xC2	27.1	0xC0	29.2	0xC3	31.1	0xC0	32.3	

Table 30: Optimum PATABLE Settings for Various Output Power Levels and Frequency Bands



SWRS038D Page 49 of 92

	3	315 MHz		433 MHz		433 MHz		868 MHz		915 MHz
Default Power Setting	Output Power [dBm]	Current Consumption, Typ. [mA]								
0xC6	8.7	24.5	7.9	25.2	8.9	28.3	7.9	26.8		

Table 31: Output Power and Current Consumption for Default PATABLE Setting

# 25 Shaping and PA Ramping

With ASK modulation, up to eight power settings are used for shaping. The modulator contains a counter that counts up when transmitting a one and down when transmitting a zero. The counter counts at a rate equal to 8 times the symbol rate. The counter saturates at FRENDO.PA\_POWER and 0 respectively. This counter value is used as an index for a lookup in the power table. Thus, in order to utilize the whole table, FRENDO.PA POWER

should be 7 when ASK is active. The shaping of the ASK signal is dependent on the configuration of the PATABLE.

Note that the ASK shaping feature is only supported for output power levels up to -1 dBm and only values in the range 0x30–0x3F, together with 0x00 can be used. The same is the case when implementing PA ramping for other modulations formats. Figure 23 shows some examples of ASK shaping.




Figure 22: PA POWER and PATABLE




Figure 23: Shaping of ASK Signal



SWRS038D Page 50 of 92



	Output Power [dBm]					
PATABLE Setting	315 MHz	433 MHz	868 MHz	915 MHz		
0x00	-62.0	-62.0	-57.1	-56.0		
0x30	-41.7	-39.0	-33.6	-33.1		
0x31	-21.8	-21.7	-21.2	-21.0		
0x32	-16.2	-16.1	-16.0	-15.8		
0x33	-12.8	-12.7	-12.7	-12.5		
0x34	-10.5	-10.4	-10.5	-10.3		
0x35	-8.6	-8.5	-8.7	-8.5		
0x36	-7.2	-7.1	-7.4	-7.2		
0x37	-5.9	-5.8	-6.2	-6.0		
0x38	-4.8	-4.9	-5.3	-5.1		
0x39	-3.9	-4.0	-4.5	-4.3		
0x3A	-3.2	-3.3	-3.8	-3.7		
0x3B	-2.5	-2.7	-3.3	-3.1		
0x3C	-2.1	-2.3	-2.8	-2.7		
0x3D	-1.7	-1.9	-2.5	-2.3		
0x3E	-1.3	-1.6	-2.1	-2.0		
0x3F	-1.1	-1.3	-1.9	-1.7		

Table 32: PATABLE Settings used together with ASK Shaping and PA Ramping

Assume working in the 433 MHz and using FSK. The desired output power is -10 dBm. Figure 24 shows how the PATABLE should look like in the two cases where no ramping is used (A) and when PA ramping is being implemented (B). In case A, the PATABLE value is taken from Table 30, while in case B, the values are taken from Table 32.




Figure 24: PA Ramping



SWRS038D Page 51 of 92

# 26 Selectivity

Figure 25 to Figure 27 show the typical selectivity performance (adjacent and alternate rejection).




Figure 25: Typical Selectivity at 1.2 kBaud Data Rate, 868 MHz, 2-FSK, 5.2 kHz Deviation. IF Frequency is 152.3 kHz and the Digital Channel Filter Bandwidth is 58 kHz




Figure 26: Typical Selectivity at 38.4 kBaud Data Rate, 868 MHz, 2-FSK, 20 kHz Deviation. IF Frequency is 152.3 kHz and the Digital Channel Filter Bandwidth is 100 kHz






Figure 27: Typical Selectivity at 250 kBaud Data Rate, 868 MHz, MSK, IF Frequency is 254 kHz and the Digital Channel Filter Bandwidth is 540 kHz

### 27 Crystal Oscillator

A crystal in the frequency range 26-27 MHz must be connected between the XOSC\_Q1 and XOSC\_Q2 pins. The oscillator is designed for parallel mode operation of the crystal. In addition, loading capacitors (C81 and C101) for the crystal are required. The loading capacitor values depend on the total load capacitance,  $C_L$ , specified for the crystal. The total load capacitance seen between the crystal terminals should equal  $C_L$  for the crystal to oscillate at the specified frequency.

$$C_L = \frac{1}{\frac{1}{C_{81}} + \frac{1}{C_{101}}} + C_{parasitic}$$

The parasitic capacitance is constituted by pin input capacitance and PCB stray capacitance. Total parasitic capacitance is typically 2.5 pF.

The crystal oscillator circuit is shown in Figure 28. Typical component values for different values of  $C_L$  are given in Table 33.

The crystal oscillator is amplitude regulated. This means that a high current is used to start up the oscillations. When the amplitude builds up, the current is reduced to what is necessary to maintain approximately 0.4 Vpp signal swing. This ensures a fast start-up, and keeps the drive level to a minimum. The ESR of the crystal should be within the specification in order to ensure a reliable start-up (see Section 4.4 on page 14).

The initial tolerance, temperature drift, aging and load pulling should be carefully specified in order to meet the required frequency accuracy in a certain application.




Figure 28: Crystal Oscillator Circuit

Component	C <sub>L</sub> = 10 pF	C <sub>L</sub> = 13 pF	C <sub>L</sub> = 16 pF
C81	15 pF	22 pF	27 pF
C101	15 pF	22 pF	27 pF

**Table 33: Crystal Oscillator Component Values** 



SWRS038D Page 53 of 92



#### 27.1 Reference Signal

The chip can alternatively be operated with a reference signal from 26 to 27 MHz instead of a crystal. This input clock can either be a full-swing digital signal (0 V to VDD) or a sine wave of maximum 1 V peak-peak amplitude. The reference signal must be connected to the

XOSC\_Q1 input. The sine wave must be connected to XOSC\_Q1 using a serial capacitor. When using a full-swing digital signal this capacitor can be omitted. The XOSC\_Q2 line must be left un-connected. C81 and C101 can be omitted when using a reference signal.

#### 28 External RF Match

The balanced RF input and output of *CC1100* share two common pins and are designed for a simple, low-cost matching and balun network on the printed circuit board. The receive- and transmit switching at the *CC1100* front-end is controlled by a dedicated on-chip function, eliminating the need for an external RX/TX-switch.

A few passive external components combined with the internal RX/TX switch/termination circuitry ensures match in both RX and TX mode.

Although *CC1100* has a balanced RF input/output, the chip can be connected to a single-ended antenna with few external low cost capacitors and inductors.

The passive matching/filtering network connected to *CC1100* should have the following differential impedance as seen from the RF-port (RF\_P and RF\_N) towards the antenna:

 $Z_{\text{out } 315 \text{ MHz}} = 122 + j31 \Omega$ 

 $Z_{\text{out }433 \text{ MHz}} = 116 + j41 \Omega$ 

 $Z_{\text{out }868/915 \text{ MHz}} = 86.5 + j43 \Omega$ 

To ensure optimal matching of the *CC1100* differential output it is recommended to follow the CC1100EM reference design ([5] or [6]) as closely as possible. Gerber files for the reference designs are available for download from the TI website.

# 29 PCB Layout Recommendations

The top layer should be used for signal routing, and the open areas should be filled with metallization connected to ground using several vias

The area under the chip is used for grounding and shall be connected to the bottom ground plane with several vias. In the CC1100EM reference designs ([5] and [6]) we have placed 5 vias inside the exposed die attached pad. These vias should be "tented" (covered with solder mask) on the component side of the PCB to avoid migration of solder through the vias during the solder reflow process.

The solder paste coverage should not be 100%. If it is, out gassing may occur during the reflow process, which may cause defects (splattering, solder balling). Using "tented" vias reduces the solder paste coverage below 100%.

See Figure 29 for top solder resist and top paste masks.

Each decoupling capacitor should be placed as close as possible to the supply pin it is supposed to decouple. Each decoupling capacitor should be connected to the power line (or power plane) by separate vias. The best routing is from the power line (or power plane) to the decoupling capacitor and then to the *CC1100* supply pin. Supply power filtering is very important.

Each decoupling capacitor ground pad should be connected to the ground plane using a separate via. Direct connections between neighboring power pins will increase noise coupling and should be avoided unless absolutely necessary.

The external components should ideally be as small as possible (0402 is recommended) and surface mount devices are highly recommended. Please note that components smaller than those specified may have differing characteristics.

Precaution should be used when placing the microcontroller in order to avoid noise interfering with the RF circuitry.

A CC1100/1150DK Development Kit with a fully assembled CC1100EM Evaluation Module is available. It is strongly advised that this reference layout is followed very closely in order to get the best performance. The schematic, BOM and layout Gerber files are all available from the TI website ([5] and [6]).



SWRS038D Page 54 of 92




Figure 29: Left: Top Solder Resist Mask (Negative). Right: Top Paste Mask. Circles are Vias

### 30 General Purpose / Test Output Control Pins

The three digital output pins GDO0, GDO1, and GDO2 are general control pins configured with IOCFG0.GDO0\_CFG, IOCFG1.GDO1\_CFG, and IOCFG2.GDO3\_CFG respectively. Table 34 shows the different signals that can be monitored on the GDO pins. These signals can be used as inputs to the MCU. GDO1 is the same pin as the SO pin on the SPI interface, thus the output programmed on this pin will only be valid when CSn is high. The default value for GDO1 is 3-stated, which is useful when the SPI interface is shared with other devices.

The default value for GDO0 is a 135-141 kHz clock output (XOSC frequency divided by 192). Since the XOSC is turned on at power-on-reset, this can be used to clock the MCU in systems with only one crystal. When the MCU is up and running, it can change the clock frequency by writing to IOCFG0.GDO0 CFG.

An on-chip analog temperature sensor is enabled by writing the value 128 (0x80) to the

IOCFG0 register. The voltage on the GDO0 pin is then proportional to temperature. See Section 4.7 on page 16 for temperature sensor specifications.

If the IOCFGx.GDOx\_CFG setting is less than 0x20 and IOCFGx\_GDOx\_INV is 0 (1), the GDO0 and GDO2 pins will be hardwired to 0 (1) and the GDO1 pin will be hardwired to 1 (0) in the SLEEP state. These signals will be hardwired until the CHIP\_RDYn signal goes low.

If the <code>IOCFGx.GDOx\_CFG</code> setting is 0x20 or higher the GDO pins will work as programmed also in SLEEP state. As an example, GDO1 is high impedance in all states if <code>IOCFG1.GDO1\_CFG=0x2E</code>.





GDOx C	FG[5:0] Description						
0 (0x00)	Associated to the RX FIF	O: Asserts when RX FIFO is filled at or above the RX FIFO threshold. De-asserts when RX FIFO					
<u>`</u>	is drained below the sam Associated to the RX FIF	ie threshold.  O: Asserts when RX FIFO is filled at or above the RX FIFO threshold or the end of packet is					
1 (0x01)	reached. De-asserts whe	en the RX FIFO is empty.					
2 (0x02)	Associated to the TX FIFO: Asserts when the TX FIFO is filled at or above the TX FIFO threshold. De-asserts when the TX FIFO is below the same threshold.						
3 (0x03)	Associated to the TX FIF threshold.	O: Asserts when TX FIFO is full. De-asserts when the TX FIFO is drained below the TX FIFO					
4 (0x04)	Asserts when the RX FIF	O has overflowed. De-asserts when the FIFO has been flushed.					
5 (0x05)		O has underflowed. De-asserts when the FIFO is flushed. has been sent / received, and de-asserts at the end of the packet. In RX, the pin will de-assert					
6 (0x06)	when the optional address	ss check fails or the RX FIFO overflows. In TX the pin will de-assert if the TX FIFO underflows.					
7 (0x07) 8 (0x08)	Asserts when a packet he Preamble Quality Reach	as been received with CRC OK. De-asserts when the first byte is read from the RX FIFO.  ed. Asserts when the PQI is above the programmed PQT value.					
9 (0x09)	Clear channel assessme	nt. High when RSSI level is below threshold (dependent on the current CCA MODE setting)					
10 (0x0A)	check for PLL lock the lo	e PLL is in lock if the lock detector output has a positive transition or is constantly logic high. To ck detector output should be used as an interrupt for the MCU.					
11 (0v0D)	Serial Clock. Synchronou	us to the data in synchronous serial mode.					
11 (0x0B)	In TX mode, data is sam	up on the falling edge by CC1100 when GDOx_INV=0.  pled by CC1100 on the rising edge of the serial clock when GDOx_INV=0.					
12 (0x0C)	Serial Synchronous Data	Output. Used for synchronous serial mode.					
13 (0x0D) 14 (0x0E)	Carrier sense High if RS	I for asynchronous serial mode. SI level is above threshold.					
15 (0x0F)	CRC_OK. The last CRC	comparison matched. Cleared when entering/restarting RX mode.					
16 (0x10)	Reserved – used for test						
17 (0x11) 18 (0x12)	Reserved – used for test Reserved – used for test						
19 (0x12)	Reserved – used for test						
20 (0x14)	Reserved – used for test						
21 (0x15)	Reserved – used for test						
22 (0x16) 23 (0x17)	RX_HARD_DATA[1]. Ca	n be used together with RX_SYMBOL_TICK for alternative serial RX output.  n be used together with RX_SYMBOL_TICK for alternative serial RX output.					
24 (0x18)	Reserved – used for test						
25 (0x19)	Reserved – used for test						
26 (0x1A)	Reserved – used for test	Il have the same signal level in SLEEP and TX states. To control an external PA or RX/TX switch					
27 (0x1B)	in applications where the	SLEEP state is used it is recommended to use GDOx CFGx=0x2F instead.  will have the same signal level in SLEEP and RX states. To control an external LNA or RX/TX					
28 (0x1C)	switch in applications wh	ere the SLEEP state is used it is recommended to use GDOx CFGx=0x2F instead.					
29 (0x1D) 30 (0x1E)	RX_SYMBOL_TICK. Car Reserved – used for test	n be used together with RX_HARD_DATA for alternative serial RX output.					
31 (0x1F)	Reserved – used for test						
32 (0x20)	Reserved – used for test						
33 (0x21) 34 (0x22)	Reserved – used for test Reserved – used for test						
35 (0x23)	Reserved – used for test						
36 (0x24)	WOR_EVNT0	•					
37 (0x25)	WOR_EVNT1						
38 (0x26) 39 (0x27)	Reserved – used for test CLK_32k	•					
40 (0x28)	Reserved – used for test						
41 (0x29)	CHIP_RDYn						
42 (0x2A)	Reserved – used for test						
43 (0x2B) 44 (0x2C)	XOSC_STABLE  Reserved – used for test						
45 (0x2C)	GDO0 Z EN N. When	this output is 0, GDO0 is configured as input (for serial TX data).					
46 (0x2E)	High impedance (3-state						
47 (0x2F)	HW to 0 (HW1 achieved	by setting GDOx INV=1). Can be used to control an external LNA/PA or RX/TX switch.					
48 (0x30) 49 (0x31)	CLK_XOSC/1 CLK_XOSC/1.5						
50 (0x32)	CLK_XOSC/2						
51 (0x33)	CLK_XOSC/3						
52 (0x34) 53 (0x35)	CLK_XOSC/4 CLK_XOSC/6	Note: There are 3 GDO pins, but only one CLK_XOSC/n can be selected as an output at any					
54 (0x36)	CLK_XOSC/8	time. If CLK_XOSC/n is to be monitored on one of the GDO pins, the other two GDO pins must					
55 (0x37)	CLK_XOSC/12	be configured to values less than 0x30. The GDO0 default value is CLK_XOSC/192.					
56 (0x38)	CLK_XOSC/16	To optimize rf performance, these signal should not be used while the radio is in RX or TX mode.					
57 (0x39)	CLK_XOSC/24	The state of the s					
58 (0x3A) 59 (0x3B)	CLK_XOSC/32 CLK_XOSC/48						
60 (0x3C)	CLK_XOSC/64						
61 (0x3D)	CLK_XOSC/96						
62 (0x3E)	CLK_XOSC/128						
63 (0x3F)	CLK_XOSC/192						

Table 34: GDOx Signal Selection (x = 0, 1, or 2)





### 31 Asynchronous and Synchronous Serial Operation

Several features and modes of operation have been included in the *CC1100* to provide backward compatibility with previous Chipcon products and other existing RF communication systems. For new systems, it is recommended to use the built-in packet handling features, as they can give more robust communication, significantly offload the microcontroller, and simplify software development.

#### 31.1 Asynchronous Operation

For backward compatibility with systems already using the asynchronous data transfer from other Chipcon products, asynchronous transfer is also included in *CC1100*. When asynchronous transfer is enabled, several of the support mechanisms for the MCU that are included in *CC1100* will be disabled, such as packet handling hardware, buffering in the FIFO, and so on. The asynchronous transfer mode does not allow the use of the data whitener, interleaver, and FEC, and it is not possible to use Manchester encoding.

Note that MSK is not supported for asynchronous transfer.

Setting PKTCTRL0.PKT\_FORMAT to 3 enables asynchronous serial mode.

In TX, the GDO0 pin is used for data input (TX data). Data output can be on GDO0, GDO1, or GDO2. This is set by the <code>IOCFG0.GDO0\_CFG</code>, <code>IOCFG1.GDO1\_CFG</code> and <code>IOCFG2.GDO2\_CFG</code> fields.

The *CC1100* modulator samples the level of the asynchronous input 8 times faster than the programmed data rate. The timing requirement for the asynchronous stream is that the error in the bit period must be less than one eighth of the programmed data rate.

#### 31.2 Synchronous Serial Operation

Setting PKTCTRL0.PKT\_FORMAT to 1 enables synchronous serial mode. In the synchronous serial mode, data is transferred on a two wire serial interface. The *CC1100* provides a clock that is used to set up new data on the data input line or sample data on the data output line. Data input (TX data) is the GDO0 pin. This pin will automatically be configured as an input when TX is active. The data output pin can be any of the GDO pins; this is set by the IOCFG0.GDO0\_CFG, IOCFG1.GDO1\_CFG, and IOCFG2.GDO2\_CFG fields.

Preamble and sync word insertion/detection may or may not be active, dependent on the sync mode set by the MDMCFG2.SYNC\_MODE. If preamble and sync word is disabled, all other packet handler features and FEC should also be disabled. The MCU must then handle preamble and sync word insertion and detection in software. If preamble and sync word insertion/detection is left on, all packet handling features and FEC can be used. One exception is that the address filtering feature is unavailable in synchronous serial mode.

When using the packet handling features in synchronous serial mode, the *CC1100* will insert and detect the preamble and sync word and the MCU will only provide/get the data payload. This is equivalent to the recommended FIFO operation mode.

# 32 System Considerations and Guidelines

#### 32.1 SRD Regulations

International regulations and national laws regulate the use of radio receivers and transmitters. Short Range Devices (SRDs) for license free operation below 1 GHz are usually operated in the 433 MHz, 868 MHz or 915 MHz frequency bands. The *CC1100* is specifically designed for such use with its 300 - 348 MHz, 400 - 464 MHz, and 800 - 928 MHz operating ranges. The most important regulations when using the *CC1100* in the 433

MHz, 868 MHz, or 915 MHz frequency bands are EN 300 220 (Europe) and FCC CFR47 part 15 (USA). A summary of the most important aspects of these regulations can be found in Application Note AN001 [2].

Please note that compliance with regulations is dependent on complete system performance. It is the customer's responsibility to ensure that the system complies with regulations.



SWRS038D Page 57 of 92



### 32.2 Frequency Hopping and Multi-Channel Systems

The 433 MHz, 868 MHz, or 915 MHz bands are shared by many systems both in industrial, office, and home environments. It is therefore recommended to use frequency hopping spread spectrum (FHSS) or a multi-channel protocol because the frequency diversity makes the system more robust with respect to interference from other systems operating in the same frequency band. FHSS also combats multipath fading.

*CC1100* is highly suited for FHSS or multichannel systems due to its agile frequency synthesizer and effective communication interface. Using the packet handling support and data buffering is also beneficial in such systems as these features will significantly offload the host controller.

Charge pump current, VCO current, and VCO capacitance array calibration data is required for each frequency when implementing frequency hopping for *CC1100*. There are 3 ways of obtaining the calibration data from the chip:

- 1) Frequency hopping with calibration for each hop. The PLL calibration time is approximately 720 µs. The blanking interval between each frequency hop is then approximately 810 us.
- 2) Fast frequency hopping without calibration for each hop can be done by calibrating each frequency at startup and saving the resulting FSCAL3, FSCAL2, and FSCAL1 register values in MCU memory. Between each frequency hop, the calibration process can then be replaced by writing the FSCAL3, FSCAL2and FSCAL1 register values corresponding to the next RF frequency. The PLL turn on time is approximately 90 µs. The blanking interval between each frequency hop is then approximately 90 us. The VCO current calibration result available in FSCAL2 is not dependent on the RF frequency. Neither is the charge pump current calibration result available in FSCAL3. The same value can therefore be used for all frequencies.
- 3) Run calibration on a single frequency at startup. Next write 0 to FSCAL3 [5:4] to disable the charge pump calibration. After writing to FSCAL3 [5:4] strobe SRX (or STX) with MCSM0.FS\_AUTOCAL=1 for each new frequency hop. That is, VCO current and VCO capacitance calibration is done but not charge pump current calibration. When charge pump current calibration is disabled the calibration

time is reduced from approximately 720  $\mu$ s to approximately 150  $\mu$ s. The blanking interval between each frequency hop is then approximately 240 us.

There is a trade off between blanking time and memory space needed for storing calibration data in non-volatile memory. Solution 2) above gives the shortest blanking interval, but requires more memory space to store calibration values. Solution 3) gives approximately 570 µs smaller blanking interval than solution 1).

Note that the recommended settings for TESTO.VCO\_SEL\_CAL\_EN will change with frequency. This means that one should always use SmartRF® Studio [7] to get the correct settings for a specific frequency before doing a calibration, regardless of which calibration method is being used.

It must be noted that the  $\mathtt{TESTn}$  registers (n = 0, 1, or 2) content is not retained in SLEEP state, and thus it is necessary to re-write these registers when returning from the SLEEP state.

# 32.3 Wideband Modulation not Using Spread Spectrum

Digital modulation systems under FFC part 15.247 includes 2-FSK and GFSK modulation. A maximum peak output power of 1W (+30 dBm) is allowed if the 6 dB bandwidth of the modulated signal exceeds 500 kHz. In addition, the peak power spectral density conducted to the antenna shall not be greater than +8 dBm in any 3 kHz band.

Operating at high data rates and frequency separation, the *CC1100* is suited for systems targeting compliance with digital modulation system as defined by FFC part 15.247. An external power amplifier is needed to increase the output above +10 dBm.

#### 32.4 Data Burst Transmissions

The high maximum data rate of *CC1100* opens up for burst transmissions. A low average data rate link (e.g. 10 kBaud), can be realized using a higher over-the-air data rate. Buffering the data and transmitting in bursts at high data rate (e.g. 500 kBaud) will reduce the time in active mode, and hence also reduce the average current consumption significantly. Reducing the time in active mode will reduce the likelihood of collisions with other systems in the same frequency range.



SWRS038D Page 58 of 92



#### 32.5 Continuous Transmissions

In data streaming applications the *CC1100* opens up for continuous transmissions at 500 kBaud effective data rate. As the modulation is done with a closed loop PLL, there is no limitation in the length of a transmission (open loop modulation used in some transceivers often prevents this kind of continuous data streaming and reduces the effective data rate).

### 32.6 Crystal Drift Compensation

The *CC1100* has a very fine frequency resolution (see Table 9). This feature can be used to compensate for frequency offset and drift.

The frequency offset between an 'external' transmitter and the receiver is measured in the *CC1100* and can be read back from the FREQEST status register as described in Section 14.1. The measured frequency offset can be used to calibrate the frequency using the 'external' transmitter as the reference. That is, the received signal of the device will match the receiver's channel filter better. In the same way the centre frequency of the transmitted signal will match the 'external' transmitter's signal.

#### 32.7 Spectrum Efficient Modulation

*CC1100* also has the possibility to use Gaussian shaped 2-FSK (GFSK). This spectrum-shaping feature improves adjacent channel power (ACP) and occupied bandwidth. In 'true' 2-FSK systems with abrupt frequency shifting, the spectrum is inherently broad. By making the frequency shift 'softer', the spectrum can be made significantly narrower. Thus, higher data rates can be transmitted in the same bandwidth using GFSK.

#### 32.8 Low Cost Systems

As the *CC1100* provides 500 kBaud multichannel performance without any external filters, a very low cost system can be made.

A differential antenna will eliminate the need for a balun, and the DC biasing can be achieved in the antenna topology, see Figure 3 and Figure 4.

A HC-49 type SMD crystal is used in the CC1100EM reference designs ([5] and [6]). Note that the crystal package strongly influences the price. In a size constrained PCB design a smaller, but more expensive, crystal may be used.

#### 32.9 Battery Operated Systems

In low power applications, the SLEEP state with the crystal oscillator core switched off should be used when the *CC1100* is not active. It is possible to leave the crystal oscillator core running in the SLEEP state if start-up time is critical.

The WOR functionality should be used in low power applications.

#### 32.10 Increasing Output Power

In some applications it may be necessary to extend the link range. Adding an external power amplifier is the most effective way of doing this.

The power amplifier should be inserted between the antenna and the balun, and two T/R switches are needed to disconnect the PA in RX mode. See Figure 30.




Figure 30: Block Diagram of CC1100 Usage with External Power Amplifier



SWRS038D Page 59 of 92



# 33 Configuration Registers

The configuration of *CC1100* is done by programming 8-bit registers. The optimum configuration data based on selected system parameters are most easily found by using the SmartRF® Studio software [7]. Complete descriptions of the registers are given in the following tables. After chip reset, all the registers have default values as shown in the tables. The optimum register setting might differ from the default value. After a reset all registers that shall be different from the default value therefore needs to be programmed through the SPI interface.

There are 13 command strobe registers, listed in Table 35. Accessing these registers will initiate the change of an internal state or mode. There are 47 normal 8-bit configuration registers, listed in Table 36. Many of these registers are for test purposes only, and need not be written for normal operation of *CC1100*.

There are also 12 Status registers, which are listed in Table 37. These registers, which are read-only, contain information about the status of *CC1100*.

The two FIFOs are accessed through one 8-bit register. Write operations write to the TX FIFO, while read operations read from the RX FIFO.

During the header byte transfer and while writing data to a register or the TX FIFO, a status byte is returned on the SO line. This status byte is described in Table 17 on page 26.

Table 38 summarizes the SPI address space. The address to use is given by adding the base address to the left and the burst and read/write bits on the top. Note that the burst bit has different meaning for base addresses above and below 0x2F.

Address	Strobe Name	Description
0x30	SRES	Reset chip.
0x31	SFSTXON	Enable and calibrate frequency synthesizer (if MCSM0 . FS_AUTOCAL=1). If in RX (with CCA): Go to a wait state where only the synthesizer is running (for quick RX / TX turnaround).
0x32	SXOFF	Turn off crystal oscillator.
0x33	SCAL	Calibrate frequency synthesizer and turn it off. SCAL can be strobed from IDLE mode without setting manual calibration mode (MCSM0.FS_AUTOCAL=0)
0x34	SRX	Enable RX. Perform calibration first if coming from IDLE and MCSM0 . FS_AUTOCAL=1.
0x35	STX	In IDLE state: Enable TX. Perform calibration first if MCSM0.FS_AUTOCAL=1.  If in RX state and CCA is enabled: Only go to TX if channel is clear.
0x36	SIDLE	Exit RX / TX, turn off frequency synthesizer and exit Wake-On-Radio mode if applicable.
0x38	SWOR	Start automatic RX polling sequence (Wake-on-Radio) as described in Section 19.5 if WORCTRL.RC_PD=0.
0x39	SPWD	Enter power down mode when CSn goes high.
0x3A	SFRX	Flush the RX FIFO buffer. Only issue SFRX in IDLE or, RXFIFO_OVERFLOW states.
0x3B	SFTX	Flush the TX FIFO buffer. Only issue SFTX in IDLE or TXFIFO_UNDERFLOW states.
0x3C	SWORRST	Reset real time clock to Event1 value.
0x3D	SNOP	No operation. May be used to get access to the chip status byte.

**Table 35: Command Strobes** 



SWRS038D Page 60 of 92



Address	Register	Description	Preserved in SLEEP State	Details on Page Number
0x00	IOCFG2	GDO2 output pin configuration	Yes	64
0x01	IOCFG1	GDO1 output pin configuration	Yes	64
0x02	IOCFG0	GDO0 output pin configuration	Yes	64
0x03	FIFOTHR	RX FIFO and TX FIFO thresholds	Yes	65
0x04	SYNC1	Sync word, high byte	Yes	65
0x05	SYNC0	Sync word, low byte	Yes	65
0x06	PKTLEN	Packet length	Yes	65
0x07	PKTCTRL1	Packet automation control	Yes	66
0x08	PKTCTRL0	Packet automation control	Yes	67
0x09	ADDR	Device address	Yes	67
0x0A	CHANNR	Channel number	Yes	67
0x0B	FSCTRL1	Frequency synthesizer control	Yes	68
0x0C	FSCTRL0	Frequency synthesizer control	Yes	68
0x0D	FREQ2	Frequency control word, high byte	Yes	68
0x0E	FREQ1	Frequency control word, middle byte	Yes	68
0x0F	FREQ0	Frequency control word, low byte	Yes	68
0x10	MDMCFG4	Modem configuration	Yes	69
0x11	MDMCFG3	Modem configuration	Yes	69
0x12	MDMCFG2	Modem configuration	Yes	70
0x13	MDMCFG1	Modem configuration	Yes	71
0x14	MDMCFG0	Modem configuration	Yes	71
0x15	DEVIATN	Modem deviation setting	Yes	72
0x16	MCSM2	Main Radio Control State Machine configuration	Yes	73
0x17	MCSM1	Main Radio Control State Machine configuration	Yes	74
0x18	MCSM0	Main Radio Control State Machine configuration	Yes	75
0x19	FOCCFG	Frequency Offset Compensation configuration	Yes	76
0x1A	BSCFG	Bit Synchronization configuration	Yes	77
0x1B	AGCTRL2	AGC control	Yes	78
0x1C	AGCTRL1	AGC control	Yes	79
0x1D	AGCTRL0	AGC control	Yes	80
0x1E	WOREVT1	High byte Event 0 timeout	Yes	80
0x1F	WOREVT0	Low byte Event 0 timeout	Yes	81
0x20	WORCTRL	Wake On Radio control	Yes	81
0x21	FREND1	Front end RX configuration	Yes	82
0x22	FREND0	Front end TX configuration	Yes	82
0x23	FSCAL3	Frequency synthesizer calibration	Yes	82
0x24	FSCAL2	Frequency synthesizer calibration	Yes	83
0x25	FSCAL1	Frequency synthesizer calibration	Yes	83
0x26	FSCAL0	Frequency synthesizer calibration	Yes	83
0x27	RCCTRL1	RC oscillator configuration	Yes	83
0x28	RCCTRL0	RC oscillator configuration	Yes	83
0x29	FSTEST	Frequency synthesizer calibration control	No	84
0x2A	PTEST	Production test	No	84
0x2B	AGCTEST	AGC test	No	84
0x2C	TEST2	Various test settings	No	84
0x2D	TEST1	Various test settings	No	84
0x2E	TEST0	Various test settings	No	84

**Table 36: Configuration Registers Overview** 



SWRS038D Page 61 of 92



Address	Register	Description	Details on page number
0x30 (0xF0)	PARTNUM	Part number for CC1100	85
0x31 (0xF1)	VERSION	Current version number	85
0x32 (0xF2)	FREQEST	Frequency Offset Estimate	85
0x33 (0xF3)	LQI	Demodulator estimate for Link Quality	85
0x34 (0xF4)	RSSI	Received signal strength indication	85
0x35 (0xF5)	MARCSTATE	Control state machine state	86
0x36 (0xF6)	WORTIME1	High byte of WOR timer	86
0x37 (0xF7)	WORTIME0	Low byte of WOR timer	86
0x38 (0xF8)	PKTSTATUS	Current GDOx status and packet status	87
0x39 (0xF9)	VCO_VC_DAC	Current setting from PLL calibration module	87
0x3A (0xFA)	TXBYTES	Underflow and number of bytes in the TX FIFO	87
0x3B (0xFB)	RXBYTES	Overflow and number of bytes in the RX FIFO	87
0x3C (0xFC)	RCCTRL1_STATUS	Last RC oscillator calibration result	87
0x3D (0xFD)	RCCTRL0_STATUS	Last RC oscillator calibration result	88

**Table 37: Status Registers Overview** 




	Wr	ite		Read								
	Single Byte	Burst	Single Byte	Burst								
0.00	+0x00 +0x40 +0x80 +0xC0											
0x00 0x01		IOCFG2 IOCFG1										
0x01			OCFG0									
0x02		FIFOTHR										
0x04	SYNC1											
0x05		S	SYNC0									
0x06			KTLEN									
0x07			TCTRL1									
0x08			TCTRL0									
0x09			ADDR									
0x0A 0x0B			HANNR SCTRL1									
0x0C			CTRL0									
0x0D			REQ2									
0x0E			REQ1									
0x0F			REQ0		ible							
0x10			MCFG4		SSC							
0x11			MCFG3		) bc							
0x12			MCFG2 MCFG1		ess							
0x13 0x14			MCFG1 MCFG0		эсс							
0x14 0x15			EVIATN		R/W configuration registers, burst access possible							
0x16			ICSM2		ınq							
0x17			ICSM1		ſS,							
0x18			ICSM0		ste							
0x19			OCCFG		egi.							
0x1A			SCFG		uc							
0x1B 0x1C			CCTRL2		atic							
0x1C		AGCCTRL1 AGCCTRL0										
0x1E		WOREVT1										
0x1F			DREVT0		) >							
0x20			DRCTRL		ΣŞ							
0x21			REND1									
0x22 0x23			REND0 SCAL3									
0x23 0x24			SCAL3									
0x25			SCAL1									
0x26			SCAL0									
0x27			CTRL1									
0x28			CCTRL0									
0x29 0x2A			STEST PTEST									
0x2A 0x2B			CTEST									
0x2C			EST2									
0x2D		T	EST1									
0x2E		7	EST0									
0x2F	0050		0050	DADTNU								
0x30	SRES		SRES	PARTNUM								
0x31 0x32	SFSTXON SXOFF		SFSTXON SXOFF	VERSION FREQEST	Ø							
0x32	SCAL		SCAL	LQI	ster							
0x34	SRX		SRX	RSSI	Status registers ti byte registers							
0x35	STX	STX STX MARCSTATE										
0x36	SIDLE SIDLE WORTIME1											
0x37	WORTIME0											
0x38	SWOR SWOR PKTSTATUS											
0x39 0x3A	SPWD	SPWD     SPWD     VCO_VC_DAC       SFRX     SFRX     TXBYTES										
0x3A 0x3B	SFTX		SFTX	RXBYTES	d Strobes, S ) and multi							
0x3C	SWORRST		SWORRST	RCCTRL1_STATUS	Command S (read only) a							
0x3D	SNOP		SNOP	RCCTRL0_STATUS	mu o p							
0x3E	PATABLE	PATABLE	PATABLE	PATABLE	Sor							
0x3F	TX FIFO	TX FIFO	RX FIFO	RX FIFO	)							

Table 38: SPI Address Space



SWRS038D Page 63 of 92



# 33.1 Configuration Register Details – Registers with preserved values in SLEEP state

# 0x00: IOCFG2 - GDO2 Output Pin Configuration

Bit	Field Name	Reset	R/W	Description
7	Reserved		R0	
6	GDO2_INV	0	R/W	Invert output, i.e. select active low (1) / high (0)
5:0	GDO2_CFG[5:0]	41 (0x29)	R/W	Default is CHP_RDYn (See Table 34 on page 56).


# 0x01: IOCFG1 - GDO1 Output Pin Configuration

Bit	Field Name	Reset	R/W	Description
7	GDO_DS	0	R/W	Set high (1) or low (0) output drive strength on the GDO pins.
6	GDO1_INV	0	R/W	Invert output, i.e. select active low (1) / high (0)
5:0	GDO1_CFG[5:0]	46 (0x2E)	R/W	Default is 3-state (See Table 34 on page 56).

# 0x02: IOCFG0 - GDO0 Output Pin Configuration

Bit	Field Name	Reset	R/W	Description
7	TEMP_SENSOR_ENABLE	0	R/W	Enable analog temperature sensor. Write 0 in all other register bits when using temperature sensor.
6	GDO0_INV	0	R/W	Invert output, i.e. select active low (1) / high (0)
5:0	GDO0_CFG[5:0]	63 (0x3F)	R/W	Default is CLK_XOSC/192 (See Table 34 on page 56).
				It is recommended to disable the clock output in initialization, in order to optimize RF performance.





# 0x03: FIFOTHR - RX FIFO and TX FIFO Thresholds

Bit	Field Name	Reset	R/W	Description	Description			
7:4	Reserved	0	R/W	Write 0 for co	Write 0 for compatibility with possible future extensions			
3:0	FIFO_THR[3:0]	7 (0111)	R/W	Set the threshold for the TX FIFO and RX FIFO. The threshold is exceeded when the number of bytes in the FIFO is equal to or higher than the threshold value.				
				Setting	Bytes in TX FIFO	Bytes in RX FIFO		
				0 (0000)	61	4		
				1 (0001)	57	8		
				2 (0010)	53	12		
				3 (0011)	49	16		
				4 (0100)	45	20		
				5 (0101)	41	24		
				6 (0110)	37	28		
				7 (0111)	33	32		
				8 (1000)	29	36		
				9 (1001)	25	40		
				10 (1010)	21	44		
				11 (1011)	17	48		
				12 (1100)	13	52		
				13 (1101)	9	56		
				14 (1110)	5	60		
				15 (1111)	1	64		

# 0x04: SYNC1 - Sync Word, High Byte

Bit	Field Name	Reset	R/W	Description
7:0	SYNC[15:8]	211 (0xD3)	R/W	8 MSB of 16-bit sync word

# 0x05: SYNC0 - Sync Word, Low Byte

Bit	Field Name	Reset	R/W	Description
7:0	SYNC[7:0]	145 (0x91)	R/W	8 LSB of 16-bit sync word

# 0x06: PKTLEN - Packet Length

Bit	Field Name	Reset	R/W	Description
7:0	PACKET_LENGTH	255 (0xFF)	R/W	Indicates the packet length when fixed packet length mode is enabled. If variable packet length mode is used, this value indicates the maximum packet length allowed.






# 0x07: PKTCTRL1 - Packet Automation Control

Bit	Field Name	Reset	R/W	Description	on	
7:5	PQT[2:0]	0 (0x00)	R/W	Preamble quality estimator threshold. The preamble quality estimator increases an internal counter by one each time a bit is received that is different from the previous bit, and decreases the counter by 8 each time a bit is received that is the same as the last bit.  A threshold of $4 \cdot PQT$ for this counter is used to gate sync word detection.		
				When PQT	r=0 a sync word is always accepted.	
4	Reserved	0	R0			
3	CRC_AUTOFLUSH	0	R/W	Enable automatic flush of RX FIFO when CRC in not OK. This requires that only one packet is in the RXIFIFO and that packet length is limited to the RX FIFO size.		
2	APPEND_STATUS	1	R/W		bled, two status bytes will be appended to the payload of the e status bytes contain RSSI and LQI values, as well as CRC	
1:0	ADR_CHK[1:0]	0 (00)	R/W	Controls a	ddress check configuration of received packages.	
				Setting	Address check configuration	
				0 (00)	No address check	
				1 (01)	Address check, no broadcast	
				2 (10)	Address check and 0 (0x00) broadcast	
				3 (11)	Address check and 0 (0x00) and 255 (0xFF) broadcast	





# 0x08: PKTCTRL0 - Packet Automation Control

Bit	Field Name	Reset	R/W	Description	Description		
7	Reserved		R0				
6	WHITE_DATA	1	R/W	Turn data	whitening on / off		
				0: Whiteni 1: Whiteni			
5:4	PKT_FORMAT[1:0]	0 (00)	R/W	Format of	RX and TX data		
				Setting	Packet format		
				0 (00)	Normal mode, use FIFOs for RX and TX		
				1 (01)	Synchronous serial mode, used for backwards compatibility. Data in on GDO0		
				2 (10)	Random TX mode; sends random data using PN9 generator. Used for test. Works as normal mode, setting 0 (00), in RX.		
				3 (11)	Asynchronous serial mode. Data in on GDO0 and Data out on either of the GDO0 pins		
3	Reserved	0	R0	,			
2	CRC_EN	1	R/W	1: CRC ca	lculation in TX and CRC check in RX enabled		
				0: CRC dis	sabled for TX and RX		
1:0	LENGTH_CONFIG[1:0]	1 (01)	R/W	Configure	the packet length		
				Setting	Packet length configuration		
				0 (00)	Fixed packet length mode. Length configured in PKTLEN register		
				1 (01)	Variable packet length mode. Packet length configured by the first byte after sync word		
				2 (10)	Infinite packet length mode		
				3 (11)	Reserved		

# 0x09: ADDR - Device Address

Bit	Field Name	Reset	R/W	Description
7:0	DEVICE_ADDR[7:0]	0 (0x00)	R/W	Address used for packet filtration. Optional broadcast addresses are 0 (0x00) and 255 (0xFF).

### 0x0A: CHANNR - Channel Number

Bit	Field Name	Reset	R/W	Description
7:0	CHAN[7:0]	0 (0x00)	R/W	The 8-bit unsigned channel number, which is multiplied by the channel spacing setting and added to the base frequency.





# 0x0B: FSCTRL1 - Frequency Synthesizer Control

Bit	Field Name	Reset	R/W	Description
7:5	Reserved		R0	
4:0	FREQ_IF[4:0]	15 (0x0F)	R/W	The desired IF frequency to employ in RX. Subtracted from FS base frequency in RX and controls the digital complex mixer in the demodulator. $f_{IF} = \frac{f_{XOSC}}{2^{10}} \cdot FREQ\_IF$ The default value gives an IF frequency of 381kHz, assuming a 26.0 MHz crystal.

# 0x0C: FSCTRL0 - Frequency Synthesizer Control

Bit	Field Name	Reset	R/W	Description
7:0	FREQOFF[7:0]	0 (0x00)	R/W	Frequency offset added to the base frequency before being used by the frequency synthesizer. (2s-complement).
				Resolution is $F_{XTAL}/2^{14}$ (1.59kHz-1.65kHz); range is $\pm 202$ kHz to $\pm 210$ kHz, dependent of XTAL frequency.

# 0x0D: FREQ2 - Frequency Control Word, High Byte

Bit	Field Name	Reset	R/W	Description
7:6	FREQ[23:22]	0 (00)	R	FREQ [23:22] is always 0 (the FREQ2 register is less than 36 with 26-27 MHz crystal)
5:0	FREQ[21:16]	30 (0x1E)	R/W	FREQ [23:22] is the base frequency for the frequency synthesiser in increments of $F_{XOSC}/2^{16}$ . $f_{carrier} = \frac{f_{XOSC}}{2^{16}} \cdot FREQ [23:0]$

# 0x0E: FREQ1 - Frequency Control Word, Middle Byte


Bit	Field Name	Reset	R/W	Description
7:0	FREQ[15:8]	196 (0xC4)	R/W	Ref. FREQ2 register

# 0x0F: FREQ0 - Frequency Control Word, Low Byte

Bit	Field Name	Reset	R/W	Description	
7:0	FREQ[7:0]	236 (0xEC)	R/W	Ref. FREQ2 register	



Page 68 of 92



# 0x10: MDMCFG4 - Modem Configuration

Bit	Field Name	Reset	R/W	Description	
7:6	CHANBW_E[1:0]	2 (0x02)	R/W		
5:4	CHANBW_M[1:0]	0 (0x00)	R/W	Sets the decimation ratio for the delta-sigma ADC input stream and thus the channel bandwidth. $BW_{channel} = \frac{f_{XOSC}}{8\cdot(4+CHANBW\_M)\cdot2^{CHANBW\_E}}$ The default values give 203 kHz channel filter bandwidth, assuming a 26.0 MHz crystal.	
3:0	DRATE_E[3:0]	12 (0x0C)	R/W	The exponent of the user specified symbol rate	

# 0x11: MDMCFG3 – Modem Configuration

Bit	Field Name	Reset	R/W	Description
7:0	DRATE_M[7:0]	34 (0x22)	R/W	The mantissa of the user specified symbol rate. The symbol rate is configured using an unsigned, floating-point number with 9-bit mantissa and 4-bit exponent. The 9 <sup>th</sup> bit is a hidden '1'. The resulting data rate is: $R_{DATA} = \frac{\left(256 + DRATE\_M\right) \cdot 2^{DRATE\_E}}{2^{28}} \cdot f_{XOSC}$ The default values give a data rate of 115.051 kBaud (closest setting to 115.2 kBaud), assuming a 26.0 MHz crystal.





# 0x12: MDMCFG2 – Modem Configuration

Bit	Field Name	Reset	R/W	Description	n		
7	DEM_DCFILT_OFF	0	R/W	Disable digi	ital DC blocking filter before demodulator.		
				0 = Enable	(better sensitivity)		
				1 = Disable (current optimized). Only for data rates ≤ 250 kBaud			
				The recommended IF frequency changes when the DC blocking is disabled. Please use SmartRF® Studio [7] to calculate correct register setting.			
6:4	MOD_FORMAT[2:0]	0 (000)	R/W	The modula	ation format of the radio signal		
				Setting	Modulation format		
				0 (000)	2-FSK		
				1 (001)	GFSK		
				2 (010)	-		
				3 (011)	ASK/OOK		
				4 (100)	-		
				5 (101)	-		
				6 (110)	-		
				7 (111)	MSK		
				ASK is only	supported for output powers up to -1 dBm		
				MSK is only supported for datarates above 26 kBaud			
3	MANCHESTER_EN	0	R/W	Enables Manchester encoding/decoding.			
				0 = Disable			
				1 = Enable			
2:0	SYNC_MODE[2:0]	2 (010)	R/W	Combined s	sync-word qualifier mode.		
					0 (000) and 4 (100) disables preamble and sync word n in TX and preamble and sync word detection in RX.		
				transmissio bits need to 3 (011) and	1 (001), 2 (010), 5 (101) and 6 (110) enables 16-bit sync word n in TX and 16-bits sync word detection in RX. Only 15 of 16 match in RX when using setting 1 (001) or 5 (101). The values 7 (111) enables repeated sync word transmission in TX and word detection in RX (only 30 of 32 bits need to match).		
				Setting	Sync-word qualifier mode		
				0 (000)	No preamble/sync		
				1 (001)	15/16 sync word bits detected		
				2 (010)	16/16 sync word bits detected		
				3 (011)	30/32 sync word bits detected		
				4 (100)	No preamble/sync, carrier-sense above threshold		
				5 (101)	15/16 + carrier-sense above threshold		
				6 (110)	16/16 + carrier-sense above threshold		
				7 (111)	30/32 + carrier-sense above threshold		





# 0x13: MDMCFG1- Modem Configuration

Bit	Field Name	Reset	R/W	Description	
7	FEC_EN	0	R/W	Enable Forward E packet payload	rror Correction (FEC) with interleaving for
				0 = Disable	
				1 = Enable (Only s	supported for fixed packet length mode, i.e. rH_CONFIG=0)
6:4	NUM_PREAMBLE[2:0]	2 (010)	R/W	Sets the minimum	number of preamble bytes to be transmitted
				Setting	Number of preamble bytes
				0 (000)	2
				1 (001)	3
				2 (010)	4
				3 (011)	6
				4 (100)	8
				5 (101)	12
				6 (110)	16
				7 (111)	24
3:2	Reserved		R0		
1:0	CHANSPC_E[1:0]	2 (10)	R/W	2 bit exponent of c	channel spacing

# 0x14: MDMCFG0- Modem Configuration

Bit	Field Name	Reset	R/W	Description
7:0	CHANSPC_M[7:0]	248 (0xF8)	R/W	8-bit mantissa of channel spacing. The channel spacing is multiplied by the channel number CHAN and added to the base frequency. It is unsigned and has the format: $\Delta f_{CHANNEL} = \frac{f_{XOSC}}{2^{18}} \cdot \left(256 + CHANSPC\_M\right) \cdot 2^{CHANSPC\_E}$ The default values give 199.951 kHz channel spacing (the closest setting to 200 kHz), assuming 26.0 MHz crystal frequency.





# 0x15: DEVIATN - Modem Deviation Setting

Bit	Field Name	Reset	R/W	Description
7	Reserved		R0	
6:4	DEVIATION_E[2:0]	4 (0x04)	R/W	Deviation exponent
3	Reserved		R0	
2:0	DEVIATION_M[2:0]	7 (111)	R/W	When MSK modulation is enabled:
				Sets fraction of symbol period used for phase change. Refer to the SmartRF® Studio software [7] for correct deviation setting when using MSK.
				When 2-FSK/GFSK modulation is enabled:
				Deviation mantissa, interpreted as a 4-bit value with MSB implicit 1. The resulting frequency deviation is given by:
				$f_{dev} = \frac{f_{xosc}}{2^{17}} \cdot (8 + DEVIATION \_M) \cdot 2^{DEVIATION\_E}$
				The default values give ±47.607 kHz deviation, assuming 26.0 MHz crystal frequency.





#### 0x16: MCSM2 - Main Radio Control State Machine Configuration

Bit	Field Name	Reset	R/W	Description
7:5	Reserved		R0	Reserved
4	RX_TIME_RSSI	0	R/W	Direct RX termination based on RSSI measurement (carrier sense). For ASK/OOK modulation, RX times out if there is no carrier sense in the first 8 symbol periods.
3	RX_TIME_QUAL	0	R/W	When the RX_TIME timer expires, the chip checks if sync word is found when RX_TIME_QUAL=0, or either sync word is found or PQI is set when RX_TIME_QUAL=1.
2:0	RX_TIME[2:0]	7 (111)	R/W	Timeout for sync word search in RX for both WOR mode and normal RX operation. The timeout is relative to the programmed EVENTO timeout.

The RX timeout in  $\mu$ s is given by EVENTO·C(RX\_TIME, WOR\_RES)·26/X, where C is given by the table below and X is the crystal oscillator frequency in MHz:

Setting	WOR_RES = 0	WOR_RES = 1	WOR_RES = 2	WOR_RES = 3			
0 (000)	3.6058	18.0288	32.4519	46.8750			
1 (001)	1.8029	9.0144	16.2260	23.4375			
2 (010)	0.9014	4.5072	8.1130	11.7188			
3 (011)	0.4507	2.2536	4.0565	5.8594			
4 (100)	0.2254	1.1268	2.0282	2.9297			
5 (101)	0.1127	0.5634	1.0141	1.4648			
6 (110)	0.0563	0.2817	0.5071	0.7324			
7 (111)	Until end of packet						

As an example, EVENT0=34666, WOR\_RES=0 and RX\_TIME=6 corresponds to 1.96 ms RX timeout, 1 s polling interval and 0.195% duty cycle. Note that WOR\_RES should be 0 or 1 when using WOR because using WOR\_RES > 1 will give a very low duty cycle. In applications where WOR is not used all settings of WOR\_RES can be used.

The duty cycle using WOR is approximated by:

Setting	WOR_RES=0	WOR_RES=1
0 (000)	12.50%	1.95%
1 (001)	6.250%	9765ppm
2 (010)	3.125%	4883ppm
3 (011)	1.563%	2441ppm
4 (100)	0.781%	NA
5 (101)	0.391%	NA
6 (110)	0.195%	NA
7 (111)	NA	

Note that the RC oscillator must be enabled in order to use setting 0-6, because the timeout counts RC oscillator periods. WOR mode does not need to be enabled.

The timeout counter resolution is limited: With RX\_TIME=0, the timeout count is given by the 13 MSBs of EVENTO, decreasing to the 7MSBs of EVENTO with RX\_TIME=6.



SWRS038D Page 73 of 92



# 0x17: MCSM1- Main Radio Control State Machine Configuration

Bit	Field Name	Reset	R/W	Description				
7:6	Reserved		R0					
5:4	CCA_MODE[1:0]	3 (11)	R/W	Selects CCA_MODE; Reflected in CCA signal				
				Setting	Clear channel indication			
				0 (00)	Always			
				1 (01)	If RSSI below threshold			
				2 (10)	Unless currently receiving a packet			
				3 (11)	If RSSI below threshold unless currently receiving a packet			
3:2	RXOFF_MODE[1:0]	0 (00)	R/W	Select what should happen when a packet has been received				
				Setting	Next state after finishing packet reception			
				0 (00)	IDLE			
				1 (01)	FSTXON			
				2 (10)	TX			
				3 (11)	Stay in RX			
				It is not pos time use C	ssible to set RXOFF_MODE to be TX or FSTXON and at the same CA.			
1:0	TXOFF_MODE[1:0]	0 (00)	R/W	Select wha	at should happen when a packet has been sent (TX)			
				Setting	Next state after finishing packet transmission			
				0 (00)	IDLE			
				1 (01)	FSTXON			
				2 (10)	Stay in TX (start sending preamble)			
				3 (11)	RX			





# 0x18: MCSM0- Main Radio Control State Machine Configuration

Bit	Field Name	Reset	R/W	Description	Description				
7:6	Reserved		R0						
5:4	FS_AUTOCAL[1:0]	0 (00)	R/W	Automatically calibrate when going to RX or TX, or back to IDLE					
				Setting	When to perfor	rm automatic calibration			
				0 (00)	Never (manual	lly calibrate using SCAL strobe)			
				1 (01)	When going from	om IDLE to RX or TX (or FSTX	ON)		
				2 (10)	When going from automatically	om RX or TX back to IDLE			
				3 (11)	Every 4 <sup>th</sup> time vautomatically	when going from RX or TX to II	DLE		
						n-radio (WOR) applications, us rrent consumption.	ing setting 3 (11)		
3:2	PO_TIMEOUT	1 (01)	R/W	Programs the number of times the six-bit ripple counter must expire after XOSC has stabilized before CHP_RDYn goes low.  If XOSC is on (stable) during power-down, PO_TIMEOUT should be set so that the regulated digital supply voltage has time to stabilize before CHP_RDYn goes low (PO_TIMEOUT=2 recommended). Typical start-up time for the voltage regulator is 50 us.					
				If XOSC is off during power-down and the regulated digital supply voltage has sufficient time to stabilize while waiting for the crystal to be stable, PO_TIMEOUT can be set to 0. For robust operation it is recommended to use PO_TIMEOUT=2.					
				Setting	Expire count	Timeout after XOSC start			
				0 (00)	1	Approx. 2.3 – 2.4 μs			
				1 (01)	16	Approx. 37 – 39 μs			
				2 (10)	64	Approx. 149 – 155 μs			
				3 (11)	256	Approx. 597 – 620 μs			
				Exact time	out depends on	crystal frequency.			
1	PIN_CTRL_EN	0	R/W	Enables the pin radio control option					
0	XOSC_FORCE_ON	0	R/W	Force the	XOSC to stay on	in the SLEEP state.			





# 0x19: FOCCFG – Frequency Offset Compensation Configuration

Bit	Field Name	Reset	R/W	Descriptio	n	
7:6	Reserved		R0			
5	FOC_BS_CS_GATE	1	R/W	If set, the demodulator freezes the frequency offset compensation and clock recovery feedback loops until the CS signal goes high.		
4:3	FOC_PRE_K[1:0]	2 (10)	R/W	The frequency compensation loop gain to be used before a sync word is detected.		
				Setting	Freq. compensation loop gain before sync word	
				0 (00)	К	
				1 (01)	2K	
				2 (10)	3 <i>K</i>	
				3 (11)	4K	
2	FOC_POST_K	1	R/W	The frequency compensation loop gain to be used after a sync word is detected.		
				Setting	Freq. compensation loop gain after sync word	
				0	Same as FOC_PRE_K	
				1	K/2	
1:0	FOC_LIMIT[1:0]	2 (10)	R/W	The satura	tion point for the frequency offset compensation algorithm:	
				Setting	Saturation point (max compensated offset)	
				0 (00)	±0 (no frequency offset compensation)	
				1 (01)	±BW <sub>CHAN</sub> /8	
				2 (10)	±BW <sub>CHAN</sub> /4	
				3 (11)	±BW <sub>CHAN</sub> /2	
					offset compensation is not supported for ASK/OOK; Always use T=0 with these modulation formats.	





# 0x1A: BSCFG – Bit Synchronization Configuration

Bit	Field Name	Reset	R/W	Description			
7:6	BS_PRE_KI[1:0]	1 (01)	R/W		The clock recovery feedback loop integral gain to be used before a sync work is detected (used to correct offsets in data rate):		
				Setting	Clock recovery loop integral gain before sync word		
				0 (00)	K,		
				1 (01)	2K,		
				2 (10)	3 <i>K</i> <sub>1</sub>		
				3 (11)	4 <i>K</i> <sub>1</sub>		
5:4	BS_PRE_KP[1:0]	2 (10)	R/W	The clock recovery feedback loop proportional gain to be used before a sync word is detected.			
				Setting	Clock recovery loop proportional gain before sync word		
				0 (00)	$K_{P}$		
				1 (01)	$2K_P$		
				2 (10)	$3K_P$		
				3 (11)	4 <i>K</i> <sub>P</sub>		
3	BS_POST_KI	1	R/W	The clock recovery feedback loop integral gain to be used after a sync word is detected.			
				Setting	Clock recovery loop integral gain after sync word		
				0	Same as BS_PRE_KI		
				1	K <sub>1</sub> /2		
2	BS_POST_KP	1	R/W	The clock i	recovery feedback loop proportional gain to be used after a sylected.	ync	
				Setting	Clock recovery loop proportional gain after sync word		
				0	Same as BS_PRE_KP		
				1	$K_{P}$		
1:0	BS_LIMIT[1:0]	0 (00)	R/W	The satura	tion point for the data rate offset compensation algorithm:		
				Setting	Data rate offset saturation (max data rate difference)		
				0 (00)	±0 (No data rate offset compensation performed)		
				1 (01)	±3.125% data rate offset		
				2 (10)	±6.25% data rate offset		
				3 (11)	±12.5% data rate offset		






# 0x1B: AGCCTRL2 - AGC Control

Bit	Field Name	Reset	R/W	Description	1
7:6	MAX_DVGA_GAIN[1:0]	0 (00)	R/W	Reduces the	e maximum allowable DVGA gain.
				Setting	Allowable DVGA settings
				0 (00)	All gain settings can be used
				1 (01)	The highest gain setting can not be used
				2 (10)	The 2 highest gain settings can not be used
				3 (11)	The 3 highest gain settings can not be used
5:3	MAX_LNA_GAIN[2:0]	0 (000)	R/W	Sets the maximum allowable LNA + LNA 2 gain relative to the maximum possible gain.	
				Setting	Maximum allowable LNA + LNA 2 gain
				0 (000)	Maximum possible LNA + LNA 2 gain
				1 (001)	Approx. 2.6 dB below maximum possible gain
				2 (010)	Approx. 6.1 dB below maximum possible gain
				3 (011)	Approx. 7.4 dB below maximum possible gain
				4 (100)	Approx. 9.2 dB below maximum possible gain
				5 (101)	Approx. 11.5 dB below maximum possible gain
				6 (110)	Approx. 14.6 dB below maximum possible gain
				7 (111)	Approx. 17.1 dB below maximum possible gain
2:0	MAGN_TARGET[2:0]	3 (011)	R/W		set the target value for the averaged amplitude from the nel filter (1 LSB = 0 dB).
				Setting	Target amplitude from channel filter
				0 (000)	24 dB
				1 (001)	27 dB
				2 (010)	30 dB
				3 (011)	33 dB
				4 (100)	36 dB
				5 (101)	38 dB
				6 (110)	40 dB
				7 (111)	42 dB






# 0x1C: AGCCTRL1 - AGC Control

Bit	Field Name	Reset	R/W	Description	
7	Reserved		R0		
6	AGC_LNA_PRIORITY	1	R/W	gain adjustm	een two different strategies for LNA and LNA 2 ent. When 1, the LNA gain is decreased first. LNA 2 gain is decreased to minimum before NA gain.
5:4	CARRIER_SENSE_REL_THR[1:0]	0 (00)	R/W	Sets the relat	tive change threshold for asserting carrier sense
				Setting	Carrier sense relative threshold
				0 (00)	Relative carrier sense threshold disabled
				1 (01)	6 dB increase in RSSI value
				2 (10)	10 dB increase in RSSI value
				3 (11)	14 dB increase in RSSI value
3:0	CARRIER_SENSE_ABS_THR[3:0]	0 (0000)	R/W	/ Sets the absolute RSSI threshold for asserting carrier sense. The 2-complement signed threshold is programmed in steps of 1 dB and is relative to the MAGN_TARGET setting.	
				Setting	Carrier sense absolute threshold
					(Equal to channel filter amplitude when AGC has not decreased gain)
				-8 (1000)	Absolute carrier sense threshold disabled
				-7 (1001)	7 dB below MAGN_TARGET setting
				-1 (1111)	1 dB below MAGN_TARGET setting
				0 (0000)	At MAGN_TARGET setting
				1 (0001)	1 dB above MAGN_TARGET setting
				7 (0111)	7 dB above MAGN_TARGET setting





# 0x1D: AGCCTRL0 - AGC Control

Bit	Field Name	Reset	R/W	Description	on		
7:6	HYST_LEVEL[1:0]	2 (10)	R/W		vel of hysteresis on the magnitude deviation (internal AGC determine gain changes).		
				Setting	Description		
				0 (00)	No hysteresis, small symmetric dead zone, high gain		
				1 (01)	Low hysteresis, small asymmetric dead zone, medium gain		
				2 (10)	Medium hysteresis, medium asymmetric dead zone, medium gain		
				3 (11)	Large hysteresis, large asymmetric dead zone, low gain		
5:4	WAIT_TIME[1:0]	1 (01)	R/W		umber of channel filter samples from a gain adjustment made until the AGC algorithm starts accumulating new		
				Setting	Channel filter samples		
				0 (00)	8		
				1 (01)	16		
				2 (10)	24		
				3 (11)	32		
3:2	AGC_FREEZE[1:0]	0 (00)	R/W	Control wh	hen the AGC gain should be frozen.		
				Setting	Function		
				0 (00)	Normal operation. Always adjust gain when required.		
				1 (01)	The gain setting is frozen when a sync word has been found.		
				2 (10)	Manually freeze the analogue gain setting and continue to adjust the digital gain.		
				3 (11)	Manually freezes both the analogue and the digital gain setting. Used for manually overriding the gain.		
1:0	FILTER_LENGTH[1:0]	1 (01)	R/W		veraging length for the amplitude from the channel filter. OK/ASK decision boundary for OOK/ASK reception.		
				Setting	Channel filter OOK decision samples		
				0 (00)	8 4 dB		
				1 (01)	16 8 dB		
				2 (10)	32 12 dB		
				3 (11)	64 16 dB		

# 0x1E: WOREVT1 – High Byte Event0 Timeout

Bit	Field Name	Reset	R/W	Description
7:0	EVENT0[15:8]	135 (0x87)	R/W	High byte of EVENTO timeout register
				$t_{Event0} = \frac{750}{f_{XOSC}} \cdot EVENT0 \cdot 2^{5 \cdot WOR\_RES}$





# 0x1F: WOREVT0 -Low Byte Event0 Timeout

Bit	Field Name	Reset	R/W	Description
7:0	EVENT0[7:0]	107 (0x6B)	R/W	Low byte of EVENTO timeout register.
				The default EVENTO value gives 1.0s timeout, assuming a 26.0 MHz crystal.

### 0x20: WORCTRL - Wake On Radio Control

Bit	Field Name	Reset	R/W	Description	n		
7	RC_PD	1	R/W	Power down signal to RC oscillator. When written to 0, automatic initial calibration will be performed			initial
6:4	EVENT1[2:0]	7 (111)	R/W	V Timeout setting from register block. Decoded to Event oscillator clock frequency equals F <sub>xosc</sub> /750, which is 34 depending on crystal frequency. The table below lists the periods after Event 0 before Event 1 times out.			Ηz,
				Setting	t <sub>Event1</sub>		
				0 (000)	4 (0.111 – 0.115 ms)		
				1 (001)	6 (0.167 – 0.173 ms)		
				2 (010)	8 (0.222 – 0.230 ms)		
				3 (011)	12 (0.333 – 0.346 ms)		
				4 (100)	16 (0.444 – 0.462 ms)		
				5 (101)	24 (0.667 – 0.692 ms)		
				6 (110)	32 (0.889 – 0.923 ms)		
				7 (111)	48 (1.333 – 1.385 ms)		
3	RC_CAL	1	R/W	Enables (1	) or disables (0) the RC oscillato	r calibration.	
2	Reserved		R0				
1:0	WOR_RES	0 (00)	R/W	Controls the Event 0 resolution as well as maximum timeout of the WOR module and maximum timeout under normal RX operation::			
				Setting	Resolution (1 LSB)	Max timeout	
				0 (00)	1 period (28µs – 29µs)	1.8 – 1.9 seconds	
				1 (01)	2 <sup>5</sup> periods (0.89ms –0.92 ms)	58 – 61 seconds	
				2 (10)	2 <sup>10</sup> periods (28 – 30 ms)	31 – 32 minutes	
				3 (11)	$2^{15}$ periods (0.91 – 0.94 s)	16.5 – 17.2 hours	
					OR_RES should be 0 or 1 when to 1 will give a very low duty cycle		
				In normal F	RX operation all settings of WOR_	RES can be used.	





# 0x21: FREND1 – Front End RX Configuration

Bit	Field Name	Reset	R/W	Description
7:6	LNA_CURRENT[1:0]	1 (01)	R/W	Adjusts front-end LNA PTAT current output
5:4	LNA2MIX_CURRENT[1:0]	1 (01)	R/W	Adjusts front-end PTAT outputs
3:2	LODIV_BUF_CURRENT_RX[1:0]	1 (01)	R/W	Adjusts current in RX LO buffer (LO input to mixer)
1:0	MIX_CURRENT[1:0]	2 (10)	R/W	Adjusts current in mixer


# 0x22: FREND0 – Front End TX Configuration

Bit	Field Name	Reset	R/W	Description
7:6	Reserved		R0	
5:4	LODIV_BUF_CURRENT_TX[1:0]	1 (0x01)	R/W	Adjusts current TX LO buffer (input to PA). The value to use in this field is given by the SmartRF® Studio software [7].
3	Reserved		R0	
2:0	PA_POWER[2:0]	0 (0x00)	R/W	Selects PA power setting. This value is an index to the PATABLE, which can be programmed with up to 8 different PA settings. In OOK/ASK mode, this selects the PATABLE index to use when transmitting a '1'. PATABLE index zero is used in OOK/ASK when transmitting a '0'. The PATABLE settings from index '0' to the PA_POWER value are used for ASK TX shaping, and for power ramp-up/ramp-down at the start/end of transmission in all TX modulation formats.

# 0x23: FSCAL3 – Frequency Synthesizer Calibration

Bit	Field Name	Reset	R/W	Description
7:6	FSCAL3[7:6]	2 (0x02)	R/W	Frequency synthesizer calibration configuration. The value to write in this field before calibration is given by the SmartRF® Studio software.
5:4	CHP_CURR_CAL_EN[1:0]	2 (0x02)	R/W	Enable charge pump calibration stage when 1
3:0	FSCAL3[3:0]	9 (1001)	R/W	Frequency synthesizer calibration result register. Digital bit vector defining the charge pump output current, on an exponential scale: IOUT = $l_0 \cdot 2^{\text{FSCAL3}[3:0]/4}$ Fast frequency hopping without calibration for each hop can be done by calibrating upfront for each frequency and saving the resulting FSCAL3, FSCAL2 and FSCAL1 register values. Between each frequency hop, calibration can be replaced by writing the FSCAL3, FSCAL2 and FSCAL1 register values corresponding to the next RF frequency.





# 0x24: FSCAL2 - Frequency Synthesizer Calibration

Bit	Field Name	Reset	R/W	Description
7:6	Reserved		R0	
5	VCO_CORE_H_EN	0	R/W	Choose high (1) / low (0) VCO
4:0	FSCAL2[4:0]	10 (0x0A)	R/W	Frequency synthesizer calibration result register. VCO current calibration result and override value Fast frequency hopping without calibration for each hop can be done by calibrating upfront for each frequency and saving the resulting FSCAL3, FSCAL2 and FSCAL1 register values. Between each frequency hop, calibration can be replaced by writing the FSCAL3, FSCAL2 and FSCAL1 register values corresponding to the next RF frequency.

# 0x25: FSCAL1 - Frequency Synthesizer Calibration

Bit	Field Name	Reset	R/W	Description
7:6	Reserved		R0	
5:0	FSCAL1[5:0]	32 (0x20)	R/W	Frequency synthesizer calibration result register. Capacitor array setting for VCO coarse tuning.  Fast frequency hopping without calibration for each hop can be done by calibrating upfront for each frequency and saving the resulting FSCAL3, FSCAL2 and FSCAL1 register values. Between each frequency hop, calibration can be replaced by writing the FSCAL3, FSCAL2 and FSCAL1 register values corresponding to the next RF frequency.

# 0x26: FSCAL0 – Frequency Synthesizer Calibration

	Bit	Field Name	Reset	R/W	Description
Ī	7	Reserved		R0	
	6:0	FSCAL0[6:0]	13 (0x0D)	R/W	Frequency synthesizer calibration control. The value to use in this register is given by the SmartRF® Studio software [7].

# 0x27: RCCTRL1 - RC Oscillator Configuration

Bit	Field Name	Reset	R/W	Description
7	Reserved	0	R0	
6:0	RCCTRL1[6:0]	65 (0x41)	R/W	RC oscillator configuration.

# 0x28: RCCTRL0 - RC Oscillator Configuration

Bit	Field Name	Reset	R/W	Description
7	Reserved	0	R0	
6:0	RCCTRL0[6:0]	0 (0x00)	R/W	RC oscillator configuration.





# 33.2 Configuration Register Details – Registers that Lose Programming in SLEEP State

# 0x29: FSTEST – Frequency Synthesizer Calibration Control

Bit	Field Name	Reset	R/W	Description
7:0	FSTEST[7:0]	89 (0x59)	R/W	For test only. Do not write to this register.

#### 0x2A: PTEST - Production Test

Bit	Field Name	Reset	R/W	Description
7:0	PTEST[7:0]	127 (0x7F)	R/W	Writing 0xBF to this register makes the on-chip temperature sensor available in the IDLE state. The default 0x7F value should then be written back before leaving the IDLE state. Other use of this register is for test only.

#### 0x2B: AGCTEST - AGC Test

Bit	Field Name	Reset	R/W	Description
7:0	AGCTEST[7:0]	63 (0x3F)	R/W	For test only. Do not write to this register.

### 0x2C: TEST2 – Various Test Settings

I	Bit	Field Name	Reset	R/W	Description
•	7:0	TEST2[7:0]	136 (0x88)	R/W	The value to use in this register is given by the SmartRF® Studio software [7].

### 0x2D: TEST1 - Various Test Settings

Bit	Field Name	Reset	R/W	Description
7:0	TEST1[7:0]	49 (0x31)	R/W	The value to use in this register is given by the SmartRF® Studio software [7].

# 0x2E: TEST0 – Various Test Settings

Bit	Field Name	Reset	R/W	Description
7:2	TEST0[7:2]	2 (0x02)	R/W	The value to use in this register is given by the SmartRF® Studio software [7].
1	VCO_SEL_CAL_EN	1	R/W	Enable VCO selection calibration stage when 1
0	TEST0[0]	1	R/W	The value to use in this register is given by the SmartRF® Studio software [7].



Page 84 of 92



# 33.3 Status Register Details

# 0x30 (0xF0): PARTNUM - Chip ID

Bit	Field Name	Reset	R/W	Description
7:0	PARTNUM[7:0]	0 (0x00)	R	Chip part number

# 0x31 (0xF1): VERSION - Chip ID

Bit	Field Name	Reset	R/W	Description
7:0	VERSION[7:0]	3 (0x03)	R	Chip version number.

# 0x32 (0xF2): FREQEST – Frequency Offset Estimate from Demodulator

Bit	Field Name	Reset	R/W	Description
7:0	FREQOFF_EST		R	The estimated frequency offset (2's complement) of the carrier. Resolution is $F_{XTAL}/2^{14}$ (1.59 - 1.65 kHz); range is $\pm 202$ kHz to $\pm 210$ kHz, dependent of XTAL frequency.
				Frequency offset compensation is only supported for 2-FSK, GFSK, and MSK modulation. This register will read 0 when using ASK or OOK modulation.


# 0x33 (0xF3): LQI - Demodulator Estimate for Link Quality

Bit	Field Name	Reset	R/W	Description
7	CRC OK		R	The last CRC comparison matched. Cleared when entering/restarting RX mode.
6:0	LQI_EST[6:0]		R	The Link Quality Indicator estimates how easily a received signal can be demodulated. Calculated over the 64 symbols following the sync word

# 0x34 (0xF4): RSSI - Received Signal Strength Indication

Bit	Field Name	Reset	R/W	Description
7:0	RSSI		R	Received signal strength indicator





# 0x35 (0xF5): MARCSTATE - Main Radio Control State Machine State

Bit	Field Name	Reset	R/W	Description		
7:5	Reserved		R0			
4:0	MARC_STATE[4:0]		R	Main Radio C	Control FSM State	
				Value	State name	State (Figure 16, page 42)
				0 (0x00)	SLEEP	SLEEP
				1 (0x01)	IDLE	IDLE
				2 (0x02)	XOFF	XOFF
				3 (0x03)	VCOON_MC	MANCAL
				4 (0x04)	REGON_MC	MANCAL
				5 (0x05)	MANCAL	MANCAL
				6 (0x06)	VCOON	FS_WAKEUP
				7 (0x07)	REGON	FS_WAKEUP
				8 (0x08)	STARTCAL	CALIBRATE
				9 (0x09)	BWBOOST	SETTLING
				10 (0x0A)	FS_LOCK	SETTLING
				11 (0x0B)	IFADCON	SETTLING
				12 (0x0C)	ENDCAL	CALIBRATE
				13 (0x0D)	RX	RX
				14 (0x0E)	RX_END	RX
				15 (0x0F)	RX_RST	RX
				16 (0x10)	TXRX_SWITCH	TXRX_SETTLING
				17 (0x11)	RXFIFO_OVERFLOW	RXFIFO_OVERFLOW
				18 (0x12)	FSTXON	FSTXON
				19 (0x13)	TX	TX
				20 (0x14)	TX_END	TX
				21 (0x15)	RXTX_SWITCH	RXTX_SETTLING
				22 (0x16)	TXFIFO_UNDERFLOW	TXFIFO_UNDERFLOW
					ng CSn low will make the c	SLEEP or XOFF state numbers hip enter the IDLE mode from the

# 0x36 (0xF6): WORTIME1 - High Byte of WOR Time

Bit	Field Name	Reset	R/W	Description
7:0	TIME[15:8]		R	High byte of timer value in WOR module

# 0x37 (0xF7): WORTIME0 - Low Byte of WOR Time

Bit	Field Name	Reset	R/W	Description
7:0	TIME[7:0]		R	Low byte of timer value in WOR module





# 0x38 (0xF8): PKTSTATUS - Current GDOx Status and Packet Status

Bit	Field Name	Reset	R/W	Description	
7	CRC_OK		R	R The last CRC comparison matched. Cleared when entering/restarting RX mode.	
6	CS		R	Carrier sense	
5	PQT_REACHED		R	Preamble Quality reached	
4	CCA		R	Channel is clear	
3	SFD		R	R Sync word found	
2	GDO2		R Current GDO2 value. Note: the reading gives the non-inverted value irrespective of what IOCFG2.GDO2_INV is programmed to.		
				It is not recommended to check for PLL lock by reading PKTSTATUS [2] with GD02_CFG=0x0A.	
1	Reserved		R0		
0	GD00		R Current GDO0 value. Note: the reading gives the non-inverted value irrespective of what IOCFG0.GDO0_INV is programmed to.		
				It is not recommended to check for PLL lock by reading PKTSTATUS [0] with GD00_CFG=0x0A.	

# 0x39 (0xF9): VCO\_VC\_DAC - Current Setting from PLL Calibration Module

Bit	Field Name	Reset	R/W	Description
7:0	VCO_VC_DAC[7:0]		R	Status register for test only.

# 0x3A (0xFA): TXBYTES - Underflow and Number of Bytes

Bi	Field Name	Reset	R/W	Description
7	TXFIFO_UNDERFLOW		R	
6:0	NUM_TXBYTES		R	Number of bytes in TX FIFO

# 0x3B (0xFB): RXBYTES – Overflow and Number of Bytes

E	Bit	Field Name	Reset	R/W	Description
7	7	RXFIFO_OVERFLOW		R	
6	6:0	NUM_RXBYTES		R	Number of bytes in RX FIFO

# 0x3C (0xFC): RCCTRL1\_STATUS - Last RC Oscillator Calibration Result

Bit	Field Name	Reset	R/W	Description
7	Reserved		R0	
6:0	RCCTRL1_STATUS[6:0]		R	Contains the value from the last run of the RC oscillator calibration routine.
				For usage description refer to AN047 [4]





# 0x3D (0xFC): RCCTRL0\_STATUS - Last RC Oscillator Calibration Result

Bit	Field Name	Reset	R/W	Description
7	Reserved		R0	
6:0	RCCTRL0_STATUS[6:0]		R	Contains the value from the last run of the RC oscillator calibration routine.
				For usage description refer to Aplication Note AN047 [4].

# 34 Package Description (QLP 20)

### 34.1 Recommended PCB Layout for Package (QLP 20)




Figure 31: Recommended PCB Layout for QLP 20 Package

Note: Figure 31 is an illustration only and not to scale. There are five 10 mil via holes distributed symmetrically in the ground pad under the package. See also the CC1100EM reference designs ([5] and [6]).

### 34.2 Soldering Information

The recommendations for lead-free reflow in IPC/JEDEC J-STD-020 should be followed.





# 35 Ordering Information

Orderable Device	Status (1)	Package Type	O I Dine I		Package Qty	Eco Plan (2)	Lead Finish	MSL Peak Temp (3)
CC1100RTKR	NRND	QLP	RTK	20	3000	Green (RoHS & no Sb/Br)	Cu NiPdAu	LEVEL3-260C 1 YEAR
CC1100RTK	NRND	QLP	RTK	20	92	Green (RoHS & no Sb/Br)	Cu NiPdAu	LEVEL3-260C 1 YEAR

#### **Table 39: Ordering Information**

(1) The marketing status values are defined as follows:

ACTIVE: Product device recommended for new designs.

LIFEBUY: TI has announced that the device will be discontinued, and a lifetime-buy period is in effect.

**NRND:** Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

PREVIEW: Device has been announced but is not in production. Samples may or may not be available.

OBSOLETE: TI has discontinued the production of the device.

(2) Eco Plan - The planned eco-friendly classification: Pb-Free (RoHS), Pb-Free (RoHS Exempt), or Green (RoHS & no Sb/Br) - please check http://www.ti.com/productcontent for the latest availability information and additional product content details.

TBD: The Pb-Free/Green conversion plan has not been defined.

**Pb-Free** (RoHS): TI's terms "Lead-Free" or "Pb-Free" mean semiconductor products that are compatible with the current RoHS requirements for all 6 substances, including the requirement that lead not exceed 0.1% by weight in homogeneous materials. Where designed to be soldered at high temperatures, TI Pb-Free products are suitable for use in specified lead-free processes.

**Pb-Free (RoHS Exempt):** This component has a RoHS exemption for either 1) lead-based flip-chip solder bumps used between the die and package, or 2) lead-based die adhesive used between the die and leadframe. The component is otherwise considered Pb-Free (RoHS compatible) as defined above.

Green (RoHS & no Sb/Br): TI defines "Green" to mean Pb-Free (RoHS compatible), and free of Bromine (Br) and Antimony (Sb) based flame retardants (Br or Sb do not exceed 0.1% by weight in homogeneous material)

(3) MSL, Peak Temp. -- The Moisture Sensitivity Level rating according to the JEDEC industry standard classifications, and peak solder temperature.

Important Information and Disclaimer: The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.

In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.





### 36 References

- [1] CC1100 Errata Notes (swrz012.pdf)
- [2] AN001 SRD Regulations for Licence Free Transceiver Operation (swra090.pdf)
- [3] AN039 Using the CC1100 in the European 433 and 868 MHz ISM Bands (swra054.pdf)
- [4] AN047 CC1100/CC2500 Wake-On-Radio (swra126.pdf)
- [5] CC1100EM 315 433 MHz Reference Design 1.0 (swrr037.zip)
- [6] CC1100EM 868 915 MHz Reference Design 2.0 (swrr038.zip)
- [7] SmartRF<sup>®</sup> Studio (swrc046.zip)
- [8] CC1100 CC2500 Examples Libraries (swrc021.zip)
- [9] CC1100/CC1150DK, CC1101DK, and CC2500/CC2550DK Examples and Libraries User Manual (swru109.pdf)






# 37 General Information

# 37.1 Document History

Revision	Date	Description/Changes
SWRS038D	2009-05-26	Updated packet and ordering information.
		Removed Product Status Definition, Address Information and TI World Wide Support section.
		Removed Low-Cost from datasheet title.
SWRS038C	2008-05-22	Added product information on front page
SWRS038B	2007-07-09	Added info to ordering information
		Changes in the <i>General Principle of Matrix Interleaving</i> figure.  Changes in Table: <i>Bill Of Materials for the Application Circuit</i>
		Changes in Figure: Typical Application and Evaluation Circuit 868/915 MHz
		Changed the equation for channel spacing in the MDMCFG0 register.
		kbps replaced by kBaud throughout the document.
		Some of the sections have been re-written to be easier to read without having any new info
		added.
		Absolute maximum supply voltage rating increased from 3.6 V to 3.9 V.  Changed the frequency accuracy after calibration for the low power RC oscillator from ±0.3 to
		±1%.
		Updates to sensitivity and current consumption numbers listed under <i>Key Features</i> .
		FSK changed to 2-FSK throughout the document.
		Updates to the Abbreviation table.
		Updates to the <i>Electrical Specifications</i> section.
		Added info about RX and TX latency.  Added info in the <i>Pinout Overview</i> table regarding GDO0 and GDO2.
		Changed current consumption in RX and TX in the simplified state diagram.
		Added info about default values after reset vs. optimum register settings in the <i>Configuration</i>
		Software section
		Changes to the SPI Interface Timing Requirements.
		Info added about t <sub>sp,pd</sub>
		The following figures have been changed: Configuration Registers Write and Read Operations,
		SRES Command Strobe, and Register Access Types.  In the Register Access section, the address range is changed.
		In the PATABLE Access section, info is added regarding limitations on output power
		programming when using PA ramping.
		In the Packet Format section, preamble pattern is changed to 10101010 and info about bug
		related to turning off the transmitter in infinite packet length mode is added.
		Added info to the Frequency Offset Compensation section.
		Added info about the initial value of the PN9 sequence in the <i>Data Whitening</i> section.  In the <i>Packet Handling in Transmit Mode</i> section, info about TX FIFO underflow state is added.
		Added section <i>Packet Handling in Firmware</i> .
		0x00 is added as a valid PATABLE setting in addition to 0x30-0x3F when using ASK.
		In the PQT section a change is made as to how much the counter decreases.
		The RSSI value is in dBm and not dB.
		The whole CS Absolute Threshold section has been re-written and the equation calculating the
		threshold has been removed.  Added info in the CCA section on what happens if the channel is not clear.
		Added info to the LQI section for better understanding.
		Removed all references to the voltage regulator in relation with the CHP RDYn signal, as this
		signal is only related to the crystal.
		Removed references to the voltage regulator in the figures: Power-On Reset and Power-On
		Reset with SRES. Changes to the SI line in the Power-On Reset with SRES figure
		Added info on the three automatic calibration options.  Removed the autosync feature from the WOR section and added info on how to exit WOR
		mode. Also added info about minimum sleep time and references to App. Note 047 together
		with info about calibration of the RC oscillator.
		The figure: Event 0 and Event 1 Relationship is changed for better readability.
		Info added to the <i>Timing</i> section related to reduced calibration time.
		The Output Power Programming section is divided into 2 new sections; Output Power
		Programming and Shaping and PA Ramping.  Added info on programming of PATABLE when using OOK, and about PATABLE when entering
		SLEEP mode.
		2 new figures added to the Shaping and PA Ramping section: Shaping of ASK Signal and PA
		Ramping, together with one new table: PATABLE Settings Used Together with ASK Shaping
		and PA Ramping.
		Changed made to current consumption in the Optimum PATABLE Settings for Various Output
		Power Levels and Frequency Bands table.
		Added section Layout Recommendations.
L	1	In section General Purpose / Test Output Control Pins: Added info on GDO pins in SLEEP



SWRS038D Page 91 of 92



Revision	Date	Description/Changes
		state.  Better explanation of some of the signals in the <i>GDOx Signal Selection</i> table. Also added some more signals.  Asynchronous transparent mode is called asynchronous serial mode throughout the document. Removed comments about having to use NRZ coding in synchronous serial mode. Added info that Manschester encoding cannot be used in this mode.  Added a third calibration method plus additional info about the 3 methods in the <i>Frequency Hopping and Multi-Channel Systems</i> section.  Added info about differential antenna in the <i>Low Cost Systems</i> section.  Changes number of commands strobes from 14 to 13.  Changed description of SFRX, SFTX, SWORRST, and SNOP in the <i>Command Strobes</i> table.  Added two new registers; RCCTRL1_STATUS and RCCTRL0_STATUS  Changed field name and/or description of the following registers:  PKTCTRL1, MCSM2, MCSM0, WORCTRL, FSCAL3, FSCAL2, FSCAL1, and TEST0.  Changed tray width in the <i>Tray Specification</i> table.  Added references.
SWRS038A	2006-06-20	Updates to Electrical Specifications due to increased amount of measurement data.  Updated application circuit for 868 MHz. Updated balun component values.  Updated current consumption figures in state diagrams.  Added figures to table on SPI interface timing requirements.  Added information about SPI read.  Added table for channel filter bandwidths.  Added figure showing data whitening.  Updates to text and included new figure in section on arbitrary length configuration.  References to SAFC strobe removed.  Added additional information about support of ASK modulation.  Added information about CRC filtering.  Added information about sync word qualifier.  Added information on RSSI offset, RSSI update rate, RSSI calculation and typical RSSI curves.  Added information on CS and tables with register settings versus CS threshold.  Updates to text and included new figures in section on power-on start-up sequence.  Changes to wake-on-radio current consumption figures under electrical specifications.  Updates to text in section on data FIFO.  Corrected formula for calculation of output frequency in Frequency Programming section.  Added information about how to check for PLL lock in section on VCO.  Corrected table with PATABLE setting versus output power.  Added typical selectivity curves for selected datarates.  Added information on how to interface external clock signal.  Added optimal match impedances in RF match section.  Better explanation of some of the signals in table of GDO signal selection. Also added some more signals.  Added information on timeout for sync word search in RX in register MCSM2.  Changes to wake-on-radio control register WORCTRL. WOR_RES[1:0] settings 10 b and 11b changed to NA.  Added description of programming bits in registers FOCCFG, BSCFG, AGCCTRL2, AGCCTRL1, AGCCTRL0, FREND1, FSCAL3.
1.0	2005-04-25	

**Table 40: Document History** 



SWRS038D Page 92 of 92

11-Nov-2025

www.ti.com

#### PACKAGING INFORMATION

Orderable part number	Status	Material type	Package   Pins	Package qty   Carrier	RoHS	Lead finish/	MSL rating/	Op temp (°C)	Part marking
	(1)	(2)			(3)	Ball material	Peak reflow		(6)
						(4)	(5)		
CC1100-RTR1	NRND	Production	VQFN (RTK)   20	3000   LARGE T&R	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100
CC1100-RTY1	NRND	Production	VQFN (RTK)   20	92   TUBE	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100
CC1100RTK	NRND	Production	VQFN (RTK)   20	92   TUBE	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100
CC1100RTK.B	NRND	Production	VQFN (RTK)   20	92   TUBE	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100
CC1100RTKR	NRND	Production	VQFN (RTK)   20	3000   LARGE T&R	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100
CC1100RTKR.B	NRND	Production	VQFN (RTK)   20	3000   LARGE T&R	Yes	SN	Level-3-260C-168 HR	-40 to 85	CC1100

<sup>(1)</sup> Status: For more details on status, see our product life cycle.

Multiple part markings will be inside parentheses. Only one part marking contained in parentheses and separated by a "~" will appear on a part. If a line is indented then it is a continuation of the previous line and the two combined represent the entire part marking for that device.

Important Information and Disclaimer: The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.

In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.

<sup>(2)</sup> Material type: When designated, preproduction parts are prototypes/experimental devices, and are not yet approved or released for full production. Testing and final process, including without limitation quality assurance, reliability performance testing, and/or process qualification, may not yet be complete, and this item is subject to further changes or possible discontinuation. If available for ordering, purchases will be subject to an additional waiver at checkout, and are intended for early internal evaluation purposes only. These items are sold without warranties of any kind.

<sup>(3)</sup> RoHS values: Yes, No, RoHS Exempt. See the TI RoHS Statement for additional information and value definition.

<sup>(4)</sup> Lead finish/Ball material: Parts may have multiple material finish options. Finish options are separated by a vertical ruled line. Lead finish/Ball material values may wrap to two lines if the finish value exceeds the maximum column width.

<sup>(5)</sup> MSL rating/Peak reflow: The moisture sensitivity level ratings and peak solder (reflow) temperatures. In the event that a part has multiple moisture sensitivity ratings, only the lowest level per JEDEC standards is shown. Refer to the shipping label for the actual reflow temperature that will be used to mount the part to the printed circuit board.

<sup>(6)</sup> Part marking: There may be an additional marking, which relates to the logo, the lot trace code information, or the environmental category of the part.



# **PACKAGE OPTION ADDENDUM**

www.ti.com 11-Nov-2025

# **PACKAGE MATERIALS INFORMATION**

www.ti.com 23-May-2025

### TAPE AND REEL INFORMATION





A0	Dimension designed to accommodate the component width
В0	Dimension designed to accommodate the component length
K0	Dimension designed to accommodate the component thickness
W	Overall width of the carrier tape
P1	Pitch between successive cavity centers

#### QUADRANT ASSIGNMENTS FOR PIN 1 ORIENTATION IN TAPE



#### \*All dimensions are nominal

Device		Package Drawing		SPQ	Reel Diameter (mm)	Reel Width W1 (mm)	A0 (mm)	B0 (mm)	K0 (mm)	P1 (mm)	W (mm)	Pin1 Quadrant
CC1100RTKR	VQFN	RTK	20	3000	330.0	12.4	4.3	4.3	1.5	8.0	12.0	Q2

# **PACKAGE MATERIALS INFORMATION**

www.ti.com 23-May-2025



### \*All dimensions are nominal

	Device	Package Type	Package Drawing	Pins	SPQ	Length (mm)	Width (mm)	Height (mm)
ı	CC1100RTKR	VQFN	RTK	20	3000	350.0	350.0	43.0

# **PACKAGE MATERIALS INFORMATION**

www.ti.com 23-May-2025

### **TUBE**




#### \*All dimensions are nominal

Device	Package Name	Package Type	Pins	SPQ	L (mm)	W (mm)	T (µm)	B (mm)
CC1100-RTY1	RTK	VQFNP	20	92	381	5.79	2286	0
CC1100RTK	RTK	VQFNP	20	92	381	5.79	2286	0
CC1100RTK.B	RTK	VQFNP	20	92	381	5.79	2286	0

# RTK (S-PVQFN-N20)

# PLASTIC QUAD FLATPACK NO-LEAD



NOTES: A. All linear dimensions are in millimeters. Dimensioning and tolerancing per ASME Y14.5—1994.

- B. This drawing is subject to change without notice.
- C. QFN (Quad Flatpack No-Lead) Package configuration.
- The package thermal pad must be soldered to the board for thermal and mechanical performance. See the Product Data Sheet for details regarding the exposed thermal pad dimensions.



# RTK (S-PVQFN-N20)


# PLASTIC QUAD FLATPACK NO-LEAD

#### THERMAL INFORMATION

This package incorporates an exposed thermal pad that is designed to be attached directly to an external heatsink. The thermal pad must be soldered directly to the printed circuit board (PCB). After soldering, the PCB can be used as a heatsink. In addition, through the use of thermal vias, the thermal pad can be attached directly to the appropriate copper plane shown in the electrical schematic for the device, or alternatively, can be attached to a special heatsink structure designed into the PCB. This design optimizes the heat transfer from the integrated circuit (IC).

For information on the Quad Flatpack No-Lead (QFN) package and its advantages, refer to Application Report, QFN/SON PCB Attachment, Texas Instruments Literature No. SLUA271. This document is available at www.ti.com.

The exposed thermal pad dimensions for this package are shown in the following illustration.



Bottom View


Exposed Thermal Pad Dimensions

4208000-3/G 02/11

NOTE: A. All linear dimensions are in millimeters



# RTK (S-PVQFN-N20)



#### NOTES:

- A. All linear dimensions are in millimeters.
- B. This drawing is subject to change without notice.
- C. Publication IPC-7351 is recommended for alternate designs.
- D. This package is designed to be soldered to a thermal pad on the board. Refer to Application Note, Quad Flat—Pack Packages, Texas Instruments Literature No. SLUA271, and also the Product Data Sheets for specific thermal information, via requirements, and recommended board layout. These documents are available at www.ti.com <a href="https://www.ti.com">http://www.ti.com</a>.
- E. Laser cutting apertures with trapezoidal walls and also rounding corners will offer better paste release. Customers should contact their board assembly site for stencil design recommendations. Refer to IPC 7525 for stencil design
- F. Customers should contact their board fabrication site for recommended solder mask tolerances and via tenting recommendations for vias placed in the thermal pad.



#### IMPORTANT NOTICE AND DISCLAIMER

TI PROVIDES TECHNICAL AND RELIABILITY DATA (INCLUDING DATASHEETS), DESIGN RESOURCES (INCLUDING REFERENCE DESIGNS), APPLICATION OR OTHER DESIGN ADVICE, WEB TOOLS, SAFETY INFORMATION, AND OTHER RESOURCES "AS IS" AND WITH ALL FAULTS, AND DISCLAIMS ALL WARRANTIES, EXPRESS AND IMPLIED, INCLUDING WITHOUT LIMITATION ANY IMPLIED WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR NON-INFRINGEMENT OF THIRD PARTY INTELLECTUAL PROPERTY RIGHTS.

These resources are intended for skilled developers designing with TI products. You are solely responsible for (1) selecting the appropriate TI products for your application, (2) designing, validating and testing your application, and (3) ensuring your application meets applicable standards, and any other safety, security, regulatory or other requirements.

These resources are subject to change without notice. TI grants you permission to use these resources only for development of an application that uses the TI products described in the resource. Other reproduction and display of these resources is prohibited. No license is granted to any other TI intellectual property right or to any third party intellectual property right. TI disclaims responsibility for, and you fully indemnify TI and its representatives against any claims, damages, costs, losses, and liabilities arising out of your use of these resources.

TI's products are provided subject to TI's Terms of Sale, TI's General Quality Guidelines, or other applicable terms available either on ti.com or provided in conjunction with such TI products. TI's provision of these resources does not expand or otherwise alter TI's applicable warranties or warranty disclaimers for TI products. Unless TI explicitly designates a product as custom or customer-specified, TI products are standard, catalog, general purpose devices.

TI objects to and rejects any additional or different terms you may propose.

Copyright © 2025, Texas Instruments Incorporated

Last updated 10/2025