

# **TPS20xxB Current-Limited, Power-Distribution Switches**

#### 1 Features

- 70mΩ High-Side MOSFET
- 500mA Continuous Current
- Thermal and Short-Circuit Protection
- **Accurate Current Limit** (0.75A Minimum, 1.25A Maximum)
- Operating Range: 2.7V to 5.5V
- 0.6ms Typical Rise Time
- Undervoltage Lockout
- Deglitched Fault Report ( OC)
- No OC Glitch During Power Up
- Maximum Standby Supply Current: 1μA (Single, Dual) or 2μA (Triple, Quad)
- Ambient Temperature Range: -40°C to 85°C
- UL Recognized, File Number E169910
- Additional UL Recognition for TPS2042B and TPS2052B for Ganged Configuration

## 2 Applications

- **Heavy Capacitive Loads**
- **Short-Circuit Protections**

## 3 Description


The TPS20xxB power-distribution switches intended for applications where heavy capacitive loads and short circuits are likely to be encountered. devices incorporates  $70m\Omega$  N-channel MOSFET power switches for power-distribution systems that require multiple power switches in a single package. Each switch is controlled by a logic enable input. Gate drive is provided by an internal charge pump designed to control the powerswitch rise times and fall times to minimize current surges during switching. The charge pump requires no external components and allows operation from supplies as low as 2.7V.

When the output load exceeds the current-limit threshold or a short is present, the device limits the output current to a safe level by switching into a constant-current mode, pulling the overcurrent (  $\overline{OCx}$ ) logic output low. When continuous heavy overloads and short circuits increase the power dissipation in the switch, causing the junction temperature to rise, a thermal protection circuit shuts off the switch to prevent damage. Recovery from a thermal shutdown is automatic once the device has cooled sufficiently. Internal circuitry ensures that the switch remains off until valid input voltage is present. This powerdistribution switch is designed to set current limit at 1A (typical).

#### **Device Information**

201100 11110111110111								
PART NUMBER	PACKAGE <sup>(1)</sup>	BODY SIZE (NOM)						
TPS20xxB	SOIC (8)	4.90mm × 3.91mm						
	SOIC (16)	9.90mm × 3.91mm						
	SOT-23 (5)	2.90mm × 1.60mm						
	HVSSOP (8)	3.00mm × 3.00mm						
	SON (8)	3.00mm × 3.00mm						

For all available packages, see the orderable addendum at the end of the data sheet.



**Typical Application Schematic** 




# **Table of Contents**


1 Features	1	8.4 Device Functional Modes	.22
2 Applications	1	9 Application and Implementation	. 23
3 Description		9.1 Application Information	. 23
4 General Switch Catalog		9.2 Typical Application	
5 Pin Configuration and Functions		10 Power Supply Recommendations	
6 Specifications		10.1 Undervoltage Lockout (UVLO)	
6.1 Absolute Maximum Ratings		11 Layout	
6.2 ESD Ratings		11.1 Layout Guidelines	
6.3 Recommended Operating Conditions		11.2 Layout Example	
6.4 Thermal Information	6	11.3 Power Dissipation	. 37
6.5 Electrical Characteristics	7	11.4 Thermal Protection	
6.6 Typical Characteristics (All Devices Excluding		12 Device and Documentation Support	.39
TPS2051BDBV and TPS2052BD)	9	12.1 Receiving Notification of Documentation Updates.	.39
6.7 Typical Characteristics (TPS2051BDBV and		12.2 Support Resources	. 39
TPS2052BD)	13	12.3 Trademarks	
7 Parameter Measurement Information	16	12.4 Electrostatic Discharge Caution	.39
8 Detailed Description	17	12.5 Glossary	
8.1 Overview		13 Revision History	
8.2 Functional Block Diagrams	17	14 Mechanical, Packaging, and Orderable	
8.3 Feature Description		Information	. 40



## 4 General Switch Catalog



## 5 Pin Configuration and Functions



† All enable outputs are active high for the TPS205xB series.

† All enable outputs are active high for the TPS205xB series.

Figure 5-1. TPS2041B and TPS2051B: DBV Package 5-Pin SOT-23 Top View

	-	-	1
GND	ď	8	OC1
IN	2	7	OUT1
EN1 <sup>†</sup>	<b>g</b> 3	6	OUT2
EN2†	4_4	5	OC2

† All enable outputs are active high for the TPS205xB series.

Figure 5-3. TPS2042B and TPS2052B: D and DGN Packages 8-Pin SOIC and HVSSOP Top View

1			
GND	1	16	OC1
IN1	2	15	OUT1
EN1†	3	14	OUT2
EN2†	4	13	OC2
GND [	5	12	OC3
IN2	6	11	OUT3
EN3† [	7	10	NC
NC [	8	9	NC


† All enable outputs are active high for the TPS205xB series.

Figure 5-2. TPS2041B and TPS2051B: D and DGN Packages 8-Pin SOIC and HVSSOP Top View

GND	Ð	<u></u>	OC1
IN	2	Ţ	OUT1
EN1†	3	<u>_6</u>	OUT2
EN2†	40	<u>_5</u>	OC2

† All enable outputs are active high for the TPS205xB series.

Figure 5-4. TPS2042B and TPS2052B: DRB Package 8-Pin SON Top View



† All enable outputs are active high for the TPS205xB series.

Figure 5-5. TPS2043B and TPS2053B: D Package 16-Pin SOIC Top View

Figure 5-6. TPS2044B and TPS2054B: D Package 16-Pin SOIC Top View

Table 5-1. Pin Functions (TPS2041B and TPS2051B)

		PIN						
NAME	TPS2041B	TPS2051B	TPS2041B	TPS2051B	I/O	DESCRIPTION		
INAIVIE	SOIC A	ND DGN	so	T-23				
EN	4	_	4	_	ı	Enable input, logic low turns on power switch		
EN	_	4	_	4	I Enable input, logic high turns on power switch			
GND	1	1	2	2	_	Ground		
IN	2, 3	2, 3	5	5	I	Input voltage		
<u>oc</u>	5	5	3	3	0	Overcurrent open-drain output, active-low		



## Table 5-1. Pin Functions (TPS2041B and TPS2051B) (continued)

		PIN						
NAME	TPS2041B	TPS2051B	TPS2041B	TPS2051B	1/0	DESCRIPTION		
INAIVIE	SOIC A	ND DGN	so	T-23				
OUT	6, 7, 8	6, 7, 8	1	1	0	Power-switch output		

## Table 5-2. Pin Functions (TPS2042B and TPS2052B)

	PIN						
NAME	TPS2042B	TPS2052B	I/O	DESCRIPTION			
NAIVIE	SOIC, HVS	SOP, SON					
EN1	3	_	I	Enable input, logic low turns on power switch IN-OUT1			
EN2	4	_	I	Enable input, logic low turns on power switch IN-OUT2			
EN1	_	3	I	Enable input, logic high turns on power switch IN-OUT1			
EN2	_	4	I	Enable input, logic high turns on power switch IN-OUT2			
GND	1	1	_	Ground			
IN	2	2	I	Input voltage			
OC1	8	8	0	Overcurrent, open-drain output, active low, IN-OUT1			
OC2	5	5	0	Overcurrent, open-drain output, active low, IN-OUT2			
OUT1	7	7	0	Power-switch output, IN-OUT1			
OUT2	6	6	0	Power-switch output, IN-OUT2			
PowerPAD <sup>TM</sup>	_	_	_	Internally connected to GND; used to heat-sink the part to the circuit board traces. Must be connected to GND pin.			

## Table 5-3. Pin Functions (TPS2043B and TPS2053B)

	PIN				
NAME	TPS2043B	TPS2053B	I/O	DESCRIPTION	
INAIVIE	SOIC	SOIC			
EN1	3	_	I	Enable input, logic low turns on power switch IN1-OUT1	
EN2	4	_	I	Enable input, logic low turns on power switch IN1-OUT2	
EN3	7	_	I	Enable input, logic low turns on power switch IN2-OUT3	
EN1	_	3	I	Enable input, logic high turns on power switch IN1-OUT1	
EN2	_	4	I	Enable input, logic high turns on power switch IN1-OUT2	
EN3	_	7	I	Enable input, logic high turns on power switch IN2-OUT3	
GND	1, 5	1, 5	_	Ground	
IN1	2	2	I	Input voltage for OUT1 and OUT2	
IN2	6	6	I	Input voltage for OUT3	
NC	8, 9, 10	8, 9, 10	_	No connection	
OC1	16	16	0	Overcurrent, open-drain output, active low, IN1-OUT1	
OC2	13	13	0	Overcurrent, open-drain output, active low, IN1-OUT2	
OC3	12	12	0	Overcurrent, open-drain output, active low, IN2-OUT3	
OUT1	15	15	0	Power-switch output, IN1-OUT1	
OUT2	14	14	0	Power-switch output, IN1-OUT2	
OUT3	11	11	0	Power-switch output, IN2-OUT3	



## Table 5-4. Pin Functions (TPS2044B and TPS2054B)

	PIN				
NAME	TPS2044B	TPS2054B	I/O	DESCRIPTION	
NAIVIE	SOIC	SOIC			
EN1	3	_	I	Enable input, logic low turns on power switch IN1-OUT1	
EN2	4	_	I	Enable input, logic low turns on power switch IN1-OUT2	
EN3	7	_	I	Enable input, logic low turns on power switch IN2-OUT3	
EN4	8	_	I	Enable input, logic low turns on power switch IN2-OUT4	
EN1	_	3	I	Enable input, logic high turns on power switch IN1-OUT1	
EN2	_	4	I	Enable input, logic high turns on power switch IN1-OUT2	
EN3	_	7	I	Enable input, logic high turns on power switch IN2-OUT3	
EN4	_	8	I	Enable input, logic high turns on power switch IN2-OUT4	
GND	1, 5	1, 5	_	Ground	
IN1	2	2	I	Input voltage for OUT1 and OUT2	
IN2	6	6	I	Input voltage for OUT3 and OUT4	
OC1	16	16	0	Overcurrent, open-drain output, active low, IN1-OUT1	
OC2	13	13	0	Overcurrent, open-drain output, active low, IN1-OUT2	
OC3	12	12	0	Overcurrent, open-drain output, active low, IN2-OUT3	
OC4	9	9	0	Overcurrent, open-drain output, active low, IN2-OUT4	
OUT1	15	15	0	Power-switch output, IN1-OUT1	
OUT2	14	14	0	Power-switch output, IN1-OUT2	
OUT3	11	11	0	Power-switch output, IN2-OUT3	
OUT4	10	10	0	Power-switch output, IN2-OUT4	



## **6 Specifications**

## 6.1 Absolute Maximum Ratings

over operating free-air temperature range (unless otherwise noted) (1)

		MIN	MAX	UNIT
V <sub>I(IN)</sub> , V <sub>I(INx)</sub>	Input voltage (2)	-0.3	6	V
V <sub>O(OUT)</sub> , V <sub>O(OUTx)</sub> (2)	Output voltage	-0.3	6	V
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$	Input voltage	-0.3	6	V
$V_{I(/OC)}, V_{I(\overline{OCx})}$	Voltage range	-0.3	6	V
I <sub>O(OUT)</sub> , I <sub>O(OUTx)</sub>	Continuous output current	Internall	y limited	
T <sub>J</sub>	Operating virtual junction temperature	-40	125	°C
T <sub>stg</sub>	Storage temperature	<del>-</del> 65	150	°C

<sup>(1)</sup> Stresses beyond those listed under Absolute Maximum Ratings may cause permanent damage to the device. These are stress ratings only, which do not imply functional operation of the device at these or any other conditions beyond those indicated under Recommended Operating Conditions. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.

## 6.2 ESD Ratings

			VALUE	UNIT
		Human body model (HBM), per ANSI/ESDA/JEDEC JS-001, all pins <sup>(1)</sup>	±2000	
V <sub>(ESD)</sub>	Electrostatic discharge	Charged device model (CDM), per JEDEC specification JESD22-C101, all pins <sup>(2)</sup>	±500	V

<sup>(1)</sup> JEDEC document JEP155 states that 500-V HBM allows safe manufacturing with a standard ESD control process.

## **6.3 Recommended Operating Conditions**

over operating free-air temperature range (unless otherwise noted)

		MIN	NOM MAX	UNIT
V <sub>I(IN)</sub> , V <sub>I(INx)</sub>	Input voltage	2.7	5.5	V
$\begin{bmatrix} V_{I(\;\overline{EN})},\; V_{I(\;\overline{ENx})},\; V_{I(EN)},\\ V_{I(ENx)} \end{bmatrix}$	Input voltage	0	5.5	٧
I <sub>O(OUT)</sub> , I <sub>O(OUTx)</sub>	Continuous output current	0	500	mA
T <sub>J</sub>	Operating virtual junction temperature	-40	125	°C

#### 6.4 Thermal Information

THERMAL METRIC <sup>(1)</sup>		D (SOIC)		DBV (SOT-23)	DGN (HVSSOP)	DRB (SON)	UNIT
		8 PINS	16 PINS	5 PINS	8 PINS	8 PINS	
$R_{\theta JA}$	Junction-to-ambient thermal resistance	119.3	81.6	208.6	53.6	47.5	°C/W
$R_{\theta JC(top)}$	Junction-to-case (top) thermal resistance	67.6	42.7	122.9	58.7	53	°C/W
R <sub>θJB</sub>	Junction-to-board thermal resistance	59.6	39.1	37.8	35.5	14.2	°C/W
ΨЈТ	Junction-to-top characterization parameter	20.3	10.4	14.6	2.7	1.2	°C/W
ΨЈВ	Junction-to-board characterization parameter	59.1	38.8	36.9	35.3	14.2	°C/W
R <sub>θJC(bot)</sub>	Junction-to-case (bottom) thermal resistance	N/A	N/A	N/A	6.7	7.3	°C/W

For more information about traditional and new thermal metrics, see the Semiconductor and IC Package Thermal Metrics application report.

<sup>(2)</sup> All voltages are with respect to GND.

<sup>(2)</sup> JEDEC document JEP157 states that 250-V CDM allows safe manufacturing with a standard ESD control process.



#### 6.5 Electrical Characteristics

over recommended operating junction temperature range,  $V_{I(IN)} = 5.5 \text{ V}$ ,  $I_O = 0.5 \text{ A}$ ,  $V_{I(/ENx)} = 0 \text{ V}$  (unless otherwise noted)

PARAMETER TEST CONDITIONS <sup>(1)</sup>				MIN	TYP	MAX	UNIT	
POWE	R SWITCH							
	Static drain-source on-state resistance, 5-V operation and	$V_{I(IN)} = 5 \text{ V or } 3.3$ -40°C \le T_1 \le 125°		D and DGN packages		70	135	mΩ
3.3-V operation		15 5 15 125		DBV package only		95	140	
r <sub>DS(on)</sub>	Static drain-source on-state resistance, 2.7-V operation	$V_{I(IN)} = 2.7 \text{ V, } I_O = -40^{\circ}\text{C} \le T_J \le 125$		D and DGN packages		75	150	mΩ
	Static drain-source on-state resistance, 5-V operation	V <sub>I(IN)</sub> = 5 V, I <sub>O</sub> = 1 connected, 0°C ≤	A, OUT1 and OUT2 T <sub>J</sub> ≤ 70°C	DGN package, TPS2042B/52B			49	mΩ
	Rise time, output	V <sub>I(IN)</sub> = 5.5 V				0.6	1.5	
t <sub>r</sub>	rtise time, output	$V_{I(IN)} = 2.7 \text{ V}$	C <sub>L</sub> = 1 μF,	T <sub>.1</sub> = 25°C		0.4	1	ms
t <sub>f</sub>	Fall time, output	$V_{I(IN)} = 5.5 V$	$R_L = 10 \Omega$	11 - 23 0	0.05		0.5	1113
ч	Tail time, output	$V_{I(IN)} = 2.7 \text{ V}$			0.05		0.5	
ENAB	LE INPUT EN AND EN	x						
V <sub>IH</sub>	High-level input voltage	$2.7 \text{ V} \le V_{I(IN)} \le 5.5$	5 V		2			V
V <sub>IL</sub>	Low-level input voltage	$2.7 \text{ V} \leq V_{I(IN)} \leq 5.5$	$2.7 \text{ V} \le \text{V}_{\text{I(IN)}} \le 5.5 \text{ V}$				0.8	•
I <sub>I</sub>	Input current	$V_{I(\overline{ENx})} = 0 \text{ V or } 5$	V <sub>I(ENx)</sub> = 0 V or 5.5 V				0.5	μΑ
t <sub>on</sub>	Turnon time	$C_L = 100  \mu F,  R_L =$	: 10 Ω				3	ms
t <sub>off</sub>	Turnoff time $C_L = 100 \mu F, R_L = 10 \Omega$						10	1110
CURR	ENT LIMIT							
	a	V <sub>I(IN)</sub> = 5 V, OUT connected to GND, device enabled into short-circuit		T <sub>J</sub> = 25°C	0.75	1	1.25	
Hoc	Short-circuit output current	-on out output	-40°C ≤ T <sub>J</sub> ≤ 125°C 0°C ≤ T <sub>J</sub> ≤ 70°C	0.7	1	1.3	Α	
		$V_{(  N )} = 5 \text{ V, } \text{OOTT}$ and $\text{OOTZ}$ connected to $\text{OCST}_3 \leq 70 \text{ GND, }$ device enabled into short-circuit, measure at IN TPS2042B/52			1.5			
I <sub>OC</sub> (2)	Overcurrent trip threshold	V <sub>IN</sub> = 5 V, 100 A/s			I <sub>OS</sub>	1.55	2	Α
SUPPL	Y CURRENT (TPS204	1B, TPS2051B)						
Supply current, low-level		No load on OUT,	$V_{I(\overline{ENx})} = 5.5 \text{ V},$	T <sub>J</sub> = 25°C		0.5	1	μA
output		or $V_{I(ENx)} = 0 V$	-40°°C ≤ T <sub>J</sub> ≤ 125°C			0.5	5	μΑ
Supply	current, high-level			T <sub>J</sub> = 25°C		75	95	μA
output		or $V_{I(ENx)} = 5.5 \text{ V}$		–40°C ≤ T <sub>J</sub> ≤ 125°C		75	95	μ/ (
Leakage current OUT connected to or $V_{I(ENx)} = 0 V$		o ground, $V_{I(\overline{ENx})} = 5.5 \text{ V}$ ,	–40°C ≤ T <sub>J</sub> ≤ 125°C		1		μΑ	
Reverse leakage current $V_{I(OUTx)} = 5.5 \text{ V}, IN = ground$		N = ground	T <sub>J</sub> = 25°C		0		μΑ	
SUPPL	Y CURRENT (TPS204	2B, TPS2052B)						
Supply current, low-level output		No load on OUT, V <sub>I(ENx)</sub> = 5.5 V		T <sub>J</sub> = 25°C		0.5	1	μA
		No load on oo i,	No load off OOT, V <sub>I(ENx)</sub> – 5.5 V			0.5	5	F" '
		nt, high-level No load on OUT, $V_{I(ENx)} = 0 \text{ V}$ TPS20x2B (DRB package only) TPS20x2B		T <sub>J</sub> = 25°C		50	70	μΑ
Supply cı	current, high-level			–40°C ≤ T <sub>J</sub> ≤ 125°C		50	90	μΛ
output			T <sub>J</sub> = 25°C		95	120	uA	
			(D and DGN packages)	–40°C ≤ T <sub>J</sub> ≤ 125°C		95	120	чπ
Leakage current			o ground, $V_{I(\overline{ENx})} = 5.5 \text{ V}$	–40°C ≤ T <sub>J</sub> ≤ 125°C		1		μΑ
Reverse leakage current $V_{I(OUTx)} = 5.5 \text{ V}$ , IN = ground			N = ground	T <sub>J</sub> = 25°C		0.2		μΑ



## 6.5 Electrical Characteristics (continued)

over recommended operating junction temperature range,  $V_{I(IN)} = 5.5 \text{ V}$ ,  $I_O = 0.5 \text{ A}$ ,  $V_{I(/ENx)} = 0 \text{ V}$  (unless otherwise noted)

PARAMETER	ER TEST CONDITIONS <sup>(1)</sup>		MIN	TYP	MAX	UNIT
SUPPLY CURRENT (TPS204	I3B, TPS2053B)					
Supply current, low-level	Na land an OUT V	T <sub>J</sub> = 25°C		0.5	2	
output	No load on OUT, $V_{I(ENx)} = 0 V$	–40°C ≤ T <sub>J</sub> ≤ 125°C		0.5	10	μA
Supply current, high-level	N. I. A. OUT. V. S. S. V.	T <sub>J</sub> = 25°C		65	90	
output	No load on OUT, V <sub>I(ENx)</sub> = 5.5 V	–40°C ≤ T <sub>J</sub> ≤ 125°C		65	110	μA
Leakage current	OUT connected to ground, V <sub>I(ENx)</sub> = 0 V	–40°C≤ T <sub>J</sub> ≤ 125°C		1		μΑ
Reverse leakage current	V <sub>I(OUTx)</sub> = 5.5 V, INx = ground	T <sub>J</sub> = 25°C		0.2		μΑ
SUPPLY CURRENT (TPS204	14B, TPS2054B)	'				
Supply current, low-level	No load on OUT, V <sub>I(ENx)</sub> = 5.5 V,	T <sub>J</sub> = 25°C		0.5	2	
output	or $V_{I(ENx)} = 0 V$	–40°C ≤ T <sub>J</sub> ≤ 125°C		0.5	10	μA
Supply current, high-level	No load on OUT, $V_{I(ENx)} = 0 V$ ,	T <sub>J</sub> = 25°C		75	110	
output	or V <sub>I(ENx)</sub> = 5.5 V	–40°C ≤ T <sub>J</sub> ≤ 125°C		75	140	μA
Leakage current	OUT connected to ground, $V_{I(\overline{ENx})} = 5.5 \text{ V}$ , or $V_{I(ENx)} = 0 \text{ V}$	-40°C≤ T <sub>J</sub> ≤ 125°C		1		μΑ
Reverse leakage current	V <sub>I(OUTx)</sub> = 5.5 V, INx = ground	T <sub>J</sub> = 25°C		0.2		μΑ
UNDERVOLTAGE LOCKOUT	(TPS20x3BD, TPS20x4BD, & TPS20x2BDRB)					
Low-level input voltage, IN, INx			2		2.5	V
Hysteresis, IN, INx	T <sub>J</sub> = 25°C			75		mV
UNDERVOLTAGE LOCKOUT	Г (TPS20x1B & TPS20x2B; D/DBV/DGN packag	es)				
Low-level input voltage, IN, INx			2		2.6	V
Hysteresis, IN, INx	T <sub>J</sub> = 25°C			75		mV
OVERCURRENT OC and OC	<del>x</del>	<u>'</u>				
Output low voltage, V <sub>OL(/OCx)</sub>	$I_{O(\overline{OCx})} = 5 \text{ mA}$				0.4	V
Off-state current	$V_{O(\overline{OCx})} = 5 \text{ V or } 3.3 \text{ V}$				1	μΑ
OC deglitch	OCx assertion or deassertion			8	15	ms
THERMAL SHUTDOWN(3)	,	<u>'</u>				
Thermal shutdown threshold						°C
Recovery from thermal shutdown			125			°C
Hysteresis				10		°C


<sup>(1)</sup> Pulse-testing techniques maintain junction temperature close to ambient temperature; thermal effects must be taken into account separately.

<sup>(2)</sup> TPS20x1B and TPS20x2B devices in the D, DGN, and DBV packages do not have overcurrent trip thresholds. Current is limited to I<sub>OS</sub> under different test condition. Check Section 8.3.7 for more details.

<sup>(3)</sup> The thermal shutdown only reacts under overcurrent conditions.




## 6.6 Typical Characteristics (All Devices Excluding TPS2051BDBV and TPS2052BD)





## 6.6 Typical Characteristics (All Devices Excluding TPS2051BDBV and TPS2052BD) (continued)







Figure 6-8. TPS20x2BDRB Supply Current, Output Disabled vs Junction Temperature







Figure 6-9. TPS2043B and TPS2053B Supply Current, Output Disabled vs Junction Temperature

Figure 6-10. TPS2044B and TPS2054B Supply Current, Output Disabled vs Junction Temperature







Figure 6-11. Static Drain-Source on-State Resistance vs Junction Temperature

Figure 6-12. Short-Circuit Output Current vs Junction Temperature




## 6.6 Typical Characteristics (All Devices Excluding TPS2051BDBV and TPS2052BD) (continued)






## 6.6 Typical Characteristics (All Devices Excluding TPS2051BDBV and TPS2052BD) (continued)






## 6.7 Typical Characteristics (TPS2051BDBV and TPS2052BD)






## 6.7 Typical Characteristics (TPS2051BDBV and TPS2052BD) (continued)






# 6.7 Typical Characteristics (TPS2051BDBV and TPS2052BD) (continued)





# 6.7 Typical Characteristics (TPS2051BDBV and TPS2052BD) (continued)



## 7 Parameter Measurement Information




Figure 7-1. Test Circuit and Voltage Waveforms




## 8 Detailed Description

#### 8.1 Overview

The TPS20xxB are current-limited, power-distribution switches providing 0.5-A continuous load current. These devices incorporates  $70\text{-m}\Omega$  N-channel MOSFET power switches for power-distribution systems that require multiple power switches in a single package. Gate driver is provided by an internal charge pump designed to minimize current surges during switching. The charge pump requires no external components and allows operation supplies as low as 2.7 V.

## 8.2 Functional Block Diagrams




Note A: Current sense

Note B: Active low (EN) for TPS2041B; Active high (EN) for TPS2051B

Figure 8-1. Functional Block Diagram (TPS2041B and TPS2051B)






Note A: Current sense

Note B: Active low  $(\overline{\text{ENx}})$  for TPS2042B; Active high (ENx) for TPS2052B

Figure 8-2. Functional Block Diagram (TPS2042B and TPS2052B)






Note A: Current sense

Note B: Active low (ENx) for TPS2043B; Active high (ENx) for TPS2053B

Figure 8-3. Functional Block Diagram (TPS2043B and TPS2053B)





Note A: Current sense

Note B: Active low (ENx) for TPS2044B; Active high (ENx) for TPS2054B

Figure 8-4. Functional Block Diagram (TPS2044B and TPS2054B)

#### 8.3 Feature Description

#### 8.3.1 Power Switch

The power switch is an N-channel MOSFET with a low on-state resistance. Configured as a high-side switch, the power switch prevents current flow from OUT to IN and IN to OUT when disabled. The power switch supplies a minimum current of 500 mA.



#### 8.3.2 Charge Pump

An internal charge pump supplies power to the driver circuit and provides the necessary voltage to pull the gate of the MOSFET above the source. The charge pump operates from input voltages as low as 2.7 V and requires little supply current.

#### 8.3.3 Driver

The driver controls the gate voltage of the power switch. To limit large current surges and reduce the associated electromagnetic interference (EMI) produced, the driver incorporates circuitry that controls the rise times and fall times of the output voltage.

#### 8.3.4 Enable ( ENx)

The logic enable pin disables the power switch and the bias for the charge pump, driver, and other circuitry to reduce the supply current. The supply current is reduced to less than 1  $\mu$ A or 2  $\mu$ A when a logic high is present on  $\overline{\text{EN}}$ . A logic zero input on  $\overline{\text{EN}}$  restores bias to the drive and control circuits and turns the switch on. The enable input is compatible with both TTL and CMOS logic levels.

#### 8.3.5 Enable (ENx)

The logic enable disables the power switch and the bias for the charge pump, driver, and other circuitry to reduce the supply current. The supply current is reduced to less than 1  $\mu$ A or 2  $\mu$ A when a logic low is present on ENx. A logic high input on ENx restores bias to the drive and control circuits and turns the switch on. The enable input is compatible with both TTL and CMOS logic levels.

#### 8.3.6 Current Sense

A sense FET monitors the current supplied to the load. The sense FET measures current more efficiently than conventional resistance methods. When an overload or short circuit is encountered, the current-sense circuitry sends a control signal to the driver. The driver in turn reduces the gate voltage and drives the power FET into its saturation region, which switches the output into a constant-current mode and holds the current constant while varying the voltage on the load.

#### 8.3.7 Overcurrent

A sense FET is employed to check for overcurrent conditions. Unlike current-sense resistors, sense FETs do not increase the series resistance of the current path. When an overcurrent condition is detected, the device maintains a constant output current and reduces the output voltage accordingly. Complete shutdown occurs only if the fault is present long enough to activate thermal limiting.

There are two kinds of current limit profiles for the TPS20xxB family of devices.

The TPS20x3BD, TPS20x4BD, and TPS20x2BDRB devices have an output I vs V characteristic similar to the plot labeled **Current Limit with Peaking** in Figure 8-5. This type of limiting can be characterized by two parameters, the overcurrent trip threshold ( $I_{OC}$ ), and the short-circuit output current threshold ( $I_{OS}$ ).

The TPS20x1B and TPS20x2B devices in the D, DGN, and DBV packages have an output I vs V characteristic similar to the plot labeled **Flat Current Limit** in Figure 8-5. This type of limiting can be characterized by one parameters, the short circuit current (I<sub>OS</sub>).




Figure 8-5. Current Limit Profiles



#### 8.3.7.1 Overcurrent Conditions (TPS20x3BD, TPS20x4BD, and TPS20x2BDRB)

Three possible overload conditions can occur for TPS20x3BD, TPS20x4BD, and TPS20x2BDRB devices. In the first condition, the output has been shorted before the device is enabled or before  $V_{I(IN)}$  has been applied (see Figure 6-21 through Figure 6-24). The TPS20xxB senses the short and immediately switches into a constant-current output.

In the second condition, a short or an overload occurs while the device is enabled. At the instant the overload occurs, high currents may flow for a short period of time before the current-limit circuit can react. After the current-limit circuit has tripped (reached the overcurrent trip threshold  $(I_{OC})$ ), the device switches into constant-current mode and current is limited at the short-circuit output current threshold  $(I_{OS})$ .

In the third condition, the load has been gradually increased beyond the recommended operating current. The current is permitted to rise until the overcurrent trip threshold ( $I_{OC}$ ) is reached or until the thermal limit of the device is exceeded. The TPS20x3BD, TPS20x4BD, and TPS20x2BDRB are capable of delivering current up to the current-limit threshold without damaging the device. Once the overcurrent trip threshold ( $I_{OC}$ ) has been reached, the device switches into its constant-current mode current is limited at the short-circuit output current threshold ( $I_{OS}$ ).

#### 8.3.7.2 Overcurrent Conditions (TPS20x1B & TPS20x2B in D, DGN, and DBV packages)

Three possible overload conditions can occur for the TPS20x1B and TPS20x2B devices in the D, DGN, and DBV packages. In the first condition, the output has been shorted before the device is enabled or before  $V_{I(IN)}$  has been applied (see Figure 6-42 through Figure 6-45). The TPS20xxB senses the short and immediately switches into a constant-current output.

In the second condition, a short or an overload occurs while the device is enabled. At the instant the overload occurs, high currents may flow for a short period of time before the current-limit circuit can react. After the short-circuit output current threshold ( $I_{OS}$ ) is reached, the device switches into constant-current mode.

In the third condition, the load has been gradually increased beyond the recommended operating current. After the short-circuit output current threshold ( $I_{OS}$ ) is reached, the device switches into constant-current mode.

## 8.3.8 Overcurrent ( OCx)

The  $\overline{OCx}$  open-drain output is asserted (active low) when an overcurrent or overtemperature condition is encountered. The output remains asserted until the overcurrent or overtemperature condition is removed. A 10-ms deglitch circuit prevents the  $\overline{OCx}$  signal from oscillation or false triggering. If an overtemperature shutdown occurs, the  $\overline{OCx}$  is asserted instantaneously.

#### 8.3.9 Thermal Sense

The TPS20xxB implements a thermal sensing to monitor the operating temperature of the power distribution switch. In an overcurrent or short-circuit condition, the junction temperature rises. When the die temperature rises to approximately 140°C due to overcurrent conditions, the internal thermal sense circuitry turns off the switch, thus preventing the device from damage. Hysteresis is built into the thermal sense, and after the device has cooled approximately 10 degrees, the switch turns back on. The switch continues to cycle off and on until the fault is removed. The open-drain false reporting output ( $\overline{OCx}$ ) is asserted (active low) when an overtemperature shutdown or overcurrent occurs.

#### 8.3.10 Undervoltage Lockout

A voltage sense circuit monitors the input voltage. When the input voltage is below approximately 2 V, a control signal turns off the power switch.

#### 8.4 Device Functional Modes

There are no other functional modes for TPS20xxB devices.



# 9 Application and Implementation

#### Note

Information in the following applications sections is not part of the TI component specification, and TI does not warrant its accuracy or completeness. TI's customers are responsible for determining suitability of components for their purposes, as well as validating and testing their design implementation to confirm system functionality.

## 9.1 Application Information

## 9.1.1 Universal Serial Bus (USB) Applications

The universal serial bus (USB) interface is a 12-Mb/s, or 1.5-Mb/s, multiplexed serial bus designed for low-to-medium bandwidth PC peripherals (for example, keyboards, printers, scanners, and mice). The four-wire USB interface is conceived for dynamic attach-detach (hot plug-unplug) of peripherals. Two lines are provided for differential data, and two lines are provided for 5-V power distribution.

USB data is a 3.3-V level signal, but power is distributed at 5 V to allow for voltage drops in cases where power is distributed through more than one hub across long cables. Each function must provide its own regulated 3.3 V from the 5-V input or its own internal power supply.

The USB specification defines the following five classes of devices, each differentiated by power-consumption requirements:

- Hosts and self-powered hubs (SPH)
- Bus-powered hubs (BPH)
- · Low-power, bus-powered functions
- High-power, bus-powered functions
- Self-powered functions

Self-powered and bus-powered hubs distribute data and power to downstream functions. The TPS20xxB can provide power-distribution solutions to many of these classes of devices.

#### 9.2 Typical Application

#### 9.2.1 Typical Application (TPS2042B)




Figure 9-1. Typical Application (Example, TPS2042B)

#### 9.2.1.1 Design Requirements

Table 9-1 shows the design parameters for this application.

**Table 9-1. Design Parameters** 

DESIGN PARAMETER	VALUE
Input voltage	5 V



Table 9-1. Design Parameters (continued)

DESIGN PARAMETER	VALUE
Output1 voltage	5 V
Output2 voltage	5 V
Output1 current	0.5 A
Output2 current	0.5 A

#### 9.2.1.2 Detailed Design Procedure

#### 9.2.1.2.1 Power-Supply Considerations

TI recommends placing a 0.01- $\mu$ F to 0.1- $\mu$ F ceramic bypass capacitor between IN and GND, close to the device. When the output load is heavy, TI recommends placing a high-value electrolytic capacitor on the necessary output pins. This precaution reduces power-supply transients that may cause ringing on the input. Additionally, bypassing the output with a 0.01- $\mu$ F to 0.1- $\mu$ F ceramic capacitor improves the immunity of the device to short-circuit transients.

#### 9.2.1.2.2 OC Response

The  $\overline{\text{OCx}}$  open-drain output is asserted (active low) when an overcurrent or overtemperature shutdown condition is encountered after a 10-ms deglitch timeout. The output remains asserted until the overcurrent or overtemperature condition is removed. Connecting a heavy capacitive load to an enabled device can cause a momentary overcurrent condition; however, no false reporting on  $\overline{\text{OCx}}$  occurs due to the 10-ms deglitch circuit. The TPS20xxB is designed to eliminate false overcurrent reporting. The internal overcurrent deglitch eliminates the need for external components to remove unwanted pulses.  $\overline{\text{OCx}}$  is not deglitched when the switch is turned off due to an overtemperature shutdown.






Figure 9-2. Typical Circuit for the OC Pin (Example, TPS2042B)

#### 9.2.1.3 Application Curves







#### 9.2.2 Host and Self-Powered and Bus-Powered Hubs

Hosts and self-powered hubs have a local power supply that powers the embedded functions and the downstream ports (see Figure 9-11 and Figure 9-12). This power supply must provide from 5.25 V to 4.75 V to the board side of the downstream connection under full-load and no-load conditions. Hosts and SPHs are required to have current-limit protection and must report overcurrent conditions to the USB controller. Typical SPHs are desktop PCs, monitors, printers, and stand-alone hubs.




Figure 9-11. Typical One-Port USB Host and Self-Powered Hub




Figure 9-12. Typical Four-Port USB Host and Self-Powered Hub

#### 9.2.2.1 Design Requirements

#### 9.2.2.1.1 USB Power-Distribution Requirements


USB can be implemented in several ways, and, regardless of the type of USB device being developed, several power-distribution features must be implemented.

- Hosts and self-powered hubs must:
  - Current-limit downstream ports
  - Report overcurrent conditions on USB V<sub>BUS</sub>
- Bus-powered hubs must:
  - Enable/disable power to downstream ports
  - Power up at <100 mA</li>



- Limit inrush current (<44  $\Omega$  and 10  $\mu$ F)
- Functions must:
  - Limit inrush currents
  - Power up at <100 mA

The feature set of the TPS20xxB allows them to meet each of these requirements. The integrated current-limiting and overcurrent reporting is required by hosts and self-powered hubs. The logic-level enable and controlled rise times meet the need of both input and output ports on bus-powered hubs, as well as the input ports for bus-powered functions (see Figure 9-13 through Figure 9-16).



<sup>&</sup>lt;sup>†</sup> USB rev 1.1 requires 120 µF per hub.

Copyright © 2016, Texas Instruments Incorporated

Figure 9-13. Hybrid Self and Bus-Powered Hub Implementation, TPS2041B and TPS2051B







Figure 9-14. Hybrid Self and Bus-Powered Hub Implementation, TPS2042B and TPS2052B





 $^\dagger$  USB rev 1.1 requires 120  $\mu F$  per hub.

Copyright © 2016, Texas Instruments Incorporated

Figure 9-15. Hybrid Self and Bus-Powered Hub Implementation, TPS2043B and TPS2053B






Figure 9-16. Hybrid Self and Bus-Powered Hub Implementation, TPS2044B and TPS2054B

#### 9.2.2.2 Detailed Design Procedure

Bus-powered hubs obtain all power from upstream ports and often contain an embedded function. The hubs are required to power up with less than one unit load. The BPH usually has one embedded function, and power is always available to the controller of the hub. If the embedded function and hub require more than 100 mA on power up, the power to the embedded function may need to be kept off until enumeration is completed. This can be accomplished by removing power or by shutting off the clock to the embedded function. Power switching the embedded function is not necessary if the aggregate power draw for the function and controller is less than one unit load. The total current drawn by the bus-powered device is the sum of the current to the controller, the embedded function, and the downstream ports, and it is limited to 500 mA from an upstream port.

#### 9.2.2.2.1 Low-Power Bus-Powered and High-Power Bus-Powered Functions

Both low-power and high-power bus-powered functions obtain all power from upstream ports; low-power functions always draw less than 100 mA; high-power functions must draw less than 100 mA at power up and can draw up to 500 mA after enumeration. If the load of the function is more than the parallel combination of 44  $\Omega$  and 10  $\mu$ F at power up, the device must implement inrush current limiting (see Figure 9-17).








Figure 9-17. High-Power Bus-Powered Function (Example, TPS2042B)

#### 9.2.2.3 Application Curves







#### 9.2.3 Generic Hot-Plug Applications

In many applications it may be necessary to remove modules or pc boards while the main unit is still operating. These are considered hot-plug applications. Such implementations require the control of current surges seen by the main power supply and the card being inserted. The most effective way to control these surges is to limit and slowly ramp the current and voltage being applied to the card, similar to the way in which a power supply normally turns on. Due to the controlled rise times and fall times of the TPS20xxB, these devices can be used to provide a softer start-up to devices being hot-plugged into a powered system. The UVLO feature of the TPS20xxB also ensures that the switch is off after the card has been removed, and that the switch is off during the next insertion. The UVLO feature insures a soft start with a controlled rise time for every insertion of the card or module.






Figure 9-26. Typical Hot-Plug Implementation (Example, TPS2042B)

By placing the TPS20xxB between the  $V_{CC}$  input and the rest of the circuitry, the input power reaches these devices first after insertion. The typical rise time of the switch is approximately 1 ms, providing a slow voltage ramp at the output of the device. This implementation controls system surge currents and provides a hot-plugging mechanism for any device.

#### 9.2.3.1 Design Requirements

Table 9-2 shows the design parameters for this application.

rable of 2. Design rarameters				
DESIGN PARAMETER	VALUE			
Input voltage	5 V			
Output1 voltage	5 V			
Output2 voltage	5 V			
Output1 current	0.5 A			
Output2 current	0.5 A			

**Table 9-2. Design Parameters** 

#### 9.2.3.2 Detailed Design Procedure


To begin the design process a few parameters must be decided upon. The designer needs to know the following:

- · Normal Input Operation Voltage
- Current Limit

Input and output capacitance improves the performance of the device; the actual capacitance must be optimized for the particular application. For all applications, TI recommends a 0.1-µF or greater ceramic bypass capacitor between IN and GND, as close to the device as possible for local noise decoupling. This precaution reduces ringing on the input due to power-supply transients. Additional input capacitance may be needed on the input to reduce voltage undershoot from exceeding the UVLO of other load share one power rail with TPS2042 device or overshoot from exceeding the absolute-maximum voltage of the device during heavy transient conditions. Preventing voltage undershoots and overshoots is especially important during bench testing when long, inductive cables are used to connect the evaluation board to the bench power supply. Output capacitance is not required, but TI recommends placing a high-value electrolytic capacitor on the output pin when large transient currents are expected on the output to reduce the undershoot, which is caused by the inductance of the output power bus just after a short has occurred and the TPS2042 device has abruptly reduced OUT current. Energy stored in the inductance drives the OUT voltage down and potentially negative as it discharges.




#### 9.2.3.3 Application Curves





www.ti.com



SLVS514P - APRIL 2004 - REVISED AUGUST 2024



# 10 Power Supply Recommendations 10.1 Undervoltage Lockout (UVLO)

An undervoltage lockout ensures that the power switch is in the off state at power up. Whenever the input voltage falls below approximately 2 V, the power switch is quickly turned off. The UVLO facilitates the design of hot-insertion systems where it is not possible to turn off the power switch before input power is removed. The UVLO also keeps the switch from being turned on until the power supply has reached at least 2 V, even if the switch is enabled. On reinsertion, the power switch is turned on, with a controlled rise time to reduce EMI and voltage overshoots.



## 11 Layout

## 11.1 Layout Guidelines

- Place the 100-nF bypass capacitor near the IN and GND pins, and make the connections using a low-inductance trace.
- Placing a high-value electrolytic capacitor and a 100-nF bypass capacitor on the output pin is recommended when large transient currents are expected on the output.
- The PowerPAD must be directly connected to PCB ground plane using wide and short copper trace.

## 11.2 Layout Example




Figure 11-1. Layout Recommendation

### 11.3 Power Dissipation

The low on-resistance on the N-channel MOSFET allows the small surface-mount packages to pass large currents. The thermal resistances of these packages are high compared to those of power packages; it is good design practice to check power dissipation and junction temperature. Begin by determining the  $r_{DS(on)}$  of the N-channel MOSFET relative to the input voltage and operating temperature. As an initial estimate, use the highest operating ambient temperature of interest and read  $r_{DS(on)}$  from Figure 6-11. Using this value, the power dissipation per switch can be calculated by Equation:

$$P_D = r_{DS(on)} \times I^2$$

Multiply this number by the number of switches being used. This step renders the total power dissipation from the N-channel MOSFETs.

Finally, calculate the junction temperature with Equation:

$$T_J = P_D \times R_{\theta JA} + T_A$$

#### where

- T<sub>A</sub>= Ambient temperature °C
- R<sub>0,JA</sub> = Thermal resistance
- P<sub>D</sub> = Total power dissipation based on number of switches being used.

Compare the calculated junction temperature with the initial estimate. If they do not agree within a few degrees, repeat the calculation, using the calculated value as the new estimate. Two or three iterations are generally sufficient to get a reasonable answer.

### 11.4 Thermal Protection

Thermal protection prevents damage to the IC when heavy-overload or short-circuit faults are present for extended periods of time. The TPS20xxB implements a thermal sensing to monitor the operating junction



temperature of the power distribution switch. In an overcurrent or short-circuit condition, the junction temperature rises due to excessive power dissipation. Once the die temperature rises to approximately  $140^{\circ}$ C due to overcurrent conditions, the internal thermal sense circuitry turns the power switch off, thus preventing the power switch from damage. Hysteresis is built into the thermal sense circuit, and after the device has cooled approximately  $10^{\circ}$ C, the switch turns back on. The switch continues to cycle in this manner until the load fault or input power is removed. The  $\overline{OCx}$  open-drain output is asserted (active low) when an overtemperature shutdown or overcurrent occurs.



## 12 Device and Documentation Support

## 12.1 Receiving Notification of Documentation Updates

To receive notification of documentation updates, navigate to the device product folder on ti.com. Click on *Notifications* to register and receive a weekly digest of any product information that has changed. For change details, review the revision history included in any revised document.

## 12.2 Support Resources

TI E2E<sup>™</sup> support forums are an engineer's go-to source for fast, verified answers and design help — straight from the experts. Search existing answers or ask your own question to get the quick design help you need.

Linked content is provided "AS IS" by the respective contributors. They do not constitute TI specifications and do not necessarily reflect TI's views; see TI's Terms of Use.

#### 12.3 Trademarks

TI E2E<sup>™</sup> is a trademark of Texas Instruments.

All trademarks are the property of their respective owners.

## 12.4 Electrostatic Discharge Caution



This integrated circuit can be damaged by ESD. Texas Instruments recommends that all integrated circuits be handled with appropriate precautions. Failure to observe proper handling and installation procedures can cause damage.

ESD damage can range from subtle performance degradation to complete device failure. Precision integrated circuits may be more susceptible to damage because very small parametric changes could cause the device not to meet its published specifications.

### 12.5 Glossary

TI Glossary

This glossary lists and explains terms, acronyms, and definitions.

### 13 Revision History

NOTE: Page numbers for previous revisions may differ from page numbers in the current version.

C	hanges from Revision O (June 2024) to Revision P (August 2024)	Page
•	Removed revision history comment about adding TPS2051BDB to this section	21
	hanges from Pavision N / July 2022) to Pavision O / June 2024)	Page
	hanges from Revision N (July 2023) to Revision O (June 2024)	Page
•	Updated origination date from June 2010 to April 2004 to match initial release of the data sheet	
•	Deleted Dissipation Ratings table	
•	Deleted "TPS2042xx and TPS2053xx" in table title	6
•	Updated max UVLO and Supply current, high-level output values for the TPS2041BDR, TPS2041BD0	GNR,
	TPS2042BDR, TPS2042BDGNR, TPS2051BDR, TPS2051BDGNR, TPS2052BDGNR, and	
	TPS2041BDBVR	7
•	Updated Overcurrent trip threshold to apply only to TPS2042B and TPS2052B (DRB packages only).	
	Updated Section 8.3.7to show that the TPS20x1B and TPS20x2B devices in the D, DGN, and DBV page 1.00 per page 1.00	
	do not have overcurrent trip thresholds	21
	Updated Section 8.3.7.1	22
	Updated Section 8.3.7.2	
	Updated Section 6.5.7.2	

Changes from Revision M (June 2016) to Revision N (July 2023)

Page



•	Update TPS2051BDBV and TPS2052BD electrical characteristics, including overcurrent trip threshol level output supply current and undervoltage lockout	, ,
C	hanges from Revision L (June 2011) to Revision M (June 2016)	Page
•	Added ESD Ratings table, Feature Description section, Device Functional Modes, Application and Implementation section, Power Supply Recommendations section, Layout section, Device and Documentation Support section, and Mechanical, Packaging, and Orderable Information section	6

## 14 Mechanical, Packaging, and Orderable Information

The following pages include mechanical, packaging, and orderable information. This information is the most current data available for the designated devices. This data is subject to change without notice and revision of this document. For browser-based versions of this data sheet, refer to the left-hand navigation.




## TPS2XXX/XXXX DBV0005A-C02



### **PACKAGE OUTLINE**

### SOT-23 - 1.25 mm max height

SMALL OUTLINE TRANSISTOR



- 1. All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.

  2. This drawing is subject to change without notice.

  3. Refernce JEDEC MO-178.

- 4. Body dimensions do not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not exceed 0.25 mm per side.

  5. Support pin may differ or may not be present.






### **EXAMPLE BOARD LAYOUT**

## DBV0005A-C02

### SOT-23 - 1.25 mm max height

SMALL OUTLINE TRANSISTOR



- 6. Publication IPC-7351 may have alternate designs.
- 7. Solder mask tolerances between and around signal pads can vary based on board fabrication site.






### **EXAMPLE STENCIL DESIGN**

## DBV0005A-C02

## SOT-23 - 1.25 mm max height

SMALL OUTLINE TRANSISTOR



- 8. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.

  9. Board assembly site may have different recommendations for stencil design.



www.ti.com 31-Oct-2025

## **PACKAGING INFORMATION**

Orderable part number	Status (1)	Material type	Package   Pins	Package qty   Carrier	<b>RoHS</b> (3)	Lead finish/ Ball material	MSL rating/ Peak reflow	Op temp (°C)	Part marking (6)
TPS2041BDBVR	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	Yes	NIPDAU   SN	Level-1-260C-UNLIM	-40 to 125	PLII
TPS2041BDBVR.A	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	Yes	SN	Level-1-260C-UNLIM	-40 to 125	PLII
TPS2041BDBVRG4	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	Yes	SN	Level-1-260C-UNLIM	-40 to 125	PLII
TPS2041BDGNR	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU   NIPDAUAG   NIPDAU	Level-1-260C-UNLIM	-40 to 125	2041B
TPS2041BDGNR.A	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2041B
TPS2041BDR	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2041B
TPS2041BDR.A	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2041B
TPS2041BDRG4	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2041B
TPS2042BDGNR	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU   NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2042BDGNR.A	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2042BDGNRG4	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2042BDR	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2042BDR.A	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2042BDRBR	Active	Production	SON (DRB)   8	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRBR.A	Active	Production	SON (DRB)   8	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRBT	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRBT.A	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRBTG4	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRBTG4.A	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042
TPS2042BDRG4	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2042B
TPS2043BD	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2043B
TPS2043BD.A	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2043B
TPS2043BDR	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2043B
TPS2043BDR.A	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2043B
TPS2043BDRG4	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2043B
TPS2044BD	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B
TPS2044BD.A	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B
TPS2044BDG4	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B





www.ti.com 31-Oct-2025

Orderable part number	Status (1)	Material type	Package   Pins	Package qty   Carrier	<b>RoHS</b> (3)	Lead finish/ Ball material	MSL rating/ Peak reflow	Op temp (°C)	Part marking (6)
TPS2044BDR	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B
TPS2044BDR.A	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B
TPS2044BDRG4	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2044B
TPS2051BDBVR	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	Yes	NIPDAU   SN	Level-1-260C-UNLIM	-40 to 125	PLJI
TPS2051BDBVR.A	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	PLJI
TPS2051BDBVR1G4.A	Active	Production	SOT-23 (DBV)   5	3000   LARGE T&R	-	Call TI	Call TI	-40 to 125	PLJI
TPS2051BDBVT	Obsolete	Production	SOT-23 (DBV)   5	-	-	Call TI	Call TI	-40 to 125	PLJI
TPS2051BDGNR	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU   NIPDAUAG   NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2051BDGNR.A	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2051BDGNRG4	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2051BDR	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2051BDR.A	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2051BDRG4	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2051B
TPS2052BD	Obsolete	Production	SOIC (D)   8	-	-	Call TI	Call TI	-40 to 125	2052B
TPS2052BDGNR	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU   NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052B
TPS2052BDGNR.A	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052B
TPS2052BDGNRG4	Active	Production	HVSSOP (DGN)   8	2500   LARGE T&R	Yes	FULL NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052B
TPS2052BDR	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052B
TPS2052BDR.A	Active	Production	SOIC (D)   8	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052B
TPS2052BDRBR	Active	Production	SON (DRB)   8	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052
TPS2052BDRBR.A	Active	Production	SON (DRB)   8	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052
TPS2052BDRBR.B	Active	Production	SON (DRB)   8	3000   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052
TPS2052BDRBT	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 85	2052
TPS2052BDRBT.A	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 85	2052
TPS2052BDRBT.B	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 85	2052
TPS2052BDRBTG4	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052
TPS2052BDRBTG4.A	Active	Production	SON (DRB)   8	250   SMALL T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2052
TPS2053BD	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2053B
TPS2053BD.A	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2053B



-40 to 125

31-Oct-2025

2054B



TPS2054BDRG4.A

www.ti.com

Orderable part number	Status	Material type	Package   Pins	Package qty   Carrier	<b>RoHS</b> (3)	Lead finish/ Ball material	MSL rating/ Peak reflow	Op temp (°C)	Part marking (6)
						(4)	(5)		
TPS2053BDR	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2053B
TPS2053BDR.A	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2053B
TPS2054BD	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2054B
TPS2054BD.A	Active	Production	SOIC (D)   16	40   TUBE	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2054B
TPS2054BDR	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2054B
TPS2054BDR.A	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2054B
TPS2054BDRG4	Active	Production	SOIC (D)   16	2500   LARGE T&R	Yes	NIPDAU	Level-1-260C-UNLIM	-40 to 125	2054B

Yes

NIPDAU

Level-1-260C-UNLIM

Active

2500 | LARGE T&R

Production

SOIC (D) | 16

Multiple part markings will be inside parentheses. Only one part marking contained in parentheses and separated by a "~" will appear on a part. If a line is indented then it is a continuation of the previous line and the two combined represent the entire part marking for that device.

Important Information and Disclaimer: The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.

In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.

<sup>(1)</sup> Status: For more details on status, see our product life cycle.

<sup>(2)</sup> Material type: When designated, preproduction parts are prototypes/experimental devices, and are not yet approved or released for full production. Testing and final process, including without limitation quality assurance, reliability performance testing, and/or process qualification, may not yet be complete, and this item is subject to further changes or possible discontinuation. If available for ordering, purchases will be subject to an additional waiver at checkout, and are intended for early internal evaluation purposes only. These items are sold without warranties of any kind.

<sup>(3)</sup> RoHS values: Yes, No, RoHS Exempt. See the TI RoHS Statement for additional information and value definition.

<sup>(4)</sup> Lead finish/Ball material: Parts may have multiple material finish options. Finish options are separated by a vertical ruled line. Lead finish/Ball material values may wrap to two lines if the finish value exceeds the maximum column width.

<sup>(5)</sup> MSL rating/Peak reflow: The moisture sensitivity level ratings and peak solder (reflow) temperatures. In the event that a part has multiple moisture sensitivity ratings, only the lowest level per JEDEC standards is shown. Refer to the shipping label for the actual reflow temperature that will be used to mount the part to the printed circuit board.

<sup>(6)</sup> Part marking: There may be an additional marking, which relates to the logo, the lot trace code information, or the environmental category of the part.

## PACKAGE OPTION ADDENDUM

www.ti.com 31-Oct-2025

### OTHER QUALIFIED VERSIONS OF TPS2041B, TPS2042B, TPS2051B:

• Automotive: TPS2041B-Q1, TPS2042B-Q1, TPS2051B-Q1

● Enhanced Product : TPS2041B-EP

NOTE: Qualified Version Definitions:

• Automotive - Q100 devices qualified for high-reliability automotive applications targeting zero defects

• Enhanced Product - Supports Defense, Aerospace and Medical Applications



www.ti.com 17-Oct-2025

## TAPE AND REEL INFORMATION





A0	Dimension designed to accommodate the component width
В0	Dimension designed to accommodate the component length
K0	Dimension designed to accommodate the component thickness
W	Overall width of the carrier tape
P1	Pitch between successive cavity centers

### QUADRANT ASSIGNMENTS FOR PIN 1 ORIENTATION IN TAPE



#### \*All dimensions are nominal

Device	Package Type	Package Drawing	Pins	SPQ	Reel Diameter (mm)	Reel Width W1 (mm)	A0 (mm)	B0 (mm)	K0 (mm)	P1 (mm)	W (mm)	Pin1 Quadrant
TPS2041BDBVR	SOT-23	DBV	5	3000	178.0	9.0	3.23	3.17	1.37	4.0	8.0	Q3
TPS2041BDBVR	SOT-23	DBV	5	3000	180.0	8.4	3.2	3.2	1.4	4.0	8.0	Q3
TPS2041BDGNR	HVSSOP	DGN	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2041BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2041BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2042BDGNR	HVSSOP	DGN	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2042BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2042BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2042BDRBR	SON	DRB	8	3000	330.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2042BDRBT	SON	DRB	8	250	180.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2042BDRBTG4	SON	DRB	8	250	180.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2043BDR	SOIC	D	16	2500	330.0	16.4	6.5	10.3	2.1	8.0	16.0	Q1
TPS2044BDR	SOIC	D	16	2500	330.0	16.4	6.5	10.3	2.1	8.0	16.0	Q1
TPS2051BDBVR	SOT-23	DBV	5	3000	180.0	8.4	3.2	3.2	1.4	4.0	8.0	Q3
TPS2051BDGNR	HVSSOP	DGN	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2051BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1



## PACKAGE MATERIALS INFORMATION

www.ti.com 17-Oct-2025

Device	Package Type	Package Drawing		SPQ	Reel Diameter (mm)	Reel Width W1 (mm)	A0 (mm)	B0 (mm)	K0 (mm)	P1 (mm)	W (mm)	Pin1 Quadrant
TPS2051BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2052BDGNR	HVSSOP	DGN	8	2500	330.0	12.4	5.3	3.3	1.3	8.0	12.0	Q1
TPS2052BDGNR	HVSSOP	DGN	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2052BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2052BDR	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
TPS2052BDRBR	SON	DRB	8	3000	330.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2052BDRBT	SON	DRB	8	250	180.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2052BDRBTG4	SON	DRB	8	250	180.0	12.4	3.3	3.3	1.0	8.0	12.0	Q2
TPS2053BDR	SOIC	D	16	2500	330.0	16.4	6.5	10.3	2.1	8.0	16.0	Q1
TPS2054BDR	SOIC	D	16	2500	330.0	16.4	6.5	10.3	2.1	8.0	16.0	Q1
TPS2054BDRG4	SOIC	D	16	2500	330.0	16.4	6.5	10.3	2.1	8.0	16.0	Q1



www.ti.com 17-Oct-2025



\*All dimensions are nominal

Device	Package Type	Package Drawing	Pins	SPQ	Length (mm)	Width (mm)	Height (mm)
TPS2041BDBVR	SOT-23	DBV	5	3000	180.0	180.0	18.0
TPS2041BDBVR	SOT-23	DBV	5	3000	210.0	185.0	35.0
TPS2041BDGNR	HVSSOP	DGN	8	2500	353.0	353.0	32.0
TPS2041BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2041BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2042BDGNR	HVSSOP	DGN	8	2500	353.0	353.0	32.0
TPS2042BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2042BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2042BDRBR	SON	DRB	8	3000	346.0	346.0	35.0
TPS2042BDRBT	SON	DRB	8	250	200.0	183.0	25.0
TPS2042BDRBTG4	SON	DRB	8	250	200.0	183.0	25.0
TPS2043BDR	SOIC	D	16	2500	353.0	353.0	32.0
TPS2044BDR	SOIC	D	16	2500	353.0	353.0	32.0
TPS2051BDBVR	SOT-23	DBV	5	3000	210.0	185.0	35.0
TPS2051BDGNR	HVSSOP	DGN	8	2500	353.0	353.0	32.0
TPS2051BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2051BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2052BDGNR	HVSSOP	DGN	8	2500	346.0	346.0	35.0



## PACKAGE MATERIALS INFORMATION

www.ti.com 17-Oct-2025

Device	Package Type	Package Drawing	Pins	SPQ	Length (mm)	Width (mm)	Height (mm)
TPS2052BDGNR	HVSSOP	DGN	8	2500	353.0	353.0	32.0
TPS2052BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2052BDR	SOIC	D	8	2500	353.0	353.0	32.0
TPS2052BDRBR	SON	DRB	8	3000	346.0	346.0	35.0
TPS2052BDRBT	SON	DRB	8	250	200.0	183.0	25.0
TPS2052BDRBTG4	SON	DRB	8	250	200.0	183.0	25.0
TPS2053BDR	SOIC	D	16	2500	340.5	336.1	32.0
TPS2054BDR	SOIC	D	16	2500	353.0	353.0	32.0
TPS2054BDRG4	SOIC	D	16	2500	353.0	353.0	32.0



## **PACKAGE MATERIALS INFORMATION**

www.ti.com 17-Oct-2025

## **TUBE**



\*All dimensions are nominal

Device	Package Name	Package Type	Pins	SPQ	L (mm)	W (mm)	T (µm)	B (mm)
TPS2043BD	D	SOIC	16	40	507	8	3940	4.32
TPS2043BD.A	D	SOIC	16	40	507	8	3940	4.32
TPS2044BD	D	SOIC	16	40	507	8	3940	4.32
TPS2044BD.A	D	SOIC	16	40	507	8	3940	4.32
TPS2044BDG4	D	SOIC	16	40	507	8	3940	4.32
TPS2053BD	D	SOIC	16	40	507	8	3940	4.32
TPS2053BD.A	D	SOIC	16	40	507	8	3940	4.32
TPS2054BD	D	SOIC	16	40	507	8	3940	4.32
TPS2054BD.A	D	SOIC	16	40	507	8	3940	4.32



Images above are just a representation of the package family, actual package may vary. Refer to the product data sheet for package details.

4203482/L





PLASTIC SMALL OUTLINE - NO LEAD



- All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.
- 2. This drawing is subject to change without notice.
- 3. The package thermal pad must be soldered to the printed circuit board for thermal and mechanical performance.



PLASTIC SMALL OUTLINE - NO LEAD



- 4. This package is designed to be soldered to a thermal pad on the board. For more information, see Texas Instruments literature number SLUA271 (www.ti.com/lit/slua271).
- Vias are optional depending on application, refer to device data sheet. If any vias are implemented, refer to their locations shown on this view. It is recommended that vias under paste be filled, plugged or tented.



PLASTIC SMALL OUTLINE - NO LEAD



NOTES: (continued)

6. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.



## D (R-PDS0-G16)

## PLASTIC SMALL OUTLINE



- A. All linear dimensions are in inches (millimeters).
- B. This drawing is subject to change without notice.
- Body length does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not exceed 0.006 (0,15) each side.
- Body width does not include interlead flash. Interlead flash shall not exceed 0.017 (0,43) each side.
- E. Reference JEDEC MS-012 variation AC.



3 x 3, 0.65 mm pitch


SMALL OUTLINE PACKAGE

This image is a representation of the package family, actual package may vary. Refer to the product data sheet for package details.



INSTRUMENTS www.ti.com






- 1. All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.

  2. This drawing is subject to change without notice.


  3. This dimension does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not
- exceed 0.15 mm per side.
- 4. This dimension does not include interlead flash. Interlead flash shall not exceed 0.25 mm per side.
- 5. Reference JEDEC registration MO-187.





- 6. Publication IPC-7351 may have alternate designs.
- 7. Solder mask tolerances between and around signal pads can vary based on board fabrication site.
- 8. Vias are optional depending on application, refer to device data sheet. If any vias are implemented, refer to their locations shown on this view. It is recommended that vias under paste be filled, plugged or tented.
- 9. Size of metal pad may vary due to creepage requirement.





- 10. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.
- 11. Board assembly site may have different recommendations for stencil design.



# PowerPAD<sup>™</sup> HVSSOP - 1.1 mm max height

SMALL OUTLINE PACKAGE



PowerPAD is a trademark of Texas Instruments.

- 1. All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.

  2. This drawing is subject to change without notice.

  3. This dimension does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not
- exceed 0.15 mm per side.
- 4. This dimension does not include interlead flash. Interlead flash shall not exceed 0.25 mm per side.
- 5. Reference JEDEC registration MO-187.





- 6. Publication IPC-7351 may have alternate designs.
- 7. Solder mask tolerances between and around signal pads can vary based on board fabrication site.
- 8. Vias are optional depending on application, refer to device data sheet. If any vias are implemented, refer to their locations shown on this view. It is recommended that vias under paste be filled, plugged or tented.
- 9. Size of metal pad may vary due to creepage requirement.






- 10. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.
- 11. Board assembly site may have different recommendations for stencil design.



# PowerPAD<sup>™</sup> VSSOP - 1.1 mm max height

SMALL OUTLINE PACKAGE




PowerPAD is a trademark of Texas Instruments.

- 1. All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.

  2. This drawing is subject to change without notice.


  3. This dimension does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not
- exceed 0.15 mm per side.
- 4. This dimension does not include interlead flash. Interlead flash shall not exceed 0.25 mm per side.
- 5. Reference JEDEC registration MO-187.
- 6. Features may differ or may not be present.





- 7. Publication IPC-7351 may have alternate designs.
- 8. Solder mask tolerances between and around signal pads can vary based on board fabrication site.
- 9. Vias are optional depending on application, refer to device data sheet. If any vias are implemented, refer to their locations shown on this view. It is recommended that vias under paste be filled, plugged or tented.
- 10. Size of metal pad may vary due to creepage requirement.





- 11. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.
- 12. Board assembly site may have different recommendations for stencil design.





SMALL OUTLINE INTEGRATED CIRCUIT



- 1. Linear dimensions are in inches [millimeters]. Dimensions in parenthesis are for reference only. Controlling dimensions are in inches. Dimensioning and tolerancing per ASME Y14.5M.
- 2. This drawing is subject to change without notice.
- 3. This dimension does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not exceed .006 [0.15] per side.
- 4. This dimension does not include interlead flash.
- 5. Reference JEDEC registration MS-012, variation AA.



SMALL OUTLINE INTEGRATED CIRCUIT



NOTES: (continued)

6. Publication IPC-7351 may have alternate designs.

7. Solder mask tolerances between and around signal pads can vary based on board fabrication site.



SMALL OUTLINE INTEGRATED CIRCUIT



- 8. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.
- 9. Board assembly site may have different recommendations for stencil design.





SMALL OUTLINE TRANSISTOR



- 1. All linear dimensions are in millimeters. Any dimensions in parenthesis are for reference only. Dimensioning and tolerancing per ASME Y14.5M.
  2. This drawing is subject to change without notice.
  3. Reference JEDEC MO-178.

- 4. Body dimensions do not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not exceed 0.25 mm per side.
- 5. Support pin may differ or may not be present.



SMALL OUTLINE TRANSISTOR



NOTES: (continued)

6. Publication IPC-7351 may have alternate designs.

7. Solder mask tolerances between and around signal pads can vary based on board fabrication site.



SMALL OUTLINE TRANSISTOR



- 8. Laser cutting apertures with trapezoidal walls and rounded corners may offer better paste release. IPC-7525 may have alternate design recommendations.
- 9. Board assembly site may have different recommendations for stencil design.



### IMPORTANT NOTICE AND DISCLAIMER

TI PROVIDES TECHNICAL AND RELIABILITY DATA (INCLUDING DATASHEETS), DESIGN RESOURCES (INCLUDING REFERENCE DESIGNS), APPLICATION OR OTHER DESIGN ADVICE, WEB TOOLS, SAFETY INFORMATION, AND OTHER RESOURCES "AS IS" AND WITH ALL FAULTS, AND DISCLAIMS ALL WARRANTIES, EXPRESS AND IMPLIED, INCLUDING WITHOUT LIMITATION ANY IMPLIED WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR NON-INFRINGEMENT OF THIRD PARTY INTELLECTUAL PROPERTY RIGHTS.

These resources are intended for skilled developers designing with TI products. You are solely responsible for (1) selecting the appropriate TI products for your application, (2) designing, validating and testing your application, and (3) ensuring your application meets applicable standards, and any other safety, security, regulatory or other requirements.

These resources are subject to change without notice. TI grants you permission to use these resources only for development of an application that uses the TI products described in the resource. Other reproduction and display of these resources is prohibited. No license is granted to any other TI intellectual property right or to any third party intellectual property right. TI disclaims responsibility for, and you fully indemnify TI and its representatives against any claims, damages, costs, losses, and liabilities arising out of your use of these resources.

TI's products are provided subject to TI's Terms of Sale, TI's General Quality Guidelines, or other applicable terms available either on ti.com or provided in conjunction with such TI products. TI's provision of these resources does not expand or otherwise alter TI's applicable warranties or warranty disclaimers for TI products. Unless TI explicitly designates a product as custom or customer-specified, TI products are standard, catalog, general purpose devices.

TI objects to and rejects any additional or different terms you may propose.

Copyright © 2025, Texas Instruments Incorporated

Last updated 10/2025